

## > Power Team

**Professional Grade High Performance Hydraulic Products, Systems and Tools** 



HYDRAULIC PUMPS - CYLINDERS - JACKS - PULLERS - TOOLS



INFRASTRUCTURE | PROCESS SOLUTIONS | DIAGNOSTIC SYSTEMS

#### **Our Company**

**POWER TEAM** is a product brand of **SPX**, a global, Fortune 500, multi-industry company with more than \$5 billion in annual revenue based in the United States in Charlotte, North Carolina.

SPX is a manufacturing leader with operations in more than 35 countries and approximately 18,000 associates worldwide, bringing to market solutions that benefit society while delivering value-added, bottom-line results to customers across five broad-based categories: power and energy, vehicle and transit, infrastructure, food and beverage and industrial processes. SPX is traded on the New York Stock Exchange.

#### **Global Reach**

An expanding world population and emerging middle class are driving increased demand for energy and high quality food. SPX is a leading global supplier of engineered technologies that support these critical needs of modern societies, providing innovative solutions to the worldwide food and beverage and power and energy markets. With a market presence that spans the globe, SPX has operations in more than 35 countries and more than 50 percent of our annual revenue is generated outside North America.

#### **SPX Brands**

Wherever and whenever companies have critical business needs, there is an SPX brand ready to help meet the challenge.

SPX markets more than 100 brands around the world. These brands serve a wide range of markets — automotive, oil and gas, power and utilities, food and beverage, broadcast and telecommunications, mining, pharmaceutical, HVAC and more.

Many are widely recognized, well-respected names across many industries and are considered category leaders.

SPX, a Global, Multi-Industry Supplier of Engineered Solutions driven by Innovation in the following segments:-

#### > Thermal Equipment

- with an emphasis on power and energy.
- meeting demands for increased power generation from multiple sources.

#### > Flow Technology

• focused largely on food and beverage and other power and energy applications.

#### > Industrial Products and Services

- focused on power and energy and niche segments.
- developed reliable technologies, components and equipment in **infrastructure** building and offered efficient solutions in **industrial processes**.

SPX Hydraulic Technologies is part of SPX Corporation.

NYSE symbol: **SPW** 

spx.com

**SPX HYDRAULIC TECHNOLOGIES** is a unit of SPX Corporation (U.S.A.), and a global manufacturer & sole owner of the **POWER TEAM** trade mark with over 85 years' experience in high performance, professional grade, 10,000psi (700bar) high-pressure hydraulic cylinders, pumps, pullers, jacks, tools & equipment.

**POWER TEAM** products are used throughout the world serving a broad range of customers for applications in industry, construction, bridge equipment manufacturers, mining, rigging, quarrying, steel mills, shipbuilding/repairing, marine projects, oil & gas, power plants, maintenance & repair (MRO), aerospace and many other industries requiring hydraulic & maintenance tools.

**SPX - POWER TEAM** is a well-renowned and one of the top leading brand in high pressure hydraulic tools & equipment serving industrial customers worldwide fully backed by our 'Lifetime Marathon Warranty'.

- Our head office & U.S. manufacturing facility is located at 5885 11th Street, Rockford, Illinois 61109, U.S.A.
- Our SPX brand torque wrenches, bolt tensioners & nut splitters are manufactured by our factory in U.K.
- Our SPX global sales and distribution centers are strategically located in U.S.A., the Netherlands, Singapore & China.

#### Quality

SPX maintains high-quality standards in all phases of design, procurement, manufacturing, sales and service of **POWER TEAM** brand solutions. We are committed to continuous quality improvement, customer satisfaction and the reduction of total costs, and regularly employ innovation, efficiency and in-depth multi-industry knowledge to meet our customers' specific needs. **POWER TEAM** is certified to the **ISO 9000 Quality Management system**.

#### **World-wide Distribution Network**

The **POWER TEAM** brand is sold through a worldwide network of stocking industrial distributors. Service is available throughout the world at authorized Power Team Hydraulic Service Centers.

For more details of our company & businesses, please refer to the following websites:-

**SPX Corporation:** 

www.spx.com

SPX Hydraulic Technologies (Business Unit):

www.spxhydraulictech.com

#### **Product Groups**



Existing Brand Identity

**POWER TEAM®** 

New Brand Identity



Professional Grade High Performance Hydraulic Products, Systems and Tools.

www.powerteam.com



## >Bolting Systems®



Topside & Subsea Hydraulic Torque Wrenches, Bolt Tensioners & Nut Splitters for Oil & Gas and Power Generation Industries.







Hydraulic Torque Wrenches, Bolt Tensioners (Foundation & Up-Tower) & Electric Pumps specially for Wind Power Applications.



#### **Hydraulic Pumps**

- Electric, Air, and Gas Powered
- Hand Pumps
- Valves, hoses and accessories

#### **Hydraulic Cylinders**

- Rams
- Standard
- Construction
- Industrial
- High Tonnage
- Pancake
- Aluminum
- Pulling

#### Jacks

- Lifting Jacks
- Inflatable Jacks
- Post-Tensioning Jacks

#### **Tools**

- Torque Wrenches
- Hydraulic Presses
- Flange Spreaders
- Nut Splitters
- Gear Pushers/Pullers
- Bearing Maintenance Pushers/Pullers

#### **Shop Equipment**

- Shop Presses
- Floor Cranes
- Load Rotors

Power Team. Over 85 years experience in supplying Professional Grade high-pressure Hydraulic Pumps, Cylinders, Jacks, Pullers & Tools.

#### A Heritage of Innovation

Since 1924, we've been instrumental in the development of innovative high force hydraulic power products, systems and tools. And many of our products are known as the industry standard for rugged construction, reliability, and long service life. Today, we provide a full range of professional grade products and services around the globe.

#### **Power Team Quality**

Power Team Products are built tough with strict ISO 9000 manufacturing processes and are covered by a Lifetime Marathon Warranty\*. Power Team is registered for the coveted ISO 9001: 2000 international quality standard.

#### Global Distribution and Service

Wherever your job is in the world, the Power Team network of distributors and service centers assures local product, parts and service availability.

\*See Warranty page for coverage details. (See page 163)

Tonnages are specified as U.S. Short Tons in this catalogue unless otherwise stated.

(1 U.S. Short Ton = 0.907 Metric Tonne)

Every effort has been made to assure the accuracy of product descriptions in this catalogue at the time of printing. SPX Hydraulic Technologies reserves the right to modify or discontinue products without prior notice.

## > Power Team®

PROFESSIONAL HYDRAULIC PUMPS, CYLINDERS, JACKS, PULLERS & TOOLS



CYLINDERS 8-32





PUMPS 33-67





HYDRAULIC ACCESSORIES 68-84







SHOP EQUIPMENT 85-93







JACKS 94-105





**SEAL KITS** 160-161

PLC SYNCHRONOUS LIFT AND LOWERING

SYSTEM...156



HYDRAULIC & MECHANICAL TOOLS 106-127





PULLERS 128-155









CONSTRUCTION PROJECTS 156-159



### **NUMERIC INDEX**

DD1/00 DD1/01 122	DE20 C 112	97	209290 209292 15	250000 105	0100	75
	PE39 Series112 PE45 Series114	87 SPE256 - SPE2514DS	208380 - 20838215 208627138	350090105 350094 - 35010014		
BC212 - BC212EUR49 BP12INT49		88		350144, 35014513, 23	,	
C51C - C10010C13		SPE556 - SPE5513DS	209199, 20920064	35018414		
C55CBT - C2514CBT		89		350207 - 350209105	*	
32	PG303 - PG55461 PG1200M-4 - PG1204S	SPE10010 - SPE10013DS		350320 - 35033217	9512, 9513	
CB30 - CB10017		90	21669 - 2187320	35037613, 21	9515	
CBS55 - CBS200100	63 PG4004, PG4004S63	SPE10010R90		35043166		
CBS6099	,		22274. 2227520	350549, 350550119		
CC5 - CC25 123	PH53C, PH53CR142 PH63C - PH113C140		24196, 2419720	350593 - 350594152	9519	
DG100, DG100B73			,	350637152		
FC2200 - FC440091	PH172 - PH503143		24832, 24833135	350723 - 35072414	9521	
FK59 - FK159B39	PH303C140	SPM25688		350822, 350823119	9552	
HB443, HB44447	PH553C - PH553CL13	SPM256C86		350895 - 35089815		
HFS3A - HFS6A119	152	SPM251488	250341 - 250343105	35098421		
HNS150 - HNS225118		SPM556, SPM5513 89	250353105	35107532	, ,	
HP35, HP35SP120		SPM1001090	250459120	35110632		
HS2000 - HS3000121		SS2138	250682105	351324, 35132523		
HST11141	PMA355 - PME355S	TWLC2 - TWLC30 110	251002152	35133423	· · · · · · · · · · · · · · · · · · ·	
HST11S140		TWSD1 - TWSD25 108		35157413		
HT50A - HT200124		TWD1-063-	<i>'</i>	351575 - 35157615		
HTS50126		TWD25-275109		351927 - 35193199	9596, 9597	
IJ13 - IJ7320105		TWS Series109	25166064	351953, 35195499	9599, 9605	
IM10E, IM10H103	144-145	TWH15 - TWH50112	252364, 252365112	351985118	,	
IPS10M, IPS17M136		TWLC Series 110-111	252511, 25251266	36578138	9616	
IPS17 - IPS17H146	58-59	1020 - 1042133		37045125	9617	
IPS30H147		1057 - 1060142		38855, 38904	9620	
IPS3017 - IPS3017B148	PR2100J Thru PR3100S	1062144		38908, 3890915	9623	
IPS5017 - IPS5017B149	154-155	1064, 1066143		39811126		
IPS50H147		1070145		41331138		
IPS5317150	R1002D - R56512D	1074143		420059 - 42006414	9631	
J24T - J259T97	26-27	1076145		420866 - 42087125, 29	9633	
JAM10033 - JEM15026	R552L - R56512L	1080143		421056, 421057		
JM25 - JM430100-101	28-29	1046164		44148, 44195138	9636 - 9640	
K82, K83141	RA202 - RA100621	1100 - 1111134		44745, 44766153		
LR2000 - LR6000 91	RA556L, RA1006L 30	1121 - 1128135		45329126	9642	
MB5 - MB16151	RB8013S - RB20013S	1130135	302482, 30248320	4558917	9643	
P12 - P59F37-38	92-93	1150 - 1154135	· · · · · · · · · · · · · · · · · · ·	47997142		
P19, P19L, P59, P59L38		1155 - 1158 139				69
P157 - P460D39		1165, 1166135		6084686		
		· ·	307159105			
PA9, PA9H43			307281125			
PA50 - PA50RM 46	RH121T18	1188141	308022118	7103126	9692 - 9705	75
PA60, PA6442	RH306D19	1266127		7136139		
PA60A Series 116-117	RHA30618	10494 66	308440OR9146-150	7162 - 7168127	9733 - 9783	70
PA172 - PA55444-45	RHA604D19	10672112	308840118	7307 - 7309127	9758, 9763	.102
PB1230C - PB51156C	RLS50 - RLS1500S16	12740112	309652, 30965364	7312126	9765 - 9775	70
151	RP20 - RP10467	15235105	31772, 3177615	7395126	9785 - 9788	125
PC200, PC200RC 67	RP25, RP5532	1633966	32054138	7400, 7401127	9792 - 9800	71
PD313 - PD812120	RSS101 - RSS250317	1762764	3211820	7402126	981	138
PE102 - PE104 48	RT172 - RT100420	201454, 20192320	3232515	7420, 7421127		
PE172 - PE174M50	RV21278 - RV21278-90	202178 - 20218014	32698 - 3343920	8000 - 8076137		
PE182 - PE184C51	83	202777, 20277864	3344A126	885127		
PE213 - PE214S 52	RWP55, RWP55-4115		33856 - 33865138	927 - 939134		
PE302 - PE304R-2 54	SF5089, 92					
PE462 - PE464S55			3425118			
PE55TWP - PE55TWP-4	SJ2010 - SJ3010P102	204666126	34331138	9006X - 9015X96		
113		204928127		9105A96		
PE552 - PE554T56-57	SPA256, SPA2514 88		3475820			
PE554W56-57			34698138			
PE4004, PE4004S60	SPE1010, SPE1010D	20776266	34755, 3475620	9205A <b>-</b> 9220A96		

### **ALPHABETICAL INDEX**

Α.
Adapters, Step Plate137
Adapters, Threaded
(Puller)137 Air/Hydraulic Pumps40-46
Aluminum Cylinders21, 30
Attachments, Pulling135
Axle Journal Roller Bearing
Service Equipment154-155
Band Breaker 122
Bead Breaker
Bearing Installer154-155
Bearing Pulling
Attachments
Blankets, Protective151
Blind Hole Puller Set138
C
Casters66, 151
Center-Hole
Cylinders
C-Clamps123
Center-Hole Twin Cylinders20
C-Frame Press
Chaser, Thread126
Compact Electric/Hyd TW Pumps
112
Counter-balance Valve82 Couplers, Hydraulic71
Cranes, Mobile 91
Cribbing Block Sets 17, 100
Cylinders, High Tonnage24-29
Cylinders, Hydraulic11-32 Cylinders, Locking Collar
28-31
Cylinders Pancake31
D Digital Pressure Gauge73
Double-Acting Cylinders
19, 22-23, 26-27
E
Electric/Hydraulic
Pumps
"Enforcer 55" Hydraulic Puller152
"Enforcer 100"
Hydraulic Puller153
F
Fixtures, Straightening 89-90, 92
Flange Spreaders
Flow Characteristics, Valves
Fluid Level &
Temperature Gauge
Forcing Presses85-90, 92-93
G
Gauges, Hydraulic
Pressure72-73
Gear and Pulley
Pullers
Head Inserts, Cylinder18, 20
11cas 111501ts, Cyllinder10, 20

Hexagon Drives
Hydraulic Pumps
Hydraulic Tester Accessories125 Hydraulic Tools106-125 Hydraulic Valves Pump Mounted78-81, 84 In-Line82-83
I Impact Sockets
Attachments
Jack Modules       100-101         Jacks, High-Tonnage       98-101         Jacks, Hydraulic       95-97         Jacks, Hydraulic Toe       97         Jacks, Inflatable       104-105         Jacks, Stressing       102         Jimmy Bars       127
L Lightweight Handpump
M         Magnetic Pick-Up Tool       126         Magnetic Strip       66         Maintenance Sets       103         Manifolds       74         Mechanical Tools       126-127         Metering Valve       82-83         Mini Jack       96         N         Nut Splitters       118
Oil, Hydraulic

P
Pancake Cylinders31
Photo Tachometer, Digital 126
PLC Synchronous Lift
Positioning Slings
Presses, Hydraulic
Roll-Bed92-93 Presses, Hydraulic Shop
85-90, 92-93
Pressure Gauges, Hydraulic72-73
Pressure Switches
Protective Blankets151 Pry Bars127
Puller Adapters137
Puller Attachments
Puller, Blind Hole138 Pullers, Bearing133-150, 152-155
Pullers, Bearing Cup135
Pullers, Gear133-150, 152-153
Pullers, Hydraulic140-150, 152-153
Pullers, Internal
Pullers, Jaw-Type
133, 136,
140, 142-143, 146-150, 152-153 Pullers, Pulley135
Pullers, Sets136, 146-150
Pullers, Slide Hammer138-139
Pulley Pullers
Pump Accessories,
Hydraulic64-67
Pump Cart67 Pump Mounted Valves 78-81, 84
Pump Reservoirs67
Pumps, Hydraulic33-63
Pumps, Hydraulic, Air40-46
Pumps, Hydraulic, Electric48-60 Pumps, Hydraulic, Gasoline61-63
Pumps, Hydraulic, Hand37-39
Pumps, Torque Wrench112-117
Punches, Hydraulic120 Push-Pullers, Hydraulic144-145
Push-Pullers, Mechanical133
0
Quality Standards, Industry162
Quarter Horse Pumps48-49
"Quiet" Pumps58-59
Railroad Axle Journal Bearing
Service Equipment154-155
Ratcheting Chain Wrenches127
Reaction Arms, Torque Wrench
Reservoir Breather Kit66
Rethreading Tools126
Roll-Bed® Presses92-93
Seal Kits66, 160-161
Shaft Protectors137
Shop Presses85-90, 92-93
Shorty Cylinders17
Slide Hammer Pullers138-139 Slings, Load-Positioning91
Sockets (Torque Wrench)109
Solenoid-Operated
Valves80-81 Spanner Wrenches127
Spanner Trienenco127

Spreaders, Hydraulic119, 121 Square Drive
Torque Wrenches108-109
Stage Lift157
Standards, Quality162
Step Plate Adapters137
Storage Boxes,
Puller Sets 151
Straightening Fixtures89-90, 92
Straightening Tool140-141
Stressing Jacks and Pumps56-57, 102
Subplates, Pump65
Switches, Hand and Foot64
Synchronous Lift
•
Testers, Hydraulic System124-125
Temperature &
Fluid Level Gauge66
Thread Chaser126
Threaded Adapters, Puller137
Tire Removing Tool122
Toe Jacks, Hydraulic97
Tools, Hydraulic106-125
Tools, Mechanical126-127
Torque Wrench Pumps112-117
Torque Wrench 107-111 Torque Wrench Links 111
Torque Wrench Sockets
Torque Wrench
Low Clearance110-111
Torque Wrench Reducers111
Twin Hose (for Torque Wrench)
U
Universal Pullers152-153
V
V-Belt Pulley Pulling
Attachments135
Valves, Hydraulic
Pump Mounted78-81, 84
In-Line
Viton Seal Kits66, 160-161
W
Warranty163
Wrenches, Industrial127
Wrenches, Ratcheting Chain127
Wrenches, Spanner127 Wrenches, Torque107-111
**Tenenes, Torque10/-111

## CYLINDER

#### SELECTION

Choosing The Right Cylinder

**Step 1** Select the hydraulic cylinder that best suits the application (See page 11-32).

**Step 2** Select the hydraulic pump, with valve option, that best matches the cylinder and application (See page 33-67).

**Step 3** Select the hydraulic accessories you need (See page 68-84).

#### **CONSIDERATIONS:**

- 1. What push or pull tonnage is required per cylinder in your application? (Rule of thumb; Always choose a cylinder with a tonnage rating of 20% or more than what is required to lift the load.)
- 2. What is the push or pull stroke length required?
- 3. Does the cylinder need to push, pull or both?
  (Single-acting cylinders extend the piston under hydraulic pressure; double-acting cylinders extend and retract the piston under pressure.)
- 4. Does the application require multiple cylinders?
- Is the application stationary, or must the components be light in weight for easy portability?
- 6. Do you need to extend a rod or cable through the center of the cylinder for the application, as in a tensioning operation?
- 7. Does the application require that the cylinder fit within limited-clearance work areas?

- 8. Does the application require that the cylinder be "dead-ended" at the end of it's work stroke?
- Will the cylinder need to withstand off-center loads? Cylinders with swivel caps are available.
- 10. Does the application require that the lifted load be supported for extended periods of time? Locking collars are ideal for such jobs, as are cribbing blocks.
- 11. Is corrosion resistance required? Our unique "Power Tech" surface treatment is standard on many Power Team cylinders, and optional on many of our cylinders which feature steel construction.
- 12. Will the application involve high cycles (over 2,500 in the cylinders lifetime)? Our "RD", "RH", "RP" and "C" series cylinders are ideal choices.

## ONLY POWER TEAM PROVIDES THE "POWER TECH" SURFACE TREATMENT:

- High corrosion and wear resistance, anti-galling properties.
- Significantly increases the life expectancy of a cylinder.
- Retains lubricants, prevents bronze and other materials from sticking to surface.
- Increases fatigue strength and impact strength.
- Increases surface yield and tensile strength.
- Provides improved abrasion and scratch resistance.
- Causes no appreciable dimensional change.
- 56 Rc minimum surface hardness.
- Passes ASTM B117-85 100 hour salt spray corrosion resistance tests.

The "Power Tech" surface treatment is standard on the gland nut, cylinder body and piston/piston rod of the following cylinders: RLS50, RLS100, RLS200, RLS300, RLS500S, RLS750S, RLS1000S, RLS1500S, and RSS1002.

NOTE (1): "Bronze plating" may be used in place of the "Power Tech" surface finish for the piston/piston rod of any of the above cylinders. The "Power Tech" surface treatment is standard on the standpipe of all "RH" series single and double-acting cylinders. The "Power Tech" surface treatment is standard on the piston/piston rod of the RT172, RT302 and RT503 cylinders.

NOTE (2): "QPQ-coated" may be used in place of "Power Tech" surface finish for the piston/piston rod & body of selected cylinders. The "QPQ-coated" surface provides higher resistance to abrasion and reduce friction, prolonging cylinder life and quality.

#### WHAT TYPE OF CYLINDER DO YOU NEED?

1. To determine a cylinder's force capacity:


Cylinder Pressure from FORCE Effective Area Pump (kg) (cm<sup>2</sup>) (kg/cm<sup>2</sup>)

2. To determine oil capacity of a cylinder:

OIL Cylinder Cylinder CAPACITY = Effective Area Štroke (cm<sup>2</sup>) (cm3) (cm)

3.To determine reservoir capacity needed for a multiple cylinder system:

Number Oil Cap. **USABLE** of Cyl. of Cyl. in OIL (cm³) System



Note: For double-acting cylinders, oil in rod end of cylinder must be subtracted to determine capacity.

4. To determine no. of strokes of a handpump:

Cylinder Effective Area (cm²) x Stroke (cm) Pump Displacement (cm³/stroke)

5. To determine piston travel rate (cm/min) of a power-driven pump:

Pump Oil Flow (cm3/min) Cylinder Effective Area (cm²)

6.Time (min) taken to move cylinder piston to full stroke of a power-driven pump:

Total Cylinder Displacement (cm3) Pump Displacement (cm³/min)

Conversion Volume: 1 litre

 $= 1000 \text{ cm}^3$ 1 U.S. gallon = 231 in<sup>3</sup> = 2,000 lbsMass: 1 short tons 1 metric tonne = 2204.6 lbs

1 metric tonne = 1000 kg Pressure: 10,000 psi = 689 bar  $= 703 \text{ kg/cm}^2$ 

**Metric to Imperial Conversion** 

Lenath: 1 mm = 0.0394 inArea: 1 cm<sup>2</sup>  $= 0.1550 \text{ in}^2$  $= 0.06102 \text{ in}^3$ Volume: 1 cm<sup>3</sup> Volume: 1 litre = 0.2642 U.S. gallon Mass: 1 kg (10N) = 2.2046 lbPower: 1 kW = 1.341 hp

Pressure: 1 kg/cm<sup>2</sup> = 14.219 psiPressure: 1 bar = 14.5038 psi = 0.7376 ft.lb Torque: 1 Nm

## **Torque & Puller**

### **Choosing the Right Tool**

Tool

#### The Questions you need to ask.

- 1. Are there work area space/access issues or tool size limitations?
- 2. How far from the stationary object will the reaction arm be placed? (Reaction arm must rest against stationary object for support)
- **CHOOSING THE RIGHT TORQUE WRENCH**
- 3. Single acting or double acting tool? 4. What size bolts need to be loosened or tightened?
- 5. What is torque requirement for the application?
- 6. Based on torque value, how much pressure required? (pressure setting for pump)
- 7. What type of pump to power the tool electric, air, hand?

#### **CHOOSING THE RIGHT PULLER**

- 1. Mechanical puller or hydraulic puller? (page 133-136 and page 140-153)
- 2. Does the job require a two jaw puller or a three jaw puller?
- 3. How much force is needed to complete the pull?
- 4. How much reach is needed?
- 5. How much spread is needed?





## HYDRAULIC CIRCUITS


Pumps, Cylinders,
Controls

These are just a few basic systems possible with Power Team hydraulic components. Countless applications are possible: In presses, for lifting or jacking applications or in production or maintenance setups. The pump shown is a typical handpump or electric/hydraulic unit. Air or gas driven/hydraulic pumps are available.

- Cylinder applies hydraulic force.
- Pump a device for converting mechanical energy to fluid energy.
- Directional valve controls the direction of hydraulic fluid in the system.
- Gauge measures Bar pressure (or Psi-Pounds per Square Inch) and/or force.
- Hose transports hydraulic fluid.
- Manifold allows distribution of hydraulic fluid from one source to several cylinders. (No. 9617)
- Swivel Connector allows proper alignment of valves and/or gauges. Used when units being connected cannot be rotated. (No. 10469)
- Quick Coupling "hose half" and "cylinder half" couplings are used for quick connection and fluid flow check when separated. (No. 9797 and 9798)
- 9 Shut-Off Valve regulates the flow of hydraulic fluid to or from cylinders. (No. 9642 or 9644)
- Load-Lowering Valve allows metered lowering of cylinder and provides safety when prolonged load holding is required. (No. 9596)
- Tee Gauge Adapter allows for installation of pressure/tonnage gauge anywhere in the hydraulic system. (No. 9670)
- Pipe Plug for blocking unused ports within the system. (No. 10909)







FROM 2 TO 1,140 U.S. SHORT TONS **SUPERIOR FEATURES OF POWER TEAM HYDRAULIC CYLINDERS:** 

We build our own cylinders in our ISO 9001 registered manufacturing facility. All Power Team cylinders are date-coded. Maximum pressure rating and capacity are stamped on the cylinder. All cylinders comply to the demanding ASME B30.1 standard and are proof tested to 125% of capacity before leaving our factory. Some other features included:

- · Cylinder bores are roller burnished to harden the surface and make it smoother, increasing seal life by
- · Base mounting holes withstand full capacity of the cylinder.
- Typical cylinder burst pressures range from 1700 to 2400 bar.
- · Cylinders with gland nuts may be "dead-ended" at 700 bar. Cylinders
- are assembled and tested by certified assemblers.
- Eddy current and mag particle inspection detects flaws in the steel.
- · Cylinder bodies are solid steel, not welded like some competitive cylinders.
- · Material is removed from surface, to assure that any flaws are removed.



Page **C SERIES...12-15** 

General Purpose Cylinders & Mounting Accessories



Page RD SERIES...22, 23

> Double-Acting. Hvdraulic-Return

> > Page

Page

Page



Page **RLS SERIES...16** 

Low Profile Cylinders



R SERIES...24-27

Single-Acting, Load Return Double-Acting, Hydraulic Return



Page RSS SERIES...17 **Shorty Cylinders** 



Page RL SERIES...28-30

Locking Collar (Steel) Single-Acting, Load-Return (Aluminum) Single-Acting, Spring-Return



Page **RH SERIES...18-19** 

Center Hole Cylinders



PLC SERIES...31

Locking Collar, Pancake Single Acting, Load-Return



Page RT SERIES...20

Center Hole Power-twin® Cylinders



CBT SERIES...32

Threaded End Cylinders



RA SERIES...21



Page RP SERIES...32 Pull Cylinders



#### **GENERAL PURPOSE**

**C** Series Cylinders 5 - 100 Ton Single-Acting, Spring-Return 700 bar (10,000 psi)




## RUGGED, HIGH QUALITY CYLINDER USED FOR LIFTING AND PRESSING

- Aluminum bronze bearing reduces wear caused by off-center loads.
- Maximum sized springs speed piston return and increase spring life.
- Solid steel cylinder body for durability.
- Chrome plated / Nickel plated piston rod resists wear and corrosion.
- Wide range of accessories available to thread onto piston rod, collar, or onto cylinder base (See page 14, 15).
- Base mounting holes standard on 5 through 55 ton cylinders; optional on 75 and 100 ton cylinders.
- A 3/8" NPTF female half coupler is standard.




C106C





Base mounting holes



#### **BASE MOUNTING HOLES FOR "C" CYLINDERS**

Cylinder Tonnage	No. Holes	Thread Size	Thread Depth (mm)	Bolt Circle Diameter (mm)	
5		1/4-20	9.5	25.4	
10	2†	<sup>5</sup> ⁄16-18	12.7	39.7	
15		<sup>3</sup> ⁄ <sub>8</sub> -16	12.7	47.6	
25		1/2-13	19.1	58.7	
55		72 <del>-</del> 13		95.3	
*Optional 75	4	<sup>3</sup> ⁄4-10	25.4	114.3	
*Optional 100	4	1-8	20.4	120.7	

<sup>\*</sup> Consult Factory (45° from coupler)

<sup>† 90°</sup> from coupler.




		Swivel Contional	_	
Cylinder Tonnage		A (mm)	B (mm)	
10 or 15	350144	22,4	30,1	
25	350145	28,7	50,8	
55 or 75	350376	31,8	71,4	

48,5

88,1

100 **351574** 






CYLI
N D
ERS
<b>"</b>


				A	В	C	D	E Piston	F	н	J Piston	K			Metric		
				Re-	Ex-				Rase	Piston		Rod		Cylinder	Tons	_	
Cyl.			Oil	tracted		Outside	Collar	Thread		Rod		Protru-	Bore	Effective	at		
Cap.	Stroke	Order	Cap.	Height	Height	Dia.	Thread	Length		Dia.	and Depth	sion	Dia.	Area	700	Weight	
(Tons)	(mm)	No.	(cm³)	(mm)	(mm)	(mm)	(in.)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(cm²)	(bar)	(kg)	
, ,	25,4	C51C	18	110,3	138,1	38,1	11/2-16	28,6	19,1	25,4	<sup>3</sup> /4-16 x 15,9	6,4	28,6	6,4	4,5	1,0	
	82,6	C53C	52	165,1	247,7	38,1	1 <sup>1</sup> /2-16	28,6	19,1	25,4	<sup>3</sup> /4-16 x 15,9	6,4	28,6	6,4	4,5	1,5	
(JI	133,4		85	215,9	349,3	38,1	$1^{1}/2-16$	28,6	19,1	25,4	<sup>3</sup> /4-16 x 15,9	6,4	28,6	6,4	4,5	1,8	
	184,2		118	273,1	457,2	38,1	1 <sup>1</sup> /2-16	28,6	19,1	25,4	<sup>3</sup> /4-16 x 15,9	6.4	28,6	6,4	4,5	2,3	
	235,0		151	323,9	558,8	38,1	$1^{1}/2 \cdot 16$	28,6	19,1	25,4	<sup>3</sup> /4-16 x 15,9	6,4	28,6	6,4	4,5	2,6	
	25,4	C101C	36	92,1	117,5	57,2	2 <sup>1</sup> / <sub>4</sub> -14	28,6	19,1	38,1	1-8 x 19,1	6,4	42,8	14,4	10,2	1,8	
	54,0	C102C	79	120,7	174,6	57,2	21/4-14	28,6	19,1	38,1	1-8 x 19,1	6,4	42,8	14,4	10,2	2,3	
		C104C	151	171,5	276,2	57,2	21/4-14	28,6	19,1	38,1	1-8 x 19.1	6,4	42,8	14,4	10,2	3,0	
		C106C	225	247,7	403,2	57,2	21/4-14	28,6	19,1	38,1	1-8 x 19,1	6,4	42,8	14,4	10.2	4,3	
10		C108C	362	298,5	504,8	57,2	21/4-14	28,6	19,1	38,1	1-8 x 19,1	6,4	42,8	14,4	10,2	5,0	
		C1010C	370	349,3	606,4	57,2	$2^{1}/4-14$	28,6	19,1	38,1	1-8 x 19,1	6,4	42,8	14,4	10,2	5,9	
		C1012C	444	400,1	708,0	57,2	$2^{1}/4-14$	28,6	19,1	38,1	1-8 x 19,1	6,4	42,8	14,4	10,2	6,6	
		C1014C	518	450,9	809,6	57,2	21/4-14	28,6	19,1	38,1	1-8 x 19,1	6,4	42,8	14,4	10,2	7,3	
		C1016C	592	520,7	927,1	57,2	2 <sup>1</sup> /4-14	28,6	19,1	38,1	1-8 x 19,1	6,4	42,8	14,4	10,2	8,4	
	25,4	C151C	51	123,8	149,2	69,9	23/4-16	28,6	19,1	44,5	1-8 x 19,1	6,4	50,8	20,3	14,2	3,4	
	54,0	C152C	110	149.2	203,2	69,9	2 <sup>3</sup> /4-16	28,6	19,1		1-8 x 19,1	6,4	50,8	20,3	14,2	4,0	
		C154C	211	200,0	304,8	69,9	23/4-16	28,6	19,1	44,5	1-8 x 19,1	6,4	50,8	20,3	14,2	5,2	
		C156C	315	271,4	427,0	69,9	23/4-16	28,6	19,1	44,5	1-8 x 19,1	6,4	50,8	20,3	14,2	6,9	
15		C158C	418	322,2	528,6	69,9	23/4-16	28,6	19,1		1-8 x 19,1	6,4	50,8	20,3	14,2	8,1	
OI -		C1510C	521	373 ,0	630,2	69,9	23/4-16	28,6	19,1		1-8 x 19,1	6,4	50,8	20,3	14,2	9,4	
		C1512C	625	423,8	731,8	69,9	23/4-16	28,6	19,1	44,5	1-8 x 19,1	6,4	50,8	20,3	14,2	10,5	
		C1514C	728	474,6	833,4	69,9	23/4-16	28,6	19,1		1-8 x 19,1	6.4	50,8	20,3	14,2	11,8	
		C1516C	824	522,3	928,7	69,9	23/4-16	28,6	19,1	44,5	1-8 x 19,1	6,4	50,8	20,3	14,2	12,8	
	25,4	C251C	84	139,7	165,1	85,7	3 <sup>5</sup> / <sub>16</sub> -12	49,2	25,4		1 <sup>1</sup> / <sub>2</sub> -16 x 25,4		65,1	33,2	23,4	5,4	
	50,8	C252C	169	165,1	215,9	85,7	3 <sup>5</sup> /16-12	49,2	25,4		1 <sup>1</sup> / <sub>2</sub> -16 x 25,4		65,1	33,2	23,4	6,3	
		C254C	338	215,9	317,5	85,7	3 <sup>5</sup> / <sub>16</sub> -12	49,2	25,4		1 <sup>1</sup> / <sub>2</sub> -16 x 25,4		65,1	33,2	23,4	8,0	
N		C256C	528	273,1	431,8	85,7	3 <sup>5</sup> / <sub>16</sub> -12		25,4		1 <sup>1</sup> / <sub>2</sub> -16 x 25,4		65,1	33,2	23,4	9,8	
25		C258C	697	323,9	533,4	85,7	3 <sup>5</sup> /16-12	49,2	25,4		1 <sup>1</sup> / <sub>2</sub> -16 x 25,4		65,1	33,2	23,4	11.6	
		C2510C	865	374,4	635,0	85,7	3 <sup>5</sup> /16-12	49,2	25,4		1 <sup>1</sup> / <sub>2</sub> -16 x 25,4		65,1	33,2	23,4	13,3	
		C2512C	1.036	425,5	736,0	85,7	3 <sup>5</sup> / <sub>16</sub> -12	49,2	25,4		1 <sup>1</sup> /2-16 x 25,4		65,1	33,2	23,4	15,0	
		C2514C	1.205	476,3	838,2	85,7	3 <sup>5</sup> /16-12	49,2	25,4	1	1 <sup>1</sup> / <sub>2</sub> -16 x 25,4		65,1	33,2	23,4	16,7	
			362	174,6	225,4	127,0	5-12	55,6	34,9		None	3,2	95,3	71,2	50,1	14,7	
		C554C	769	231,8	339,7	127,0	5-12	55,6	34,9	79,4	None	3,2	95,3	71,2	50,1	18,7	
51		C556C	1.131	282,6	441.3	127,0	5-12	55,6	34,9	79,4	None	3,2	95,3	71,2	50,1	23,1	
(JI		C5510C	1.853	384,2	644,5	127,0	5-12	55,6	34,9		None	3,2	95,3	71,2	50,1	30,4	
				460,4	796,9			55,6		79,4	None		95,3	71,2	50,1	35,3	
		C756C	1.596		469,9	146,1		44,5		95,3	None		114,3		72,1	33,3	
75		C7513C	3.421	492,1	825,5	146,1		44,5		95,3	None		114,3		72,1	49,6	
		C1002C	675	219,1	269,9		6 <sup>1</sup> /4-12	57,2		104,8			130,2		93,6	28,5	
100				336,6	504,8		6 <sup>1</sup> /4-12			104,8			130,2		93,6	41,2	
8		C10010C					6 <sup>1</sup> /4-12			104,8				133,0	93,6	51,2	
				,		1 100,0	J /4-12	101,2	71,3	1104,0	INOTIC	0,2	100,2	1 100,0	55,0	51,2	
	Base r	mounting h	oles: se	ee page 12	2.												


#### **ACCESSORIES**


**C** Series Mounting Accessories















- \* Can be used with RD106, RD1010 Cylinder.
- \*\* Can be used with RD256, RD2514 Cylinder.










					7.75. (1. 0) 1.4.00 (11.00 0.4.11
5†	208380	41,4	44,5	³/414 NPSM	7,1 Dia. (No.2) 1/4-20 UNC x 3/4"
					Lg. Socket Head Cap Screws
10†	208381	47,8	63,5	1 <sup>1</sup> /4-11 <sup>1</sup> /2 NPSM	8,6 Dia. (No.2) 5/16-18 UNC x 3/4"
					Lg. Socket Head Cap Screws
25†	208382	60,5	98,6	2-11 <sup>1</sup> / <sub>2</sub> NPSM	13,5 Dia. (No.2) 1/213 UNC x 1"
					Lg. Socket Head Cap Screws



**Part** 

No.

25395\*

54,1


Cylinder

**Tons** 

10



CYLINDERS



3/4-14 NPSM

54,1 11/4-111/2 NPSM

Cylinder Flat Bas	- 40	X			<del>Т</del> В ¥
Cylinder Tons	Part No.	A (mm)	B (mm)	C (in)	D (mm)
5	25750*	114,3	63,5	³/414 NPSM	34

				D V	
Cylinder Tons	Part No.	A (mm)	B (mm)	C (in)	D (mm)
5	25750*	114,3	63,5	³/414 NPSM	34
10	32325*	166,6	88,9	1 <sup>1</sup> /4-11 <sup>1</sup> /2 NPSM	36,6

#### **Smooth Saddle Serrated Saddle**



**Cylinder Tons** 

5

10 or 15

25


5

10

25

Body Clevis†






2-11 <sup>1</sup>/<sub>2</sub> NPSM

76,2




351576\* ( plain)



4								
	<b>Cylinder Tons</b>	Part No.	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (mm)
	5	350096	52,3	28,7	16	16	14,2	6,4
	10	350097	76,2	42,9	22,4	25,4	25,4	6,4
	15	350098	77,7	42,9	22,4	25,4	25,4	6,4
	25	420061	90,4	57,2	31,8	31,8	38,1	6,4

<sup>\*</sup> Items require threaded adapter when used with "C" series cylinders. They may be used on threaded "CBT" cylinders without the use of an adapter.

33,3



	Plu	unger Base	
Cylinder Tons		A (mm) B (mm)	C (in)

25 25652 152,4 31,8 2-11 <sup>1</sup>/<sub>2</sub> NPSM

<sup>†</sup> Mounting screws are included.

#### **LOW PROFILE**

RLS Series Cylinders 5 - 150 Ton Single-Acting, Spring-Return 700 bar (10,000 psi)



## IDEAL FOR CONFINED AREAS FROM 41 TO 101,6 MM CLEARANCE.

 Cylinder body, piston and gland nut "Power Tech" treated for corrosion and abrasion resistance (See page 8).

 Standard domed piston rod (5-30 ton) or swivel cap (50-150 ton) minimize effects of off-center loading.

• Unique heavy duty spring provides fast piston return.

• A 9796 <sup>3</sup>/<sub>8</sub>" NPTF female half coupler is standard with each cylinder (the RLS50 has a <sup>3</sup>/<sub>8</sub>" coupler which is not angled). Oil ports are <sup>3</sup>/<sub>8</sub>" NPTF.

• Couplers on all cylinders, except RLS50, are angled upward for extra clearance.



#### **MOUNTING HOLES FOR "RLS" CYLINDERS**

RLS50	8,6mm C'bore x 6,4mm deep, 5,6mm thru hole
RLS100	10,7mm C'bore x 8,7mm deep, 7,1mm thru hole

RLS200	15,5mm C'bore x 10,4mm deep, 10,4mm thru hole
RLS300	15,5mm C'bore x 11,2mm deep, 10,4mm thru hole


RLS500S	17,8mm C'bore x 12,7mm deep, 11,9mm thru hole
RLS750S	20,3mm C'bore x 14,2mm deep, 13,5mm thru hole

RLS1000S	20,3mm C'bore x 14,2mm deep, 13,5mm thru hole
RLS1500S	20,6mm C'bore x 14,2mm deep, 13,5mm thru hole



**RLS1000S** 

ASME B30.1 700 bar



													55	NAME OF		7/03 里山	6
				A	В	C1 & C2	F	H	W	X	Y	Z			Metric		
Cyl.			Oil	Re- tracted	Ex- tended	Outside		Piston Rod Prod	L				Bore	Cyl. Eff.	Tons at		
Cap.	Stroke	Order	Cap.	Height	Height	Dia.	Port	Dia.	Mo	unting F	lole Loc	cation	Dia.	Area	700	Weight	
(Tons)	(mm)	No.	(cm³)	(mm)	(mm)	(mm)	(mm)	(mm)		(mr	n)		(mm)	(cm²)	bar	(kg)	
5	14,3	RLS50	10	41,3	55,6	41,3x65,1	19,1	15,9	19,1	28,6	6,4	25,4	28,6	6,4	4,5	1,0	_
10	11,1	RLS100	17	44,5	55,6	55,6x82,6	15,9	19,1	17,5	36,5	9,5	33,3	42,9	14,4	10,1	1,5	_
20	11,1	RLS200	33	50,8	61,9	76,2x101,6	16,7	28,6	18,3	49,2	13,5	39,7	60,3	28,6	20,1	2,5	_
30	12,7	RLS300	53	58,7	71,4	95,3x114,3	18,3	34,9	20,6	52,4	21,4	44,5	73,0	41,9	29,5	3,9	
50	15,9	RLS500S	99	66,7	82,6	114,3x139,7	21,4	44,5	23,8	66,7	23,8	54,0	88,9	62,1	43,6	6,3	
75	15,9	<b>RLS750S</b>	163	79,4	95,3	140,5x165,1	25,4	54,0	23,8	76,2	32,1	65,9	114,3	102,6	72,2	10,6	
100	15,9	<b>RLS1000S</b>	202	85,7	101,6	152,4x177,8	25,4	63,5	20,6	76,2	38,1	71,4	127,0	126,6	89,1	13,6	
150	14,3	<b>RLS1500S</b>	282	101,6	115,9	190,5x215,9	33,3	76,2	33,3	117,5	36,5	79,4	158,8	197,9	139,2	23,6	

Note: RLS Series cylinders may be supplied with QPQ-coating on its pistons & bodies (See page 8).



## IDEAL FOR CONFINED AREAS FROM 89 TO 290.5 MM CLEARANCE.

- Power Tech piston rods and gland nuts resist scoring and corrosion.
- Heavy duty return spring (except for doubleacting models) provides fast piston return & low collapsed height.
- Coupler on 10 thru 50 ton models is angled upward 5° for added clearance.
- · Grooved piston top keeps load from sliding.
- Cylinders can be "dead-ended" at full capacity.
- Removable carrying handles on 100 ton and 250 ton models.



RSS302

ASME B30.1 700 bar



SHORTY

**RSS** Series Cylinders

10 - 250 Ton

Single-Acting, Spring-Return

& Double-Acting

700 bar (10,000 psi)



Cribbing blocks are shown in a 30 ton RSS302 "Shorty" cylinder.



Convert Power Team "Shorty" cylinders to mechanical cribbing devices; more stable than timber or other awkward, makeshift methods. Ideal for lifting applications such as structure moving. Reduce cribbing time dramatically. In effect, increases the stroke of the cylinder; stacking pads act as cylinder extensions:

- 1. Extend cylinder and insert lower supporting ring.
- 2. Retract cylinder, insert a stacking pad.
- 3.Extend cylinder again; pad increases cylinder stroke.
- 4. Repeat process until all rings and pads are used.


#### Each cribbing block set includes rings, pads and insertion handle (Optional).


No. CB30 — Cribbing block set for use with No. RSS302; 30 ton cylinder.


No. CB50 — Cribbing block set for use with No. RSS502; 50 ton cylinder.

**No. CB100** — Cribbing block set for use with No. RSS1002; 100 ton cylinder.

 $\ensuremath{\text{No.}}$  45589 — Insertion handle is used for inserting rings and pads.







			Reduce enter loa	APS FOR the effect ding. Tilts le as opti	ts of s up to 5°.
Use with Cyl. No.	Swivel Cap Order No.	Weight (kg)	A (mm)	B (mm)	C (mm)
RSS101	350320	0,2	25,4	36,5	36,5
RSS202	350321	0,6	34,9	54	54
RSS302	350322	0,7	34,9	63,5	54
RSS502	350331	1,2	36,5	82,6	54
RSS1002	350332	3,0	46	111,1	85,7

					A	В	C	F	Н				
Cyl. Capacity (Tons)	Stroke (mm)	Order No.	(c	il ap. m³) Return	Retracted Height (mm)	Extended Height (mm)	Outside Dia. (mm)	Base to Port (mm)	Piston Rod Dia. (mm)	Bore Dia. (mm)	Cylinder Effective Area (cm²)	Metric Tons at 700 (bar)	Weight (kg)
10	38,1	RSS101	56	-	88,9	127,0	69,9	15,9	38,1	42,9	14,4	10,2	2,7
20	44,5	RSS202	126	_	95,3	139,7	90,5	15,9	54,8	60,3	28,6	20,0	4,5
30	61,9	RSS302	259	_	117,5	179,4	101,6	15,9	63,5	73,0	41,9	29,5	6,7
50	60,3	RSS502	374	_	127,0	187,3	123,8	19,1	79,4	88,9	62,0	43,6	10,5
100	57,2	RSS1002	725	_	139,7	196,9	168,3	23,8	111,1	127,0	126,6	89,1	21,4
100	38,1	RSS1002D	t <sub>482</sub>	212	144,5	182,6	174,6	23,8 *	95,3	127,0	126,6	89,1	24,7
250	76,2	RSS2503	2.469	-	290,5	366,7	250,8	46,0	139,7	203,2	323,9	227,8	99,7

\*Cylinder top to port is 40 mm

<sup>†</sup>Double-acting

Note: RSS Series cylinders (except RSS1002D & RSS2503) may be supplied with QPQ-coating on its pistons & bodies (See page 8).

#### **CENTER HOLE**

RH Series Cylinders 10 - 100 Ton Single-Acting, Spring-Return 700 bar (10,000 psi)





10, 20, 100 Ton Single-Acting Models Feature Plain Collar



#### IDEAL FOR PULLING AND TENSION-ING OF CABLES, ANCHOR BOLTS, FORCING SCREWS, ETC.


- Interchangeable piston head inserts provide versatility of application.
- 12, 20\*, 30\*, 50, 60 Ton Single-Acting Models Feature Threaded Collar
- Withstands full "dead-end" loads.
- Plated piston rod resists wear and corrosion.
- Corrosion resistant standpipe has "Power Tech" treatment.
- All cylinders except RH120 are furnished with a 9796 <sup>3</sup>/<sub>8</sub>" NPT female half coupler.
- Aluminum cylinder body and piston are featured on the RHA306 cylinder.



ASME B30.1 700 bar

\* Model RH203 and RHA306 do not feature the collar thread. See the chart below.





H	IEAD INSERTS FOR RI COPT	H SERIES CYLINDERS TONAL)
	For Use With:	Threaded Insert Order No.
	RH102, RH108	<b>28632</b> <sup>3</sup> / <sub>4</sub> "–16
	RH203	<b>28612</b> 1"–8
	RH302, RH306	<b>38904</b> 1 <sup>1</sup> / <sub>4</sub> "–7
	RH303	<b>28644</b> 1 <sup>1</sup> / <sub>4</sub> "-7
	RH503	38855 1 <sup>5</sup> /8"-5 <sup>1</sup> /2
	RH603, RH605 RH606	34251 1 <sup>5</sup> /8"-5 <sup>1</sup> / <sub>2</sub>

				A	В	C	D	Ε	F	Н	N	0				
				Re-	Ex-			Collar	Base	Piston	Center	Insert	_	Cylinder	Metric	
Cyl.			0il	tracted				Thread	to	Rod	Hole	Thread	Holes (in.) &		Tons at	
Cap.	Stroke	Order	Cap.	Height		Dia.	Thread		Port	Dia.	Dia.	and Size		Area		Weight
(Tons)	(mm)	No.	(cm³)	(mm)	(mm)	(mm)	(in.)	(mm)	(mm)	(mm)	(mm)	(in.)	(mm)	(cm²)	bar	(kg)
10	63,5	RH102 <sup>†</sup>	91	134,9	198,4	76,2	None	None	25,4	52,4	19,4	1 <sup>3</sup> / <sub>4</sub> -12	½ - 20 x 60.3	14,3	10,0	4,1
10	203,2	RH108 <sup>†</sup>	290	287,3	490,5	76,2	None	None	25,4	52,4	19,4	1 <sup>3</sup> / <sub>4</sub> -12	¹/4 - 20 x 60.3	14,3	10,0	8,5
12	7,9	RH120**	14	55,6	63,5	69,9	2 3/4-16	31,8	9,5	34,9	17,5	<sup>3</sup> /4 <b>-1</b> 6	<sup>5</sup> / <sub>16</sub> - 18 x 50.8	17,8	12,5	1,4
12	41,3	RH121	74	122,2	163,5	69,9	2 3/4-16	31,8	25,4	34,9	20,2	None	None	17,8	12,5	3,0
12	41,3	RH121T**	74	122,2	163,5	69,9	2 3/4-16	31,8	25,4	34,9	17,5	<sup>3</sup> /4 <b>-1</b> 6	None	17,8	12,5	3,0
12	76,2	RH123	136	184,2	260,4	69,9	2 3/4-16	20,6	25,4	34,9	20,6	None	None	17,8	12,5	4,0
20	50,8	RH202	155	155,6	206,4	98,4	3 7/8-12	38,1	25,4	54,0	27,4	1 9/16-16	³/ <sub>8</sub> - 16 x 82.5	30,4	21,4	7,3
20	76,2	RH203 <sup>†</sup>	193	154,0	230,2	101,6	None	None	25,4	69,9	26,6	2 1/4-12	³/ <sub>8</sub> - 16 x 82.5	25,3	17,8	9,1
20	152,4	RH206	465	308,0	460,4	98,4	3 <sup>7</sup> /s-12	38,1	25,4	54,0	27,4	1 9/16-16	³/ <sub>8</sub> - 16 x 82.5	30,4	21,4	13,7
30	63,5	RH302	260	158,8	222,3	120,7	4 3/4-12	38,1	29,4	82,6	32,9	2 3/4-12	<sup>7</sup> / <sub>16</sub> - 20 x 92.1	40,9	28,8	11,6
30	149,2	RHA306 <sup>†</sup>	625	283,4	432,6	130,2	None	None	31,8	82,6	32,5	2 <sup>5</sup> /8-8	None	40,9	28,8	9,9
30	152,4	RH306	625	247,7	400,1	120,7	4 3/4-12	38,1	29,4	82,6	32,5	2 3/4-12	<sup>7</sup> / <sub>16</sub> - 20 x 92.1	40,9	28,8	17,7
50	76,2	RH503	534	181,0	257,2	152,4	6-12	50,8	31,8	104,8	42,5	3 1/4-12	5/s - 18 x 120 €	70,0	49,3	21,2
60	76,2	RH603*	607	235,0	311,2	158,8	6 1/4-12	63,5	25,4	91,3	54,0	3-12	½ - 13 x 130.2	79,4	55,9	27,2
60	152,4	RH606*	1.211	311,2	463,6	158,8	6 1/4-12	63,5	25,4	91,3	54,0	3-12	½ - 13 x 130.2	79,4	55,9	35,4
100	76,2	RH1003* <sup>†</sup>	1.014	254,0	330,2	212,7	None	None	31,8	127,0	79,4	4 <sup>1</sup> /s-12	None	133,0	93,5	52,2

<sup>\*</sup> Supplied with carrying handles.



<sup>\*\*</sup> RH120 and RH121T do not have an internal threaded insert, but do have a  $^{3}$ /4-16 internal thread. The RH120 inlet port is  $^{1}$ /4" NPTF.

<sup>†</sup>RH102, RH108, RH203, RHA306 & RH1003 with plain collar.

#### CENTER HOLE

**RH** Series Cylinders 30 - 200 Ton Double-Acting 700 bar (10,000 psi)



#### **IDEAL FOR PULLING AND** TENSIONING.

- Interchangeable piston head inserts provide versatility of application (See page 18).
- Built-in safety feature prevents over-pressurization of the retract circuit.
- Plated piston rod resists wear; superior packings provide high cycle life without leakage.
- · Corrosion-resistant standpipe has "Power Tech" treatment (See page 8).
- Each cylinder has 9796 <sup>3</sup>/<sub>8</sub>" NPTF female half couplers. The 60 ton thru 200 ton models are equipped with removable carrying handles.




30, 60, 100, 150, 200 Ton **Double-Acting Models** Feature Plain Collar





30, 60, 100 Ton **Double-Acting Models Feature Threaded Collar** 






					Re-	Ex-			Collar	Base	Cylinde	r Piston	Center	Insert	Mounting	Cyl	inder	Met	ric	
Cyl.	Cyl. Oil		tracted	tended Outside		Collar	Thread	to	Top to	Rod	Hole	Thread	Holes (in.) and	Effe	ective	Tons at				
Cap.	Stroke	Order	Cap	) <u>.</u>	Height	Height	Dia.	Thread	Length	Port	Port	Dia.	Dia.	Size	Bolt Circle	A	rea	700		Weight
(Tons)	(mm)	No.	(cm	1 <sup>3</sup> )	(mm)	(mm)	(mm)	(in.)	(mm)	(mm)	(mm)	(mm)	(mm)	(in.)	(mm)	(0	:m²)	ba	ır	(kg)
Push	Pull		Push	Pull												Push	Pull	Push	Pull	_
30	15 76,2	RH303	289	167	179,4	255,6	120,7	None	None	25,4	41,3	63,5	32,5	2-12	³/ <sub>8</sub> -16 x 92,1	38,0	21,8	26,8	15,3	13,5
30	15 152,4	RH306D	580	333	281,0	433,4	120,7	None	None	25,4	41,3	63,5	32,5	2-12	/ <sub>10</sub> -20 x 92,1	38,0	21,8	26,8	15,3	20,4
30	20 257,2	RH3010	1,082	672	438,2	695,3	114,3	4 1/2-12	41	44,5	81,0	60,3	33,3 1	<sup>7</sup> /≈16	None	42,2	26,1	29,7	18,3	27,7
60	25 101,6	RHA604D	807	338	241,3	342,9	177,8	None	None	39,7	57,2	101,6	54,0	3-12 1	/₂-13 x 130,2	79,4	33,2	55,8	25,1	16,2
60	25 127,0	RH605*	1.009	423	241,3	368,3	165,9	None	None	25,4	44,5	101,6	54,0	3-12 1	/₂-13 x 130,2	79,4	33,2	55,8	25,1	33,1
60	40 257,2	RH6010*	2,181	1,427	458,8	716,0	158,8	61/4-12	47,6	54,0	81,8	92,1	54,4	3-16	None	84,8	55,4	59,6	38,9	54,5
100	45 38,1	RH1001	526	233	165,1	203,2	212,7	None	None	31,8	58,7	127,0	79,8	4-16 5	/ <sub>8</sub> -11 x 177,8	138,0	60,8	97,0	42,7	38,6
100	50 152,4	RH1006*	1.971	1.076	314,3	466,7	184,2	None	None	37,3	59,1	111,1	52,4	None 1	/₂-13 x 139,7	129,2	70,5	90,8	49,6	43,1

**100** 45 257,2 **RH10010\*** 3,552 1,556 495,3 752,5 215,9 8 \( \)/212 57 63,5 91,7 139,7 79,8 4 \( \)/212 None 138,0 60,8 97,0 42,7 109,0 **150** 70 127,0 RH1505\* 2.475 1.207 311,2\*\* 438,2 215,9 None None 37,3 68,3 139,7 65,1 None None 194,1 94,8 136,9 66,8 67,2 150 75 203,2 RH1508\* 3,929 2.086 349,3 552,5 247,7 None None 39,3 61,1 152,4 80,2 5.12 None 193,2 102,6 135,9 72,1 103,1

- \* Supplied with carrying handles.
- \*\* Measured with 19 mm high serrated insert installed.



#### **CENTER HOLE**

RT Series Cylinders
17-1/2 - 100 Ton
Single-Acting, Spring-Return
& Double-Acting
700 bar (10,000 psi)





#### IDEAL FOR PULLING AND PRESSING.

- A proven design; used throughout industry for over 40 years.
- Cylinders withstand full "dead-end" loads.
- Compact design; ideal for applications in which space is limited.
- Basic head can be changed from a tapped hole to plain hole by simply changing insert.
- Pistons have "Power Tech" treatment for corrosion and abrasion resistance.



#### "QUICK CHANGE" HEAD INSERTS FOR RT SERIES CYLINDERS

For Use	Threaded	Plain
With:	Order No.*	Order No.
RT172	21669	21714
RT302	21873	21872
RT503	22274	22275
RT1004	24197	24196

#### \* Provided with cylinder

Switch from a tapped hole to a plain hole quickly with these cylinder head inserts. They are held in place with a socket screw. Plain hole permits use of a speed nut for readjusting cylinder after extension.



	Acting, Spring-Re		-
	% NPTF N Hole M Thd	8°	8° NPTF Mount C <sub>2</sub> Hole
A D	01 02		M N 7

Dimensions for reference only

CyL Capacity (Tons)	/ Stroke Order (mm) No.	Oil Cap. (cm³) Push Return	Re- tracted Height (mm)	Ex tended Height (mm)	Out- side Dia. (mm)	C2 Out- side Dia. (mm)	L Load Cap Dia. (mm)	M Load Cap Thread (in.)	Hole	Mounting Hole Location (mm)	Mountir Hole (mm)	CyL ng Eff. Area (cm²)	Metric Tons at 700 bar	Weight (kg)
17,5	50,8 <b>RT172</b>	116 -	174,6	225,4	95,3	146,1	44,5	1-8	27,0	38,1	8,7	22,8	16,1	6,6
30	63,5 <b>RT302</b>	258 -	214,3	277,8	108,0	190,5	57,2	1 1/4-7	32,9	46,0	11,9	40,5	28,5	12,8
50	76,2 <b>RT503</b>	482 -	268,3	344,5	149,2	238,1	73,0	1 <sup>5</sup> /8-5 <sup>1</sup> / <sub>2</sub>	42,5	60,3	16,7	63,3	44,5	25,4
100	123,8 <b>RT1004</b>	** 1.5831.037	384,2	508,0	266,7	336,6	120,7	2 1/2-8	65,1	73,0	19,8	124,1*	87,3	72,6

<sup>\*</sup> Push side only for RT1004 double-acting cylinder.


NOTE: Each cylinder complete with threaded cylinder head insert, cylinder half coupler and cylinder attaching screws.

			"CENTER	R-HOLE" CYLINDER	ACCESSORIES (OPTIO	NAL)
	To use with Cyl. No:		RT172, RH203	RT302, RH302 RH303, RH306	RT503, RH503, RH603 RH605, RH606	RT1004
	Order Set No.		RHA20	RHA30	RHA50	RHA100
- 0	1 Speed Crank	1	24814	27198	29595	303785
	2 Speed Nut	2	302482	302483	33439	34136
			1"-8 thd.	11/4"-7 thd.	$1^{5}/8$ "- $5^{1}/2$ " thd.	$2^{1}/_{2}$ "-8 thd.
	3 Adjusting	3	32118	34758	32698	32699
	Screw		1"—8 x 508 mm Lg.	1 ¼"-7 x 609,6 mm Lg.	1%"-5 ½"x 762 mm Lg.	2 ½ "-8 x 869,9 mm Lg.
	4 Threaded	4	Order threaded ins	sert for RH series cylind	lers with the accessory set (S	ee page 18).
	Insert		Threaded insert su	applied with RT series o	ylinders.	
	5 Pushing	5	201923	34510	34755	-
	Adapter		1"-8 x 12,7 mm	1 <sup>1</sup> / <sub>4</sub> "-7 x 19,1mm	1 <sup>5</sup> / <sub>8</sub> "-5 <sup>1</sup> / <sub>2</sub> x 25,4 mm	
	-		dia. shank	dia. shank	dia. shank	
	6 Pushing	6	201454	34511	34756	-
	Adapter		1"-8 x 19,5 mm	1 <sup>1</sup> / <sub>4</sub> "-7 x 25,4 mm	1 <sup>5</sup> / <sub>8</sub> "-5 <sup>1</sup> / <sub>2</sub> x 31,7 mm	
			dia. shank	dia. shank	dia. shank	
	7 Jack Screw	7	24813	25931	32701	32702
	•		1"-8 x 177,8 mm Lg.	1¹/₄"-7 x 228,6 mm Lg	1 <sup>5</sup> /8"-5 <sup>1</sup> /2 x 279,4 mm Lg.	2 ½"-8 x 406,4 mm lg
	8 Screw Cap	8	28228	28229	28230	-
U	•		1"-8 x 38,1 mm dia.	1 1/4"-7 x 44,4 mm dia.	1 5/8"-5 1/2 x 57,1 mm dia.	

<sup>\*\*</sup> The RT1004 has a bypass when full stroke is reached, preventing over-pressurization of the cylinder.

## HALF THE WEIGHT OF EQUAL CAPACITY STEEL CYLINDERS.


- Aluminum body resists sparking in explosive environments.
- Hard-coated aluminum piston rod and cylinder bore resist wear and corrosion.
- Grooved piston top helps keep the load from sliding on top of piston.
- Designed for jacking and other non-production operations.




#### **ALUMINUM**

RA Series Cylinders 20 - 100 Ton Single-Acting, Spring-Return 700 bar (10,000 psi)





		off cen	ter loadi	duce the one of the one of the original distribution distribution of the original distribution of the o	
Cylinder Tonnage	Swivel Cap Order No.	Wt. (kg.)	"RA" ( A (mm)	Cylinders B (mm)	C (mm)
55 100	350376 350984	0,9 2,5	31,8 49,2	71,4 79,4	71,4 95,3





Base Mtg. Holes (4) at 45° from coupler (RA556, RA5510) 3/8"-16 x 114,3mm Dia. B.C. Depth = 12,7 mm

				A	В	С	F Base	H Piston	K Piston		Cylinder	Metric	
Cyl. Cap. (Tons)	Stroke (mm)	Order No.	Oil Cap. (cm³)	Retracted Ht. (mm)	Extended Ht. (mm)	Outside Dia. (mm)	to Port (mm)	Rod Dia. (mm)	Rod Protrusion (mm)	Bore Dia. (mm)	Effective Area (cm²)	Tons at 700 bar	Weight. (kg)
	54,0	RA202	154	161,9	215,9	95,3	31,8	50,8	7,9	60,3	28,6	20,1	3,5
20	104,8	RA204	300	212,7	317,5	95,3	31,8	50,8	7,9	60,3	28,6	20,1	4.2
	155,6	RA206	445	263,5	419,1	95,3	31,8	50,8	7,9	60,3	28,6	20,1	5.1
4.5	54,0	RA302	226	187,3	241,3	108,0	31,8	63,5	9,5	73,0	41,9	29,4	5,0
30	104,8	RA304	439	238,1	342,9	108,0	31,8	63,5	9,5	73,0	41,9	29,4	5,9
	155,6	RA306	652	288,9	444,5	108,0	31,8	63,5	9,5	73,0	41,9	29,4	6,8
	54,0	RA552	386	171,5	225,4	133,4	34,9	79,4	6,4	95,3	71,2	50,1	7,3
(JI	104,8	RA554	746	222,3	327,0	133,4	34,9	79,4	6,4	95,3	71,2	50,1	8,9
(J	155,6	RA556*	1.109	273,1	428,6	133,4	34,9	79,4	6,4	95,3	71,2	50,1	10,9
	254,0	RA5510*	1.811	384,2	638,2	133,4	34,9	79,4	6,4	95,3	71,2	50,1	14,4
1	54,0	RA1002	718	196,9	250,8	187,3	30,2	104,8	3,2	130,2	133,0	93,5	15,1
00	158,8	RA1006*	2.116	298,5	457,2	187,3	30,2	104,8	3,2	130,2	133,0	93,5	22,6

<sup>\*</sup> Equipped with carrying handles.

#### **DOUBLE ACTING**

**RD** Series Cylinders 10 - 500 Ton Double-Acting, Hydraulic-Return 700 bar (10,000 psi)




## HIGH TONNAGE PREMIUM DESIGN FOR HIGH CYCLE LIFE.

- High tonnage premium design for high cycle life.
- Perfect for bridge lifting, building reconstruction, shipyard, utility and mining equipment maintenance.
- Aluminum bronze overlay bearings provide long life.
- Chrome plated piston rod resists corrosion.
- Load cap snaps out to expose internal piston rod threads for pulling applications; threads withstand full tonnage.
- Grooved ring pattern in load cap helps guard against load slippage.
- Each cylinder has two 9796 3/8" NPTF female half couplers.
- Built-in safety relief valve prevents over-pressurization of the retract circuit.
- Feature mounting holes and collar threads.






RD10013








#### Reduce the effects of off center loading. Tilts up to 5 degrees. (Available as optional) Swivel Cylinder Cap Weight A В C Tonnage Order No. (kg) (mm) (mm) (mm) 350144 22,2 36,5 21,8 10 0,4 350145 25 28,6 54 36,5 0,6 55 351325 1,9 61,9 63,5 39,3 100 351324 5,1 75,0 95,3 67,5 150 351334 5,8 66,7 111,1 77,8

**SWIVEL CAPS FOR "RD" CYLINDERS** 





						A	В	C	D	E	F Base	<b>G</b> Cylinder	Н	1	K							
						Re-	Ex-	Out-	Collar	Thread	to	Piston	Piston	Rod Int.	Piston	Load						
	Cyl.	er al	0.1		)il	tracted	tended	side	Thread	Length	Port	Top to	Rod	(in) and	Rod Pro-		Bore		Eff.	Metric		w···
	Jap ons)	Stroke (mm)	Order No.		acity m³)	Height (mm)	Height (mm)	Dia. (mm)	Size (in_)	Thread (mm)	trusion (mm)	Port (mm)	Dia. (mm)	Depth (mm)	trusion (mm)	Dia. (mm)	Dia. (mm)		rea m²)	at 7 ba		Weight (kg)
	ı Pul			Push		(	(	,,	(/			(,	()	()	,,		(	Push		Push	Pull	10/
10	4	158,8	RD106	228	90	296,9	455,6	76,2	2 3/4-12	41,3	25,4	63,5	33,3	1-8 x 25,4	6,4	34,9	42,9	14,4	5,7	10,2	4,0	10,0
10	4	254,0	RD1010	366	144	398,5	652,5	76,2	2 3/4-12	41,3	25,4	63,5	33,3	1-8 x 25,4	6,4	34,9	42,9	14,4	5,7	10,2	4,0	12,7
25	8	158,8	RD256	528	166	314,3	473,1	101,6	4-12	41,3	25,4	63,5	54,0	1 ½-16 x 25,4	9,5	54,0	65,1	33,2	10,4	23,4	7,3	18,1
25	8	362,0	RD2514	1.205	376	517,5	879,5	101,6	4-12	41,3	25,4	63,5	54,0	1 ½-16 x 25,4	9,5	54,0	65,1	33,2	10,4	23,4	7,3	29,5
55	28	158,8	RD556	1.132	577	329,4	488,2	127,0	5-12	41,3	33,3	63,5	66,7	1 <sup>11</sup> /18-8 x 30,2	15,9	66,7	95,3	71,2	36,3	50,1	25,6	27,9
55	28	333,4	RD5513	2.376	1.212	504,0	837,4	127,0	5-12	41,3	33,3	63,5	66,7	1 <sup>11</sup> /10-8 x 30,2	15,9	66,7	95,3	71,2	36,3	50,1	25,6	40,9
55	28	460,4	RD5518	3280	1.673	657,2	1.117,6	127,0	5-12	41,3	33,3	63,5	66,7	1 <sup>11</sup> /18 x 30,2	15,9	66,7	95,3	71,2	36,3	50,1	25,6	64,5
80	44	333,4	RD8013	3421	1.901	517,5	850,9	146,1	53/412	41,3	38,1	63,5	76,2	2-4 <sup>1</sup> / <sub>2</sub> x 38,1	14,3	73,0	114,3	102,6	57,0	72,1	40,1	53,6
100	44	168,3	RD1006	2.242	959	350,0	518,3	174,6	6 <sup>7</sup> /8-12	41,3	38,1	63,5	98,4	2 <sup>3</sup> / <sub>4</sub> -12 x 29,4	15,9	98,4	130,2	133,1	57,0	93,5	40,1	57,2
100	44	333,4	RD10013	4.440	1.902	515,1	848,5	174,6	6 <sup>7</sup> /s12	41,3	38,1	63,5	98,4	2³/4-12 x 29,4	15,9	98,4	130,2	133,1	57,0	93,5	40,1	82,2
100	44	511,2	RD10020	6.809	2.919	718,3	1.229,5	174,6	6 <sup>7</sup> / <sub>8</sub> -12	41,3	38,1	63,5	98,4	2³/4-12 x 29,4	15,9	98,4	130,2	133,1	57,0	93,5	40,1	118,0
150	73	168,3	RD1506	3.334	1.606	377,8	546,1	209,6	81/4-12	41,3	50,8	63,5	114,8	3 <sup>1</sup> /48 x 38,1	20,6	114,3	158,8	197,9	95,3	139,1	66,9	85,4
<u>150</u>	73	333,4	RD15013	6.604	3.180	542,9	876,3	209,6	8 <sup>1</sup> /4-12	41,3	50,8	63,5	114,8	3 <sup>1</sup> /+8 x 38,1	20,6	114,3	158,8	197,9	95,3	139,1	66,9	123,5
<u>150</u>	73	460,4	RD15018	9.132	4.392	673,9	1.134,3	209,6	81/412	41,3	50,8	63,5	114,8	3 <sup>1</sup> / <sub>4</sub> 8 x 38,1	19,1	114,3	158,8	197,9	95,3	139,1	66,9	170,7
200	113	168,3	RD2006	4.485	2.457	406,4	574,7	241,3	91/2-12	41,3	63,5	68,3	123,8	3 <sup>1</sup> /48 x 57,1	27,0	114,3	184,2	266,3	145,9	187,2	102,6	118,9
200	113	333,4	RD20013	8.886	4.869	571,5	904,9	241,3	91/2-12	41,3	63,5	68,3	123,8	3 <sup>1</sup> /48 x 57,1	27,0	114,3	184,2	266,3	145,9	187,2	102,6	161,6
200	113	460,4	RD20018	12.270	6.722	723,9	1.184,3	241,3	91/212	41,3	63,5	68,3	123,8	3 <sup>1</sup> /#8 x 57,1	27,0	114,3	184,2	266,3	145,9	187,2	102,6	200,7
300	147	152,4	RD3006	5.920	2.903	488,9	591,3	273,1	101/2-12	60,3	85,7	85,7	158,8	2 <sup>1</sup> /2-12 x 82,5	28,6	174,6	222,3	387,8	190,0	272,7	133,6	172,5
300	147	330,2	RD30013	12.825	6.281	630,2	960,4	273,1	101/2-12	60,3	85,7	85,7	158,8	2 <sup>1</sup> /2-12 x 82,5	28,6	174,6	222,3	387,8	190,0	272,7	133,6	296,9
400	186	152,4	RD4006	7.724	4.051	489,7	642,1	320,7	121/2-8	69,9	97,6	97,6	184,2	3-12 x 92,2	31,8	198,4	254,0	506,6	240,3	356,2	169,0	265,6
400	186	330,2	RD40013	16.744	8.790	667,5	997,7	320,7	121/2-8	69,9	97,6	97,6	184,2	3-12 x 92,2	31,8	198,4	254,0	506,6	240,3	356,2	169,0	349,6
500	245	152,4	RD5006	9.774	4.838	522,3	674,7	374,7	14³/48	79,4	105,6	105,6	203,2	3¹/₄12 x 107,9	38,1	215,9	285,8	641,1	317,0	450,8	222,8	371,8
500	245	330,2	RD50013	21.189	10.480	700,1	1.030,3	374,7	143/48	79,4	105,6	105,6	203,2	3 <sup>1</sup> /4-12 x 107,9	38,1	215,9	285,8	641,1	317,0	450,8	222,8	495,8

NOTE: Base mounting holes are standard on all RD cylinders. Orientation of base mounting holes to coupler. Orientation on RD300, RD400 & RD500 series is random.

BASE MOUNTING HOLES FOR "RD" CYLINDERS												
Tonnage	10	25	55	80	100	150	200	300	400	500		
No. of Holes	2	4	4	4	4	4	4	4	4	6		
Thread Size	³/8"-16	1/2"-13	5/8"-11	5/8"-11	3/4"-10	1"-8	11/4"-7	11/4"-7	11/2"-12	13/8"-12		
Depth (mm)	16	19	22	22	25	25	32	44	48	51		
B.C. Dia.	51	70	89	114	140	152	165	159	184	203		
Orientation	90°	45°	45°	45°	45°	45°	45°	Random	Random	Random		

### **HIGH TONNAGE**

R Series Cylinders (Steel) 55 to 1140 Ton Single-Acting, Load-Return 700 bar (10,000 psi)





RxxxxC Series

- High-tonnage, single-acting hydraulic cylinders.
- Visible indicator band alerts when stroke limit is reached; overflow port ("weep hole") stroke limiter prevents piston from being overextended.
- Alloy heat treated piston and body for reliability and strength.
- Hard chrome / nickel plated piston rod increase corrosion resistance and give superior bearing qualities.
- Each cylinder has one 3/8"NPTF female half coupler (9796).
- Comply with ASME B30.1

R2802C


- Recommended to use with Swivel Caps (Optional)
- Base mounting holes are optional unless specified.




R1502C

		- (6			Α	В	С	F	н	К
Cylinder				Oil	Retracted		Outside	Base to	Piston Rod	Piston Rod
Cap.		oke	Cylinder Order No.	Capacity	Height	Extended Height	Diameter	Port	Diameter	Protrusion
(Tons)	(inch)	(mm)		(cu. cm.)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)
55	2	50.8	R552C	362	125.4	176.2	127.0	25.4	95.3	3.2
<u>55</u>	4	101.6	R554C	725	176.2	277.8	127.0	25.4	95.3	3.2
55	6	152.4	R556C	1,087	227.0	379.4	127.0	25.4	95.3	3.2
55	8	203.2	R558C	1,449	277.8	481.0	127.0	25.4	95.3	3.2
55	10	254.0	R5510C	1,812	328.6	582.6	127.0	25.4	95.3	3.2
100	2	50.8	R1002C	676	139.7	190.5	165.1	25.4	130.2	3.2
100	4	101.6	R1004C	1,353	190.5	292.1	165.1	25.4	130.2	3.2
100	6	152.4	R1006C	2,029	241.3	393.7	165.1	25.4	130.2	3.2
100	8	203.2	R1008C	2,705	292.1	495.3	165.1	25.4	130.2	3.2
100	10	254.0	R10010C	3,382	342.9	596.9	165.1	25.4	130.2	3.2
100	12	304.8	R10012C	4,058	393.7	698.5	165.1	25.4	130.2	3.2
150	2	50.8	R1502C	1,006	161.9	212.7	204.8	31.8	158.8	3.2
150	4	101.6	R1504C	2,012	212.7	314.3	204.8	31.8	158.8	3.2
150	6	152.4	R1506C	3,018	263.5	415.9	204.8	31.8	158.8	3.2
150	8	203.2	R1508C	4,025	314.3	517.5	204.8	31.8	158.8	3.2
150	10	254.0	R15010C	5,031	365.1	619.1	204.8	31.8	158.8	3.2
150	12	304.8	R15012C	6,037	415.9	720.7	204.8	31.8	158.8	3.2
200	2	50.8	R2002C	1,354	190.5	241.3	235.0	41.3	184.2	3.2
200	4	101.6	R2004C	2,707	241.3	342.9	235.0	41.3	184.2	3.2
200	6	152.4	R2006C	4,061	292.1	444.5	235.0	41.3	184.2	3.2
200	8	203.2	R2008C	5,415	342.9	546.1	235.0	41.3	184.2	3.2
200	10	254.0	R20010C	6,769	393.7	647.7	235.0	41.3	184.2	3.2
200	12	304.8	R20012C	8,122	444.5	749.3	235.0	41.3	184.2	3.2
280	2	50.8	R2802C	1,860	209.5	260.3	276.2	47.6	215.9	3.2
280	4	101.6	R2804C	3,720	260,3	361.9	276,2	47.6	215,9	3,2
280	6	152.4	R2806C	5,579	311,1	463.5	276,2	47.6	215,9	3,2
280	8	203.2	R2808C	7,439	351.9	555.1	276.2	47.6	215.9	3.2
280	10	254.0	R28010C	9,299	412.7	666.7	276.2	47.6	215.9	3.2
280	12	304.8	R28012C	11,159	463.5	768.3	276.2	47.6	215.9	3.2
355	2	50.8	R3552C	2,323	231.8	282.6	298.5	54.0	241.3	3.2
355	4	101,6	R3554C	4,646	282,6	384,2	298.5	54.0	241.3	3,2
355	6	152,4	R3556C	6,969	333.4	485.8	298.5	54.0	241.3	3,2
	8		+	-	384.2				+	3.2
355		203.2	R3558C	9,292		587.4	298.5	54.0	241.3	
355	10	254.0	R35510C	11,616	435.0	689.0	298.5	54.0	241.3	3.2
355	12	304.8	R35512C	13,939	485.8	790.6	298.5	54.0	241.3	3.2
430	2	50.8	R4302C	2,838	263.5	314.3	330.2	63.5	266.7	3.2
430	4	101.6	R4304C	5,676	314.3	415.9	330.2	63.5	266.7	3.2
430	6	152.4	R4306C	8,514	365.1	517.5	330.2	63.5	266.7	3.2
430	8	203.2	R4308C	11,352	415.9	619.1	330.2	63.5	266.7	3.2
430	10	254.0	R43010C	14,190	466.7	720.7	330.2	63.5	266.7	3.2
430	12	304.8	R43012C	17,028	517.5	822.3	330.2	63.5	266.7	3.2
565	2	50.8	R5652C	3,707	292.1	342.9	377.8	69.9	304.8	3.2
565	4	101.6	R5654C	7,413	342.9	444.5	377.8	69.9	304.8	3.2
565	6	152.4	R5656C	11,120	393.7	546.1	377.8	69.9	304.8	3.2
565	8	203.2	R5658C	14,827	444.5	647.7	377.8	69.9	304.8	3.2
565	10	254.0	R56510C	18,533	495.3	749.3	377.8	69.9	304.8	3.2
565	12	304.8	R56512C	22,240	546.1	850.9	377.8	69.9	304.8	3.2
660			*R6606C	13,051	464.8	617.2	419.1		330.2	
880	6	152.4	*R8806C	17,375	508.0	660.4	495.3		381.0	
1,140			*R11406C	22,317	551.2	703.6	571.5		431.8	
1.001.500	cial Culinda	re' complete	with woar ri		swivel cap & i	hase mountin				

<sup>\* &#</sup>x27;-QC1 Special Cylinders' complete with wear rings, integral swivel cap & base mounting holes. Stroke available in 2" (50.8mm) increment up to 12" (304.8mm). Consult factory for details.




## **The HEAVY LIFTER Single-Acting Solution**



#### Recommendation

Use Swivel Caps (Optional) to reduce the effects of off-center loading.

- Tilts up to 5°.
  Radial grooves on top of cap reduce load slippage.
- Notch across face of each cap helps keep loads having a protruding or round shaped centered.



						х	Υ		
Cylinder Order No.	Bore Diameter	Effective Area	Metric Tons at	Weight	Swivel Cap Order No.	Swivel Cap Protrusion	Swivel Cap Diameter	Retracted Ht. (Cap & Cyl.)	Weight (Cap & Cyl.)
	(mm)	(cm²)	690 bar	(kg)	(Optional)	(mm)	(mm)	(mm)	(kg)
R552C	95.3	71.2	50.1	12.3	420866	25.4	71.4	150.8	13.1
R554C	95.3	71.2	50.1	17.5	420866	25.4	71.4	201.6	18.3
R556C	95.3	71.2	50.1	22.7	420866	25.4	71.4	252.4	23.5
R558C	95.3	71.2	50.1	27.9	420866	25.4	71.4	303.2	28.7
R5510C	95.3	71.2	50.1	32.7	420866	25.4	71.4	354.0	33.5
R1002C	130.2	133.1	93.6	23.6	420866	25.4	71.4	165.1	24.4
R1004C	130.2	133.1	93.6	32.0	420866	25.4	71.4	215.9	32.8
R1006C	130.2	133.1	93.6	40.4	420866	25.4	71.4	266.7	41.2
R1008C	130.2	133,1	93.6	48.8	420866	25.4	71.4	317.5	49.6
R10010C	130.2	133.1	93.6	57.2	420866	25.4	71.4	368.3	58.0
R10012C	130.2	133.1	93.6	65.6	420866	25.4	71.4	419.1	66.4
R1502C	158.8	197.9	139.1	41.8	420867	38.1	130.2	200.0	45.8
R1504C	158.8	197.9	139.1	55.2	420867	38.1	130.2	250.8	59.2
R1506C	158.8	197.9	139.1	68.6	420867	38.1	130.2	301.6	72.6
R1508C	158.8	197.9	139.1	82.0	420867	38.1	130.2	352.4	86.0
R15010C	158.8	197.9	139.1	95.3	420867	38.1	130.2	403.2	99.3
R15012C	158.8	197.9	139.1	108.7	420867	38.1	130.2	454.0	112.7
R2002C	184.2	266.3	187.2	65.8	420867	38.1	130.2	228.6	69.8
R2004C	184.2	266.3	187.2	83.1	420867	38.1	130.2	279.4	87.1
R2006C	184.2	266.3	187.2	100.3	420867	38.1	130.2	330.2	104.3
R2008C	184.2	266.3	187.2	117.6	420867	38.1	130.2	381.0	121.6
R20010C	184.2	266.3	187.2	134.8	420867	38.1	130.2	431.8	138.8
R20012C	184.2	266.3	187.2	152.1	420867	38.1	130.2	482.6	156.1
R2802C	215.9	366.0	257.3	91.2	420868	44.5	149.2	254.0	97.3
R2804C	215.9	366.0	257.3	113.7	420868	44.5	149.2	304.8	119.8
R2806C	215.9	366.0	257.3	136.1	420868	44.5	149.2	355.6	142.2
R2808C	215.9	366.0	257.3	158.6	420868	44.5	149.2	396.4	164.7
R28010C	215.9	366.0	257.3	181.0	420868	44.5	149.2	457.2	187.1
R28012C	215.9	366.0	257.3	203.5	420868	44.5	149.2	508.0	209.6
R3552C	241.3	457.2	321.4	137.1	420869	69.9	195.3	301.7	153.9
R3554C	241.3	457.2	321.4	167.1	420869	69.9	195.3	352.5	183.9
R3556C	241.3	457.2	321.4	197.0	420869	69.9	195.3	403.3	213.8
R3558C	241.3	457.2	321.4	226.8	420869	69.9	195.3	454.1	243.6
R35510C	241.3	457.2	321.4	256.5	420869	69.9	195.3	504.9	273.3
R35512C	241.3	457.2	321.4	286.3	420869	69.9	195.3	555.7	303.1
R4302C	266.7	558.5	392,6	199.8	420870	79.4	225.4	342.9	223.4
R4304C	266.7	558.5	392.6	238.2	420870	79.4	225.4	393.7	261.8
R4306C	266.7	558.5	392.6	276.5	420870	79.4	225.4	444.5	300.1
R4308C	266.7	558.5	392.6	314.9	420870	79.4	225.4	495.3	338.5
R43010C	266.7	558.5	392.6	353.2	420870	79.4	225.4	546.1	376.8
R43012C	266.7	558.5	392.6	391.6	420870	79.4	225.4	596.9	415.2
R5652C	304.8	729.5	512.8	289.7	420871	92.1	250.8	384.2	325.1
R5654C	304.8	729.5	512.8	339.6	420871	92.1	250.8	435.0	375.0
R5656C	304.8	729.5	512.8	389.5	420871	92.1	250.8	485.8	424.9
R5658C	304.8	729.5	512.8	439.5	420871	92.1	250.8	536.6	474.9
R56510C	304.8	729.5	512.8	489.4	420871	92.1	250.8	587.4	524.8
R56512C	304.8	729.5	512.8	539.4	420871	92.1	250.8	638.2	574.8
*R6606C	330.2	856.3	600.0	472.0			254.0	464.8	472.0
*R8806C	381.0	1,140.1	800.0	718.1			292.1	508.0	718.1
*R11406C	431,8	1,464.4	1,000.0	1,031,8		l	317.5	551.2	1,031,8

#### **RxxxxD Series**

### **HIGH TONNAGE**

R Series Cylinders (Steel)
100 to 1140 Ton
Double-Acting, Hydraulic-Return
700 bar (10,000 psi)







- High-tonnage, double-acting hydraulic cylinders for positive return.
- Cylinders come standard with swivel caps to reduce the effects of off-center loading.
- Cylinders may be "dead-ended" without damage.
- Hard chrome / nickel plated, heat treated piston rod reduces wear on piston and gland nut
- Built-in safety relief valve prevents over-pressurization of the retract circuit.
- Each cylinder has two 3/8"NPTF female half couplers (9796).
- Comply with ASME B30.1
- Base mounting holes are optional unless specified.

					Α	В	С	F	G	
Cylinder Cap.	Str	oke	Cylinder		oil acity	Retracted Height	Extended Height	Outside Diameter	Base to Port	Cyl Top to Port
(Tons)	(inch)	(mm)	Order No.	Push (cm³)	Return (cm³)	(mm)	(mm)	(mm)	(mm)	(mm)
100	2	50.8	R1002D	676	314	168.7	219.5	165.1	25.4	56.0
100	4	101.6	R1004D	1,353	628	219.5	321.1	165.1	25.4	56.0
100	6	152.4	R1006D	2,029	942	270.3	422.7	165,1	25.4	56.0
100	8	203.2	R1008D	2,705	1,256	321.1	524.3	165.1	25.4	56.0
100	10	254.0	R10010D	3,382	1,570	371.9	625.9	165.1	25.4	56.0
100	12	304.8	R10012D	4,058	1,884	422.7	727.5	165.1	25.4	56.0
150	2	50.8	R1502D	1,006	485	188.9	239.7	204.8	31.8	57.2
150	4	101.6	R1504D	2,012	970	239.7	341.3	204.8	31.8	57.2
150	6	152.4	R1506D	3,018	1,455	290.5	442.9	204.8	31.8	57.2
150	8	203.2	R1508D	4,025	1,940	341.3	544.5	204.8	31.8	57.2
150	10	254.0	R15010D	5,031	2,424	392.1	646.1	204.8	31.8	57.2
150	12	304.8	R15012D	6,037	2,909	442.9	747.7	204.8	31.8	57.2
200	2	50.8	R2002D	1,354	644	206.8	257.6	235.0	41.3	58.7
200	4	101.6	R2004D	2,707	1,287	257.6	359.2	235.0	41.3	58.7
200	6	152.4	R2006D	4,061	1,931	308.4	460.8	235.0	41.3	58.7
200	8	203.2	R2008D	5,415	2,575	359.2	562.4	235.0	41.3	58.7
200	10	254.0	R20010D	6,769	3,219	410.0	664.0	235.0	41.3	58.7
200	12	304.8	R20012D	8,122	3,862	460.8	765.6	235.0	41.3	58.7
280	2	50.8	R2802D	1,860	772	233.8	284.6	276.3	47.6	65.5
280	4	101.6	R2804D	3,720	1,544	284.6	386.2	276.3	47.6	65.5
280	6	152.4	R2806D	5,579	2,317	335.4	487.8	276.3	47.6	65.5
280	8	203.2	R2808D	7,439	3,089	386.2	589.4	276.3	47.6	65.5
280	10	254.0	R28010D	9,299	3,861	437.0	691.0	276.3	47.6	65.5
280	12	304.8	R28012D	11,159	4,633	487.8	792.6	276.3	47.6	65.5
355	2	50.8	R3552D	2,323	776	288.9	339.7	298.5	54.0	69.9
355	4	101.6	R3554D	4,646	1,553	339.7	441.3	298.5	54.0	69.9
355	6	152.4	R3556D	6,969	2,329	390.5	542.9	298.5	54.0	69.9
355	8	203.2	R3558D	9,292	3,105	441.3	644.5	298.5	54.0	69.9
355	10	254.0	R35510D	11,616	3,881	492.1	746.1	298.5	54.0	69.9
355	12	304.8	R35512D	13,939	4,658	542.9	847.7	298.5	54.0	69.9
430	2	50.8	R4302D	2,838	978	312.7	363.5	330.2	63.5	75.0
430	4	101.6	R4304D	5,676	1,956	363.5	465.1	330.2	63.5	75.0
430	6	152.4	R4306D	8,514	2,934	414.3	566.7	330.2	63.5	75.0
430	8	203.2	R4308D	11,352	3,913	465.1	668.3	330.2	63.5	75.0
430	10	254.0	R43010D	14,190	4,891	515.9	769.9	330.2	63.5	75.0
430	12	304.8	R43012D	17,028	5,869	566.7	871.5	330.2	63.5	75.0
565	2	50.8	R5652D	3,707	1,259	345.3	396.1	377.8	69.9	81.4
565	4	101.6	R5654D	7,413	2,517	396.1	497.7	377.8	69.9	81.4
565	6	152.4	R5656D	11,120	3,776	446.9	599.3	377.8	69.9	81.4
565	8	203.2	R5658D	14,827	5,035	497.7	700.9	377.8	69.9	81.4
565	10	254.0	R56510D	18,533	6,294	548.5	802.5	377.8	69.9	81.4
565	12	304.8	R56512D	22,240	7,552	599.3	904.1	377.8	69.9	81.4
660			*R6606D	13,051	4,537	520.7	673.1	419.1		
880	6	152.4	*R8806D	17,375	6,255	563.9	716.3	495.3		
1,140			*R11406D	22,317	8,244	607.1	759.5	571.5		
* '-0C1 Spe	cial Culinda	we! complete	with war ri	nas integral	cuival can 9 l	haca mauntin	a holos			

<sup>\* &#</sup>x27;-QC1 Special Cylinders' complete with wear rings, integral swivel cap & base mounting holes. Stroke available in 2" (50.8mm) increment up to 12" (304.8mm). Consult factory for details.



# The HEAVY LIFTER Double-Acting Solution



	Н	К				
Cylinder	Piston Rod	Piston Rod	Bore	Effective	Metric Tons	Weight
Order No.	Diameter (mm)	Protrusion (mm)	Diameter (mm)	Area Push (cm²)	at 690 bar Push	(Kg)
R1002D	95,3	7.1	130,2	133,1	93,6	24,5
R1004D	95.3	7.1	130,2	133,1	93,6	30,0
R1006D	95.3	7.1	130,2	133.1	93.6	36.8
R1008D	95.3	7.1	130.2	133.1	93.6	39.9
R10010D	95.3	7.1	130.2	133.1	93.6	49.0
R10012D	95.3	7.1	130.2	133.1	93.6	58.2
R1502D	114.3	7.5	158.8	197,9	139.1	43.1
R1504D	114.3	7.5	158.8	197.9	139.1	52,4
R1506D	114.3	7.5	158.8	197.9	139.1	61.7
R1508D	114,3	7.5	158.8	197.9	139,1	71.0
R15010D	114.3	7.5	158.8	197.9	139.1	80.3
R15012D	114.3	7.5	158.8	197.9	139.1	89.6
R2002D	133.4	8.7	184.2	266.3	187.2	61.7
R2004D	133.4	8.7	184.2	266.3	187.2	73.3
R2006D	133.4	8.7	184.2	266.3	187.2	84.9
R2008D	133.4	8.7	184.2	266.3	187.2	96.7
R20010D	133.4	8.7	184.2	266.3	187.2	108.5
R20012D	133.4	8.7	184.2	266.3	187.2	120.3
R2802D	165.1	10.3	215.9	366.0	257.3	99.4
R2804D	165.1	10.3	215.9	366.0	257.3	117.1
R2806D	165.1	10.3	215.9	366.0	257.3	134.8
R2808D	165.1	10.3	215.9	366.0	257.3	152.8
R28010D	165.1	10.3	215.9	366.0	257.3	170.7
R28012D	165.1	10.3	215.9	366.0	257.3	188.7
R3552D	196.9	11.1	241.3	457.2	321.4	147.0
R3554D	196.9	11.1	241.3	457.2	321.4	169.1
R3556D	196.9	11.1	241.3	457.2	321.4	191.1
R3558D	196.9	11.1	241.3	457.2	321.4	213.2
R35510D	196.9	11.1	241.3	457.2	321.4	235.2
R35512D	196.9	11.1	241.3	457.2	321.4	257.3
R4302D	215.9	11.9	266.7	558.5	392.6	199.3
R4304D	215.9	11.9	266.7	558.5	392.6	226.3
R4306D	215.9	11.9	266.7	558.5	392.6	253.3
R4308D	215.9	11.9	266.7	558.5	392.6	279.4
R43010D	215.9	11.9	266.7	558.5	392.6	305.5
R43012D	215.9	11.9	266.7	558.5	392.6	331.6
R5652D	247.7	13.9	304.8	729.5	512.8	281.0
R5654D	247.7	13.9	304.8	729.5	512.8	315.7
R5656D	247.7	13.9	304.8	729.5	512.8	350.4
R5658D	247.7	13.9	304.8	729.5	512.8	385.4
R56510D R56512D	247.7 247.7	13.9	304.8	729.5	512.8 512.8	420.4
*R6606D	266.7	13.9	304.8 330.2	729 <u>.</u> 5 856 <u>.</u> 3	600.0	455.4 492.0
*R8806D	304.8		330.2 381.0	1,140.1	800.0	492.0 745.4
*R8806D *R11406D	304.8		431.8	1,140.1	1,000.0	1,071.0
N 1 1400D	344.3		43 1.0	1,404.4	1,000.0	1,0/1.0

#### **Pump/Valve Selection**

 Use pump with 4-way directional control valve to operate double-acting cylinder/s.



#### **RD Series**

 For high tonnage & higher cycle applications, opt for POWER TEAM 'RD' Series double-acting cylinders. (See page 22 & 23)



#### **An Unequal Load Distribution**

 Precision Synchronous Lift & Lowering System for lifting unequal load from 4 to 80 jacking points.
 Consult factory for details. (See page 156)

## LOCKING COLLAR HIGH TONNAGE

R Series Cylinders (Steel) 55 to 1140 Ton Single-Acting, Load-Return 700 bar (10,000 psi)





Locking Collar feature permits non-hydraulic support of load

#### **RxxxxL Series**


- High-tonnage, locking collar, single-acting hydraulic cylinders.
- Safe & positive mechanical lock to support load.
- Support lifted load for extended periods of time with hydraulic pressure released.
- Visible indicator band alerts when stroke limit is reached; overflow port ("weep hole") stroke limiter prevents piston from being overextended.
- All cylinders feature hard chrome / nickel plated pistons to resist corrosion and abrasion.
- Each cylinder has one 3/8"NPTF female half coupler (9796).
- Comply with ASME B30.1

R556L


- Recommended to use with Swivel Caps (Optional)
- Base mounting holes are optional unless specified.

Company   Comp						Α	В	С	F	Н	К	T
		Str	oke	Cylinder		Retracted	Extended	Outside	Base to	Piston Rod		
555         2         50.8         R552L         362         161.9         212.7         112.4         25.4         95.3         3.2         36.5           55         6         152.4         R556L         1.087         263.5         415.9         125.4         25.4         95.3         3.2         36.5           55         6         152.4         R556L         1.087         263.5         415.9         125.4         25.4         95.3         3.2         36.5           55         10         254.0         R5510L         1.812         365.1         619.1         125.4         25.4         95.3         3.2         36.5           100         2         50.8         R1002L         676         184.2         255.0         165.1         25.4         490.2         32.2         44.5           100         6         152.4         11006L         1.033         23.0         36.6         165.1         25.4         490.2         32.2         44.5           100         8         203.2         R10018         2.075         336.6         559.8         185.1         25.4         190.2         32.0         44.5           100         10		(inch)	(100100)	Order No.		_						
555         4         101.6         R554L         725         212.7         314.3         125.4         25.4         95.3         3.2         36.5           55         6         152.4         R558L         1,087         263.5         415.9         125.4         25.4         95.3         3.2         36.5           55         8         203.2         R558L         1,449         314.3         517.5         125.4         25.4         95.3         3.2         36.5           100         4         101.6         R1004L         1,353         235.0         336.6         165.1         25.4         130.2         3.2         44.5           100         6         152.4         R1006L         2,029         288.8         438.2         165.1         25.4         130.2         3.2         44.5           100         10         254.0         R1010L         3,382         386.8         159.8         165.1         25.4         130.2         3.2         44.5           100         10         254.0         R1010L         3,382         387.4         641.4         165.1         25.4         130.2         3.2         44.5           150         2				DEEDL								
555         6         152.4         R556L         1,087         263.5         415.9         125.4         25.4         95.3         3.2         36.5           55         10         254.0         R5510L         1,812         365.1         619.1         125.4         25.4         95.3         3.2         36.5           100         2         50.8         R1002L         676         184.2         235.0         155.1         25.4         95.3         3.2         345.5           100         4         101.6         R1004L         1,353         235.0         336.6         165.1         25.4         130.2         3.2         44.5           100         8         203.2         R1068L         2,705         336.6         539.8         165.1         25.4         130.2         3.2         44.5           100         10         254.0         R101.6         17004L         4,058         348.2         165.1         25.4         130.2         3.2         44.5           100         12         348.8         R101.1         4,053         348.2         245.1         130.2         3.2         44.5           150         10         254.0         R1001				1	<b>+</b>							
55         8         203.2         R\$588.         1,449         314.3         517.5         125.4         25.4         95.3         3.2         36.5           55         10         24.0         R\$510.         1,812         365.1         619.1         125.4         25.4         95.3         3.2         34.5           100         4         101.6         R1004.         1,353         235.0         336.6         165.1         25.4         130.2         3.2         44.5           100         6         152.4         R1006.         2,029         285.8         438.2         165.1         25.4         130.2         3.2         44.5           100         8         203.2         R1008.         2,705         336.6         165.1         25.4         130.2         3.2         44.5           100         10         254.0         R10010.         3,382         387.4         661.4         165.1         25.4         130.2         3.2         44.5           100         10         254.0         R10010.         3,382         387.4         661.4         266.4         257.2         204.8         31.8         186.8         3.2         44.5 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>												
100												
100												
100												
100				<del> </del>	1							
100												
100												
100												
150												
150					-							
150				1								
150					†							
150					<del>                                     </del>							
150												
200         2         50.8         R2002L         1,354         241.3         292.1         235.0         41.3         184.2         3.2         50.8           200         4         101.6         R2004L         2,707         292.1         393.7         235.0         41.3         184.2         3.2         50.8           200         8         203.2         R2008L         5,415         393.7         596.9         235.0         41.3         184.2         3.2         50.8           200         10         254.0         R20010L         6,769         444.5         698.5         235.0         41.3         184.2         3.2         50.8           200         12         304.8         R20012L         1,860         247.7         298.5         235.0         41.3         184.2         3.2         50.8           280         2         50.8         R2802L         1,860         247.7         298.5         276.2         47.6         215.9         3.2         57.2           280         4         101.6         R2804L         3,720         298.5         400.1         276.2         47.6         215.9         3.2         57.2           280 <t< td=""><td></td><td></td><td></td><td></td><td>-</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>					-							
200         4         101.6         R2004L         2,707         292.1         393.7         235.0         41.3         184.2         3.2         50.8           200         6         152.4         R2006L         4,061         342.9         495.3         235.0         41.3         184.2         3.2         50.8           200         10         254.0         R2001DL         6,769         444.5         698.5         235.0         41.3         184.2         3.2         50.8           200         12         304.8         R20012L         8,122         495.3         800.1         235.0         41.3         184.2         3.2         50.8           280         2         50.8         R2802L         1,860         247.7         298.5         276.2         47.6         215.9         3.2         57.2           280         4         101.6         R2804L         3,720         298.5         400.1         276.2         47.6         215.9         3.2         57.2           280         6         152.4         R2806L         7,439         400.1         603.3         276.2         47.6         215.9         3.2         57.2           280         <												
200   6												
200				1	<del> </del>							
200					t							
200					<u> </u>							
280         2         50.8         R2802L         1,860         247.7         298.5         276.2         47.6         215.9         3.2         57.2           280         4         101.6         R2804L         3,720         298.5         400.1         276.2         47.6         215.9         3.2         57.2           280         6         152.4         R2806L         5,579         349.3         501.7         276.2         47.6         215.9         3.2         57.2           280         8         203.2         R2801L         7,439         400.1         603.3         276.2         47.6         215.9         3.2         57.2           280         10         254.0         R28010L         9,299         450.9         704.9         276.2         47.6         215.9         3.2         57.2           280         12         304.8         R28012L         11,159         501.7         806.5         276.2         47.6         215.9         3.2         57.2           280         12         304.8         R3552L         2,323         292.1         344.5         298.5         54.0         241.3         3.2         60.3           355				1								
280         4         101.6         R2804L         3,720         298.5         400.1         276.2         47.6         215.9         3.2         57.2           280         6         152.4         R2806L         5,579         349.3         501.7         276.2         47.6         215.9         3.2         57.2           280         10         254.0         R28010L         9,299         450.9         704.9         276.2         47.6         215.9         3.2         57.2           280         12         304.8         R28012L         11,159         501.7         806.5         276.2         47.6         215.9         3.2         57.2           355         2         50.8         R3552L         2,323         292.1         342.9         244.6         215.9         3.2         60.3           355         4         101.6         R3554L         4,646         342.9         444.5         298.5         54.0         241.3         3.2         60.3           355         8         203.2         R3558L         9,292         444.5         298.5         54.0         241.3         3.2         60.3           355         8         203.2 <td< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></td<>												
280         6         152.4         R2806L         5,579         349.3         501.7         276.2         47.6         215.9         3.2         57.2           280         8         203.2         R2808L         7,439         400.1         603.3         276.2         47.6         215.9         3.2         57.2           280         10         254.0         R28010L         9,299         450.9         704.9         276.2         47.6         215.9         3.2         57.2           280         12         304.8         R28012L         11,159         501.7         806.5         276.2         47.6         215.9         3.2         57.2           355         2         50.8         R3552L         2,323         292.1         342.9         298.5         54.0         241.3         3.2         60.3           355         4         101.6         R3556L         4,666         342.9         444.5         298.5         54.0         241.3         3.2         60.3           355         6         152.4         R3556L         4,669         393.7         546.1         298.5         54.0         241.3         3.2         60.3           355				1								
280         8         203.2         R2808L         7,439         400.1         603.3         276.2         47.6         215.9         3.2         57.2           280         10         254.0         R28010L         9,299         450.9         704.9         276.2         47.6         215.9         3.2         57.2           280         12         304.8         R28012L         11,159         501.7         806.5         276.2         47.6         215.9         3.2         57.2           355         2         50.8         R3552L         2,323         292.1         342.9         298.5         54.0         241.3         3.2         60.3           355         4         101.6         R3554L         4,646         342.9         444.5         298.5         54.0         241.3         3.2         60.3           355         6         152.4         R3556L         6,969         393.7         546.1         298.5         54.0         241.3         3.2         60.3           355         8         203.2         R3558L         9,292         444.5         647.7         298.5         54.0         241.3         3.2         60.3           355				1	†							
280         10         254.0         R28010L         9,299         450.9         704.9         276.2         47.6         215.9         3.2         57.2           280         12         304.8         R28012L         11,159         501.7         806.5         276.2         47.6         215.9         3.2         57.2           355         2         50.8         R3552L         2,323         292.1         342.9         298.5         54.0         241.3         3.2         60.3           355         4         101.6         R3554L         4,646         342.9         444.5         298.5         54.0         241.3         3.2         60.3           355         6         152.4         R3556L         6,969         393.7         546.1         298.5         54.0         241.3         3.2         60.3           355         10         254.0         R3551L         11,616         495.3         749.3         298.5         54.0         241.3         3.2         60.3           355         10         254.0         R3551L         13,939         546.1         850.9         298.5         54.0         241.3         3.2         60.3           355												
280         12         304.8         R28012L         11,159         501.7         806.5         276.2         47.6         215.9         3.2         57.2           355         2         50.8         R3552L         2,323         292.1         342.9         298.5         54.0         241.3         3.2         60.3           355         4         101.6         R3554L         4,646         342.9         444.5         298.5         54.0         241.3         3.2         60.3           355         6         152.4         R3556L         6,969         393.7         546.1         298.5         54.0         241.3         3.2         60.3           355         8         203.2         R3558L         9,292         444.5         647.7         298.5         54.0         241.3         3.2         60.3           355         10         254.0         R35510L         11,616         495.3         749.3         298.5         54.0         241.3         3.2         60.3           355         12         304.8         R35512L         13,939         546.1         850.9         298.5         54.0         241.3         3.2         60.3           430												
355				<del> </del>								
355         4         101.6         R3554L         4,646         342.9         444.5         298.5         54.0         241.3         3.2         60.3           355         6         152.4         R3556L         6,969         393.7         546.1         298.5         54.0         241.3         3.2         60.3           355         8         203.2         R3558L         9,292         444.5         647.7         298.5         54.0         241.3         3.2         60.3           355         10         254.0         R35510L         11,616         495.3         749.3         298.5         54.0         241.3         3.2         60.3           355         12         304.8         R35512L         13,939         546.1         850.9         298.5         54.0         241.3         3.2         60.3           430         2         50.8         R4302L         2,838         333.4         384.2         380.2         63.5         266.7         3.2         69.9           430         4         101.6         R4304L         5,676         384.2         485.8         330.2         63.5         266.7         3.2         69.9           430												
355         6         152.4         R3556L         6,969         393.7         546.1         298.5         54.0         241.3         3.2         60.3           355         8         203.2         R3558L         9,292         444.5         647.7         298.5         54.0         241.3         3.2         60.3           355         10         254.0         R35510L         11,616         495.3         749.3         298.5         54.0         241.3         3.2         60.3           355         12         304.8         R35512L         13,939         546.1         850.9         298.5         54.0         241.3         3.2         60.3           430         2         50.8         R4302L         2,838         333.4         384.2         330.2         63.5         266.7         3.2         69.9           430         4         101.6         R4304L         5,676         384.2         485.8         330.2         63.5         266.7         3.2         69.9           430         6         152.4         R4306L         8,514         435.0         587.4         330.2         63.5         266.7         3.2         69.9           430												
355         8         203.2         R3558L         9,292         444.5         647.7         298.5         54.0         241.3         3.2         60.3           355         10         254.0         R35510L         11,616         495.3         749.3         298.5         54.0         241.3         3.2         60.3           355         12         304.8         R35512L         13,939         546.1         850.9         298.5         54.0         241.3         3.2         60.3           430         2         50.8         R4302L         2,838         333.4         384.2         330.2         63.5         266.7         3.2         69.9           430         4         101.6         R4304L         5,676         384.2         485.8         330.2         63.5         266.7         3.2         69.9           430         6         152.4         R4306L         8,514         435.0         587.4         330.2         63.5         266.7         3.2         69.9           430         8         203.2         R4308L         11,352         485.8         689.0         330.2         63.5         266.7         3.2         69.9           430				<del> </del>								
355   10   254.0   R35510L   11,616   495.3   749.3   298.5   54.0   241.3   3.2   60.3					<u> </u>							
355         12         304.8         R35512L         13,939         546.1         850.9         298.5         54.0         241.3         3.2         60.3           430         2         50.8         R4302L         2,838         333.4         384.2         330.2         63.5         266.7         3.2         69.9           430         4         101.6         R4304L         5,676         384.2         485.8         330.2         63.5         266.7         3.2         69.9           430         6         152.4         R4306L         8,514         435.0         587.4         330.2         63.5         266.7         3.2         69.9           430         8         203.2         R4308L         11,352         485.8         689.0         330.2         63.5         266.7         3.2         69.9           430         10         254.0         R43010L         14,190         536.6         790.6         330.2         63.5         266.7         3.2         69.9           430         12         304.8         R43012L         17,028         587.4         892.2         330.2         63.5         266.7         3.2         69.9           565												
430         2         50.8         R4302L         2,838         333.4         384.2         330.2         63.5         266.7         3.2         69.9           430         4         101.6         R4304L         5,676         384.2         485.8         330.2         63.5         266.7         3.2         69.9           430         6         152.4         R4306L         8,514         435.0         587.4         330.2         63.5         266.7         3.2         69.9           430         8         203.2         R4308L         11,352         485.8         689.0         330.2         63.5         266.7         3.2         69.9           430         10         254.0         R43010L         14,190         536.6         790.6         330.2         63.5         266.7         3.2         69.9           430         12         304.8         R43012L         17,028         587.4         892.2         330.2         63.5         266.7         3.2         69.9           565         2         50.8         R5652L         3,707         371.2         422.0         377.8         69.9         304.8         3.2         79.4           565												
430         4         101.6         R4304L         5,676         384.2         485.8         330.2         63.5         266.7         3.2         69.9           430         6         152.4         R4306L         8,514         435.0         587.4         330.2         63.5         266.7         3.2         69.9           430         8         203.2         R4308L         11,352         485.8         689.0         330.2         63.5         266.7         3.2         69.9           430         10         254.0         R43010L         14,190         536.6         790.6         330.2         63.5         266.7         3.2         69.9           430         12         304.8         R43012L         17,028         587.4         892.2         330.2         63.5         266.7         3.2         69.9           565         2         50.8         R5652L         3,707         371.2         422.0         377.8         69.9         304.8         3.2         79.4           565         4         101.6         R5654L         7,413         422.0         523.6         377.8         69.9         304.8         3.2         79.4           565					-							
430         6         152.4         R4306L         8,514         435.0         587.4         330.2         63.5         266.7         3.2         69.9           430         8         203.2         R4308L         11,352         485.8         689.0         330.2         63.5         266.7         3.2         69.9           430         10         254.0         R43010L         14,190         536.6         790.6         330.2         63.5         266.7         3.2         69.9           430         12         304.8         R43012L         17,028         587.4         892.2         330.2         63.5         266.7         3.2         69.9           565         2         50.8         R5652L         3,707         371.2         422.0         377.8         69.9         304.8         3.2         79.4           565         4         101.6         R5654L         7,413         422.0         523.6         377.8         69.9         304.8         3.2         79.4           565         6         152.4         R5656L         11,120         473.1         625.5         377.8         69.9         304.8         3.2         79.4           565				1								
430       8       203.2       R4308L       11,352       485.8       689.0       330.2       63.5       266.7       3.2       69.9         430       10       254.0       R43010L       14,190       536.6       790.6       330.2       63.5       266.7       3.2       69.9         430       12       304.8       R43012L       17,028       587.4       892.2       330.2       63.5       266.7       3.2       69.9         565       2       50.8       R5652L       3,707       371.2       422.0       377.8       69.9       304.8       3.2       79.4         565       4       101.6       R5654L       7,413       422.0       523.6       377.8       69.9       304.8       3.2       79.4         565       6       152.4       R5656L       11,120       473.1       625.5       377.8       69.9       304.8       3.2       79.4         565       8       203.2       R5658L       14,827       523.9       727.1       377.8       69.9       304.8       3.2       79.4         565       10       254.0       R56510L       18,533       574.7       828.7       377.8       69.9 <td></td> <td></td> <td></td> <td>1</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>				1								
430         10         254.0         R43010L         14,190         536.6         790.6         330.2         63.5         266.7         3.2         69.9           430         12         304.8         R43012L         17,028         587.4         892.2         330.2         63.5         266.7         3.2         69.9           565         2         50.8         R5652L         3,707         371.2         422.0         377.8         69.9         304.8         3.2         79.4           565         4         101.6         R5654L         7,413         422.0         523.6         377.8         69.9         304.8         3.2         79.4           565         6         152.4         R5656L         11,120         473.1         625.5         377.8         69.9         304.8         3.2         79.4           565         8         203.2         R5658L         14,827         523.9         727.1         377.8         69.9         304.8         3.2         79.4           565         10         254.0         R56510L         18,533         574.7         828.7         377.8         69.9         304.8         3.2         79.4           565												
430         12         304.8         R43012L         17,028         587.4         892.2         330.2         63.5         266.7         3.2         69.9           565         2         50.8         R5652L         3,707         371.2         422.0         377.8         69.9         304.8         3.2         79.4           565         4         101.6         R5654L         7,413         422.0         523.6         377.8         69.9         304.8         3.2         79.4           565         6         152.4         R5656L         11,120         473.1         625.5         377.8         69.9         304.8         3.2         79.4           565         8         203.2         R5658L         14,827         523.9         727.1         377.8         69.9         304.8         3.2         79.4           565         10         254.0         R56510L         18,533         574.7         828.7         377.8         69.9         304.8         3.2         79.4           565         12         304.8         R56512L         22,240         625.5         930.3         377.8         69.9         304.8         3.2         79.4           565												
565         2         50.8         R5652L         3,707         371.2         422.0         377.8         69.9         304.8         3.2         79.4           565         4         101.6         R5654L         7,413         422.0         523.6         377.8         69.9         304.8         3.2         79.4           565         6         152.4         R5656L         11,120         473.1         625.5         377.8         69.9         304.8         3.2         79.4           565         8         203.2         R5658L         14,827         523.9         727.1         377.8         69.9         304.8         3.2         79.4           565         10         254.0         R56510L         18,533         574.7         828.7         377.8         69.9         304.8         3.2         79.4           565         12         304.8         R56512L         22,240         625.5         930.3         377.8         69.9         304.8         3.2         79.4           660         *R6606L         13,051         553.7         706.1         419.1         330.2         88.9           880         6         152.4         *R8806L         17,375 <td></td>												
565         4         101.6         R5654L         7,413         422.0         523.6         377.8         69.9         304.8         3.2         79.4           565         6         152.4         R5656L         11,120         473.1         625.5         377.8         69.9         304.8         3.2         79.4           565         8         203.2         R5658L         14,827         523.9         727.1         377.8         69.9         304.8         3.2         79.4           565         10         254.0         R56510L         18,533         574.7         828.7         377.8         69.9         304.8         3.2         79.4           565         12         304.8         R56512L         22,240         625.5         930.3         377.8         69.9         304.8         3.2         79.4           660         *R6606L         13,051         553.7         706.1         419.1         330.2         88.9           880         6         152.4         *R8806L         17,375         609.6         762.0         495.3         381.0         101.6												
565         6         152.4         R5656L         11,120         473.1         625.5         377.8         69.9         304.8         3.2         79.4           565         8         203.2         R5658L         14,827         523.9         727.1         377.8         69.9         304.8         3.2         79.4           565         10         254.0         R56510L         18,533         574.7         828.7         377.8         69.9         304.8         3.2         79.4           565         12         304.8         R56512L         22,240         625.5         930.3         377.8         69.9         304.8         3.2         79.4           660         *R6606L         13,051         553.7         706.1         419.1         330.2         88.9           880         6         152.4         *R8806L         17,375         609.6         762.0         495.3         381.0         101.6					· ·							
565     8     203.2     R5658L     14,827     523.9     727.1     377.8     69.9     304.8     3.2     79.4       565     10     254.0     R56510L     18,533     574.7     828.7     377.8     69.9     304.8     3.2     79.4       565     12     304.8     R56512L     22,240     625.5     930.3     377.8     69.9     304.8     3.2     79.4       660     *R6606L     13,051     553.7     706.1     419.1     330.2     88.9       880     6     152.4     *R8806L     17,375     609.6     762.0     495.3     381.0     101.6				1								
565     10     254.0     R56510L     18,533     574.7     828.7     377.8     69.9     304.8     3.2     79.4       565     12     304.8     R56512L     22,240     625.5     930.3     377.8     69.9     304.8     3.2     79.4       660     *R6606L     13,051     553.7     706.1     419.1     330.2     88.9       880     6     152.4     *R8806L     17,375     609.6     762.0     495.3     381.0     101.6					-							
565     12     304.8     R56512L     22,240     625.5     930.3     377.8     69.9     304.8     3.2     79.4       660     *R6606L     13,051     553.7     706.1     419.1     330.2     88.9       880     6     152.4     *R8806L     17,375     609.6     762.0     495.3     381.0     101.6												
660     *R6606L     13,051     553.7     706.1     419.1     330.2     88.9       880     6     152.4     *R8806L     17,375     609.6     762.0     495.3     381.0     101.6												
880 6 152.4 *R8806L 17,375 609.6 762.0 495.3 381.0 101.6		12	304.8						69.9		3.2	
		_	450.4	-	†		•					
1,140     *K11406L  22,317   665.5   817.9   571.5   431.8   114.3		6	152.4		<del></del>							
	1,140			*K11406L	22,317	665.5	817.9	5/1.5		431.8		114.3

<sup>\* &#</sup>x27;-QC1 Special Cylinders' complete with wear rings, integral swivel cap & base mounting holes. Stroke available in 2" (50.8mm) increment up to 12" (304.8mm). Consult factory for details.




## **POSITIVE MECHANICAL LOCK** to Support Load



#### Recommendation

Use Swivel Caps (Optional) to reduce the effects of off-center loading.

- Tilts up to 5°.
- Radial grooves on top of cap reduce load slippage.
  Notch across face of each cap helps keep loads having a protruding or round shaped centered.



						Х	Y		
Cylinder	Bore Diameter	Effective Area	Metric Tons at	Weight	Swivel Cap Order No.	Swivel Cap Protrusion	Swivel Cap Diameter	Retracted Ht. (Cap & Cyl.)	Weight (Cap & Cyl.)
Order No.	(mm)	(cm²)	690 bar	(kg)	(Optional)	(mm)	(mm)	(mm)	(kg)
R552L	95.3	71.2	50.1	15,3	420866	25.4	71.4	187.3	16.1
R554L	95.3	71,2	50.1	20.8	420866	25.4	71.4	238.1	21.6
R556L	95.3	71.2	50.1	26.3	420866	25.4	71.4	288.9	27.1
R558L	95.3	71.2	50.1	31.3	420866	25.4	71.4	339,7	32.1
R5510L	95.3	71.2	50,1	36.3	420866	25.4	71.4	390.5	37,1
R1002L	130.2	133.1	93.6	30.0	420866	25.4	71.4	209.6	30.8
R1004L	130.2	133.1	93.6	38.4	420866	25.4	71.4	260.4	39.2
R1006L	130.2	133.1	93.6	46.8	420866	25.4	71.4	311.2	47.6
R1008L	130.2	133.1	93.6	55.7	420866	25.4	71.4	362.0	56.5
R10010L	130.2	133.1	93.6	64.5	420866	25.4	71.4	412.8	65.3
R10012L	130.2	133.1	93.6	73.4	420866	25.4	71.4	463.6	74.2
R1502L	158.8	197.9	139.1	53.0	420867	38.1	130.2	244.5	57.0
R1504L	158.8	197.9	139.1	66.7	420867	38.1	130.2	295.3	70.7
R1506L	158.8	197.9	139.1	80.4	420867	38.1	130.2	346.1	84.4
R1508L	158.8	197.9	139.1	94.1	420867	38,1	130,2	396.9	98.1
R15010L	158.8	197.9	139.1	107.8	420867	38.1	130.2	447.7	111.8
R15012L	158.8	197.9	139.1	121.5	420867	38.1	130.2	498.5	125.5
R2002L	184.2	266.3	187.2	83.1	420867	38.1	130.2	279.4	87.1
R2004L	184.2	266.3	187.2	100.4	420867	38.1	130.2	330.2	104.4
R2006L	184.2	266.3	187.2	117.6	420867	38,1	130.2	381.0	121.6
R2008L	184.2	266.3	187.2	134.9	420867	38.1	130.2	431.8	138.9
R20010L	184.2	266.3	187.2	152.1	420867	38.1	130.2	482.6	156.1
R20012L	184.2	266.3	187.2	169.4	420867	38.1	130.2	533.4	173.4
R2802L	215.9	366.0	257.3	118.5	420868	44.5	149.2	292.2	124.6
R2804L	215.9	366.0	257.3	140.8	420868	44.5	149.2	343.0	146.9
R2806L	215.9	366.0	257.3	163.0	420868	44.5	149.2	393.8	169.1
R2808L	215.9	366.0	257.3	185.6	420868	44.5	149.2	444.6	191.7
R28010L	215.9	366.0	257.3	208.1	420868	44.5	149.2	495.4	214.2
R28012L	215.9	366.0	257.3	230.7	420868	44.5	149.2	546.2	236.8
R3552L	241.3	457.2	321.4	173.0	420869	69.9	195.3	362.0	189.8
R3554L	241.3	457.2	321.4	202.8	420869	69.9	195.3	412.8	219.6
R3556L	241.3	457.2	321.4	232.5	420869	69.9	195.3	463.6	249.3
R3558L	241.3	457.2	321.4	262.3	420869	69.9	195.3	514.4	279.1
R35510L	241.3	457.2	321.4	292.0	420869	69.9	195.3	565.2	308.8
R35512L	241.3	457.2	321.4	321.8	420869	69.9	195.3	616.0	338.6
R4302L	266.7	558.5	392.6	252.4	420870	79.4	225,4	412.8	276.0
R4304L	266.7	558.5	392.6	290.8	420870	79.4	225.4	463.6	314.4
R4306L	266.7	558.5	392.6	329.2	420870	79.4	225.4	514.4	352.8
R4308L	266.7	558.5	392.6	367.6	420870	79.4	225.4	565.2	391.2
R43010L	266.7	558.5	392.6	405.9	420870	79.4	225.4	616.0	429.5
R43012L	266.7	558.5	392.6	444.3	420870	79.4	225.4	666.8	467.9
R5652L	304.8	729.5	512.8	368.2	420871	92.1	250.8	463.3	403.6
R5654L	304.8	729.5	512.8	418.1	420871	92.1	250.8	514.1	453.5
R5656L	304.8	729.5	512.8	468.0	420871	92.1	250.8	565.2	503.4
R5658L	304.8	729.5	512.8	518.0	420871	92.1	250.8	616.0	553.4
R56510L	304.8	729.5	512.8	568.0	420871	92.1	250.8	666.8	603.4
R56512L	304.8	729.5	512.8	618.0	420871	92.1	250.8	717.6	653.4
*R6606L	330.2	856.3	600.0	568.3			254.0	553.7	568.3
*R8806L	381.0	1,140.1	800.0	871.8			292.1	609.6	871.8
*R11406L	431.8	1,464.4	1,000.0	1,262.0			317.5	665.5	1,262.0

Note: Supported loads not to exceed the rated capacity of the cylinders. Not intended to support additional dynamic loads, such as those applied by moving vehicles.

### **LOCKING COLLAR**

RL Series Cylinders Aluminum
55 & 100 Ton
Single-Acting, Spring-Return
700 bar (10,000 psi)



## POSITIVE MECHANICAL LOCK TO SUPPORT LOAD.

- Supports lifted load for extended periods of time with hydraulic pressure released.
- At half the weight of steel cylinders of comparable capacity, aluminum cylinders are ideal when portability is a key factor.
- Feature carrying handle.






Locking collar feature permits non-hydraulic support of load.




RA1006L

ASME B30.1

700 bar





		SWIVEL CAPS reduce the effect off center loading. Tilts up to (Available as optional)								
Cylinder Tonnage	Swivel Cap Order No.	Wt. (kg.)	A (mm)	B (mm)	C (mm)					
55	Q99-1000	0,9	31,8	63,2	71,4					

Cyl. Cap. Strol	Order se No.	Oil Cap.	A Retracted Ht.	B Extended Ht.	C Outside Dia.	F Base to Port	H Piston Rod Dia.	K Piston Rod Protrusion	T Nut nThickness	Bore Dia.	Cylinder Effective Area	Metric Tons at 700	Weight
(Tons) (mm		(cm³)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(cm²)	bar	(kg)
<b>55</b> 155,	5 <b>RA556L</b>	1.109	317,5	473,1	133,4	34,9	82,6	12,7	38,1	95,3	71,2	50,1	13,4
<b>100</b> 158,	8 <b>RA1006L</b>	2.116	339,7	498,5	187,3	30,2	114,3	6,4	38,1	130,2	133,0	93,5	29,1

Note: Supported loads not to exceed the rated capacity of the cylinders. Not intended to support additional dynamic loads, such as those applied by moving vehicles.

## PANCAKE LOCKING COLLAR


PLC Series Cylinders 67 - 565 Ton Single-Acting, Load-Return 700 bar (10,000 psi)

#### POSITIVE MECHANICAL LOCK TO SUPPORT LOAD. IDEAL FOR CONFINED AREA APPLICATIONS.

- Compact design for use where space is limited
- Locking collar designed to support lifted load for extended periods of time with hydraulic pressure released
- Overflow port ("weep hole") prevents piston from being overextended under load.
- Special coating improves corrosion and abrasion resistance
- Cylinders come standard with hardened caps. Swivel caps reduce the effects of off-center loading and improves performance under side load.
- Equipped with 3/8" NPTF female half couplers








Integral Swivel Cap reduces the effects of off center loading.

Tilts up to 5 degrees.

Radial grooves on top of cap reduce load slippage.




Cyl. Cap. (Tons)	Stroke (mm)	Order Oil No. Cap. (cm³)		Retracted Extended Ht. Ht. (mm) (mm) 1.25.7 176.5		B Outside Dia. (mm)	D Piston Rod Dia (mm)	F Nut Thickness (mm)	C Bore Dia. (mm)	Cylinder Effective Area (cm²)	Metric Tons at 700 bar	Weight (kg)
67	50.8	PLC672	437	125.7	176.5	147.3	104.4	24.1	104.7	86.09	61	15.0
110	50.8	PLC1102	745	137.7	188.5	177.8	136.7	30.5	136.7	146.66	103	26.0
180	50.8	PLC1802	1,176	153.9	204.7	228.6	171.7	38.1	171.7	231.55	163	44.0
220	50.8	PLC2202	1,448	160.8	211.6	254.0	190.5	40.6	190.5	285.02	200	57.0
280	50.8	PLC2802	1,860	164.8	215.6	279.4	215.9	41.9	215.9	366.10	257	75.0
430	45	PLC4302	2,514	183.9	228.9	355.6	266.7	55.5	266.7	558.65	393	134.0
565	45	PLC5652	3,283	197.9	242.9	406.4	304.8	59.7	304.8	729.66	513	189.0

#### THREADED END

**CBT** Series Cylinders 5 - 25 Tons Single-Acting, Spring-Return 700 bar (10,000 psi)





## THREADED PISTON ROD END AND BASE THREADS

## ACCOMMODATE ACCESSORIES AND ADAPTERS.

 Threaded cylinder collars, piston rod ends, and internal base threads simplify mounting.

• Plated piston rod resists wear and corrosion.

 A 9796 3/8" NPTF female half coupler is standard with each cylinder; oil port threads are 3/8" NPTF.



ASME B30.1 700 bar



	Stroke (mm)	Order No.	Oil Cap. (cm³)	A Re- tracted Height (mm)	B Ex- tended Height (mm)		D Collar Thread (in.)	E Collar Thread Length (mm)	F Base to Port (mm)	H Piston Rod Dia. (in.)	Rod	P Piston Rod Thread (NPT)	Q Internal Base Thread (NPSM) (in.)	Bore Dia. (mm)	Cyl. Eff. Area (cm²)	Metric Tons at 700 bar	Weight (kg)
<b>01</b> –	133,4	C55CBT	85	266,7	400,1	38,1	11/2-16	28,6	47,6	25,4	28,6	3/4-14	3/4-14	28,6	6,4	4,5	2,0
10	,	C106CBT C1010CBT	228 375		447,7 650,9		2 <sup>1</sup> / <sub>4</sub> –14 2 <sup>1</sup> / <sub>4</sub> –14		42,9 42,9	38,1 38,1	27,0 27,0	1 <sup>1</sup> / <sub>4</sub> -11 <sup>1</sup> / <sub>2</sub> 1 <sup>1</sup> / <sub>4</sub> -11 <sup>1</sup> / <sub>2</sub>	$1^{1}/_{4}$ – $11^{1}/_{2}$ $1^{1}/_{4}$ – $11^{1}/_{2}$	27,0 27,0	14,4 14,4	10,2 10,2	4,7 6,3
25	158,8 362,0	C256CBT C2514CBT	528 1205	339,7 542,9	498,5 904,9		$3^{5}/_{16}$ –12 $3^{5}/_{16}$ –12	49,2 49,2	47,6 47,6	57,2 57,2	47,6 47,6	$2-11^{1}/_{2}$ $2-11^{1}/_{2}$	2-11 <sup>1</sup> / <sub>2</sub> 2-11 <sup>1</sup> / <sub>2</sub>	47,6 47,6	33,3 33,3	23,4 23,4	11,1 18,2

## PULLING

**RP** Series Cylinders


## 2 & 5 Ton Single-Acting, Spring-Return 700 bar (10,000 psi)

#### DESIGNED FOR PULLING AND TENSIONING.

- Heavy duty compression spring provides long cycle life and rapid extension of piston.
- Spring automatically extends piston rod when pump pressure is released.




	Stroke (mm)	Order No.					Thread	Thread	Top to Port	Rod	Rod Protrusion	P Piston Rod Thread (NPTF)		Dia.		Metric Tons at 700 bar Pull	Weight (kg)
2	127,0	RP25	45	242,9	379,9	44,5	1 1/2-16	25,4	42,9	19,1	25,4	3/4-14	<sup>3</sup> / <sub>4</sub> <b>-1</b> 4	28,6	3,5	2,5	1,8
_ 5	139,7	RP55	102	301,6	441,3	57,2	2 1/4-14	25,4	42,9	30,2	34,9	11/4-111/2	11/4-111,	/2 42,9	7,3	5,1	5



#### Clevis ORDERING INFORMATION (optional)

Use with	Order	Α	В	С	D	Е	
Cyl No.	No.	(mm)	(mm)	(mm)	(mm)	(mm)	
RP25	421057*	130,3	109,5	33,3	50,8	19,1	
RP55	421056**	152,4	127,0	38,1	63,5	22,4	

<sup>\*</sup> For base mounting, extension rod 351106 is required.



<sup>\*\*</sup> For base mounting, extension rod 351075 is required.

#### HIGH PERFORMANCE HYDRAULIC PUMPS

Page PUMP SELECTION...34-36

Page HB44...47

Intensifier

PE55...56, 57 Vanguard® Electric

Page

Hydraulic

Page



Page P SERIES...37-39

Hand Pumps

Page

PE10, PR10... 48.49

Electric / Battery

PQ60...58 Quiet Electric Hydraulic



Page

PA6, PA6D... 40, 41



Page PE17...50

Electric Hydraulic



Page

PQ120...59

Quiet Electric Hydraulic



Page PA60...42

Air Hydraulic

Air Hydraulic



Page PE18...51

Vanguard Jr.® Electric Hydraulic



Page PE400...60

Electric Hydraulic



Page

PA9...43



Page PE21...52

Electric Hydraulic



Page

PG30/55...61 Gasoline Driven



Page PA17...44

Air Hydraulic



Page PED25...53

Electric Hydraulic

Page



Page PG120-

PG400...62, 63



Gasoline Driven



64-67

**ACCESSORIES...** 



Page 4 PA46/55...45

Air Hydraulic



Page PE46...55

PE30...54

Electric Hydraulic

Electric Hydraulic



PA50...46



#### PUMP SELECTION

High Performance
Choose the Right Pump













Air/Hydraulic Pumps

Electric/Hydraulic Pumps

Gasoline-driven Hydraulic Pumps

- Step 1 Select the hydraulic cylinder that best suits the application (See page 11-32).
- Select the series of hydraulic pump with adequate oil output and reservoir capacity to power cylinder(See page 35, 37-63).
   Check speed/selection chart, consult factory. (See page 36)
- **Step 3** Select pump within series with the valve option that is best suited to the cylinder and application (See page 76-81, 84).

#### **CONSIDERATIONS:**


What maximum system operating pressure (bar) is required? What volume of oil delivery is required? (For manual pumps, cm³ of oil per handle stroke; for powered pumps, I/min. of oil).

Is a single- or 2-speed pump required? (2-speed pumps deliver high oil volume at low pressure for rapid cylinder piston advance, then shift to to the high pressure, low volume stage under load). What is the preferred source of power?

- a) Manual (hand or foot operated). Provides portability, can be used where electricity or shop air are not available.
- b) Air/Hydraulic. Uses shop air or a portable air compressor. Ideal for use in petrochemical, mines or other inflammable or explosive environments.
- c) Electric /Hydraulic. What voltage is available? Is a battery operated pump preferred?

- d) Gasoline Engine/Hydraulic. Powers high-output pumps at remote job sites where air or electricity are unavailable.
- Is portability of the pump a factor to consider?
- Will the pump be used intermittently, or will it need to provide high-cycle operation? Does the application require that the pump be capable of starting under load?
- Is fluid heat build-up a factor in your application?
   High cycle applications may require a larger capacity oil
   reservoir for cooling. Also, if you are using large
   displacement cylinders, the reservoir capacity must be
   sufficient to fully extend the piston of the cylinder.
- Will the application require large displacement or multiple cylinders? Reservoir size and pump output levels will be factors to consider.
- Does the working environment require a pump having a low operating noise (dBA) level?
- Must the pump operate in a spark-free environment?

## **PUMP SELECTION** 700 bar (10,000 psi)





### **PUMP CAPACITY**


Selection Chart **Choosing the Right Pump** and Cylinder

The following guidelines are for general lifting and construction applications. Hydraulic tools, pullers and presses may fall outside these

recommendations. Always check to see that the pump's "usable reservoir capacity" exceeds the cylinder(s) oil capacity.

Generally Marginal **Not Recommended for** most applications **Check Requirements** Recommended

					bar Marking Pr													
		Page		PRESSURE STAGE		Cyli	nder Ca	pacity (T	ons)									
		No.		lacksquare	5	10	15	20	25	30	55	75	100	150	200	300	400	500
_	Hand Pumps*	37	P12‡	Single	14	32	44	65	72	93								
	manu i umps	37	P55‡	Single	6	14	19	28	31	40	71							
		38	P19/	Low	4	8	10	15	17	21								
S	-		P19L	High	13	30	42	59	68	86	00	00						
M	-97	38	P59F	Low	1,8 8	4,1 17	5,7 24	8 3	9 48	12 50	20 85	29 122						
$\Rightarrow$	1 100	38	P59(L)‡	High Low	1,5	3,2	4,7	7	7,7	9,7	16,7	23,9						
٩	-	39	P157#	High	6	14	19	28	31	40	71	101						
		39	P159#	Low	,5	1	1,3	1,9	2,2	2,8	5	7	9	13	18			
-		39	P300‡	High	7	15	21	30	34	43	77	110	143	200	250			
		39	P460‡	Low	,1	,3	,6	,6	,7	,9	1,5	2,2	2,8	4,2	5,6	8,4	11,2	
				High	3,3	7,7	9	14	17,5	22	37	55	71	105	143	213	284	
-	Electric/	48	PE10	Low	,5	1,2	1,6	2,2	2,6	3,2	5,5							
	Hydraulic		DE4E:	High	6	13,4	18,9	27	31	39	66,2	2.0	4-0-	0.5	0.7			
	Pumps†	50	PE17‡	Low	,2	,5 7.0	,7	,9	1,1	1,4	2,3	3,3	4,3	6,5	8,7			
	The state of the s	51	PE18	High Low	3,5	7,9	10,9 1,2	16 1,6	18 1,8	23 2,3	39 3,9	56,3 5,7	73 7,3	109 10,8	146 14,6	21,9	29,2	
		31	LETO	High	,4 3,3	,8 7,5	10,3	1,6	1,0	2,3 21	3,9 37	5, <i>t</i> 53	69	10,8	136	207	25,2 276	
		52	PE21‡	Low	,2	,5	,7	1,0	1,1	1,4	2,5	3,6	4,6	6,8	9,2	13,8	18,4	
		-		High	2,8	6,4	9	13	15	19	32	45,5	59	88	118	177	236	
		53	PED25	Low	,2	,4	,6	,9	1,0	1,3	2,2	3,2	4,1	6,1	8,3	12,0	15,7	19,9
				High	2,4	5,4	7,5	10,6	12,4	15,6	26,5	38,2	49,5	73,6	99,1	144,3	188,5	238,6
		54	PE30‡	Low	,2	,45	,6	,9	1	1,3	2,2	3,2	4,1	6				
				High	2	4,5	6	9	10	13	22	32	41	60				
	Section 1	55	PE46‡	Low	,1	,3	,4	,5 5.0	,6 C.O	,7	1,3	1,8	2,4	3,5	4,7	7,2	9,6	
	100.0	56-57	PE55‡	High Low	1,3	2,9	4,1	5,9	6,8	8,6	,9	22 1,4	28 1,8	42	56 3,5	84 5,4	112 7,2	
	P2 210	30-37	PE60‡	High	,1 1,1	,2 2,4	,3 3,4	,4 4,8	,4 5,6	,6 7,1	,9 12	17,8	23	2,6 34	3,3 45	69	92	
		58	PQ60	Low	,1	,2	,3	,4	,4	,5	,9	1,3	1,7	2,5	3,4	5,1	6,8	8,5
				High	1	2,2	3,3	4,4	5,2	6,5	11	16,2	21	31	41	63	84	105
	A STATE OF	59	PQ120	Low	,1	,2	,3	,4	,4	,5	,9	1,3	1,7	2,5	3,4	5,1	6,8	8,5
	Sec. 1			High	,5	1,1	1,6	2,2	2,6	3,2	5,5	7,7	10	15	21	30	40	50
	1	60	PE400	Low	,1	,1	,2	,2	,3	,3	,6	8	1	1,5	2,1	3	4	5
		40.41	DACT	High	,1	,3	,4	,6	,7	,9	1,6	2,2	2,9	4,4	5,9	8,7	11,6	14,5
	Air/Hydraulic	40-41	PA6‡ PA9‡	Single	10 10	22,4	31 31	44,4 44,4	51,3	65,2	•	•	•	•	•			
	Pumps†	43 44	PA17‡	Single Low	,2	22,4 ,5	,7	,9	51,3 1,1	65,2 1,4	2,3	3,3	4,3	6,5	8,7			
	-	111	1717	High	3,5	7,9	10,9	16	18	23	39	56	73	109	146	_	_	
	-	45	PA46‡	Low	,1	,3	,4	,5	,6	,7	1,3	2	2,4	3,5	4,7	7,2	9,6	
	5		·	High	1,3	2,9	4,1	5,9	6,8	8,6	14	22	28	56	42	84	112	
	-	45	PA55‡	Low	,1	,3	,4	,6	,7	,9	1,5	2,2	2,8	4,1	5,5	8,4	11,2	
				High	1,1	2,4	3,4	4,8	5,6	7,1	12	18	23	34	45	69	92	
	Gas/Hydraulic	61	PG30	Low	,3	,7	1	1,3	1,6	2	3,3	4,8	6,2	9,3	12,4	18,1	•	
	Pumps†	61	DCEE#	High	2	4,5	6,3	8,9	10,3	13	22	31,8	41,3	61,4	83	121	0.0	12.5
		61	PG55‡	Low High	,1 1,1	,3 2,5	,4 3,5	,6 4,9	,7 5,6	,8 7,1	1,4 12,1	2 17,3	2,6 22,5	3,9 33,5	5,2 45	7,6 66	9,9 86	12,5 109
		62-63	PG120‡	Low	,1	,3	,4	,6	,7	,8	1,4	2	2,5	3,9	5,2	7,6	9,9	109
		J=-03	101204	High	,5	1,0	1,5	2,0	2,4	3,0	5,1	7,3	9,5	14,2	19,1	27,8	36,3	46,0
	d	62-63	PG400	Low	,1	,1	,2	,2	,3	,3	,6	,8	1,0	1,5	2,0	3,0	3,8	4,9
				High	,2	,3	,2 ,5	,7	,8	1,0	1,7	2,4	3,1	4,6	6,2	9,0	11,8	15,0





# BEST SUITED FOR APPLICATIONS WHERE THERE IS LITTLE OR NO FREE TRAVEL.

- All metal construction, won't burn through in welding environments.
- Formed metal handle provides less flex, and reduces operator fatigue.
- Convenient fill port on P23 and P55 allows pumps to be filled in a horizontal or vertical position.
- Fill cap seal acts as safety valve preventing over-pressurizing of reservoir

P55 Hand Pump on an aircraft towbar


- Relief valve inboard of check valve prevents loads from drifting down.
- Large valve knob gives added control for slowly metering loads down.
- Carrying handle on P55.

















HAND PUMP

Hydraulic P Series

197 to 902 cm<sup>3</sup> Reservoir

Single-Speed, Single-Acting

700 bar (10,000 psi)

except P23 (210 bar)

Power Team hand pumps, with the angled fill port, have a built in "relief valve" protection system. This system is designed to protect overpressurization of the reservoir from sudden back pressure. This system also works as a seal to prevent oil leaks.

				Volume 8	& Pressure			Rese	ervoir		
For		•		ime per	Maxi		Handle	Oil	Usable Oil	Oil	Product
Use With	Order No.	Speed	Strol LP	ke (cm³) HP	Pressui LP	re (bar) HP	Effort (kg)	Capacity (cm³)	Capacity (cm³)	Port (in)	Weight (kg))
With	1101	Specu	<b>L</b> I		-		(1/6/	(CIII )	(ciii )	(1117	(u2))
Single	P12	1		1,1	_	700	34	197	148	³/8-NPTF	2,6
Acting	P23	1		2,6	_	210	32	390	333	³/8-NPTF	5,5
Cylinders*	P55	1	_	2,6	_	700	66	902	738	3/8-NPTF	7,2

LP = Low Pressure HP = High Pressure

<sup>\*</sup> Pump includes 2-Way Valve

## HAND PUMP

Hydraulic P Series 400 to 1131 cm<sup>3</sup> Reservoir Two-Speed, Single-Acting 700 bar (10,000 psi)

Lightweight

<u> Aluminium</u>

Design







#### **PUMP AUTOMATICALLY SHIFTS INTO** THE HIGH PRESSURE LIFT STAGE UPON CONTACT WITH THE LOAD.

- All metal construction won't burn through in welding environments.
- Two-speed reduces handle strokes so you work faster and easier.
- Formed metal handle provides less flex, and reduces operator fatigue.
- Convenient fill port allow pumps to be filled in a horizontal or vertical position.
- · Relief valve inboard of check valve prevents loads from drifting down.
- Large valve knob gives added control for slowly metering loads down.
- Carrying handle (except P19).










700 bar

Pump	A	В	C	D	E	F	G	H	J	K	L	M	N
No	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(deg.)	(mm)	(mm)	(in)	(mm)
P19	139,7	371,5	73,0	115,9	347,7	101,6	82,6	281,0	53°	7,9	101,6	3/8-NPTF	35,7
P19L	141,5	_			347	104,1	82,6	281,0	40°	7,9	104,1	³/ <sub>8</sub> -NPTF	
P59	177,8	533,4	88,9	127,0	584,2	108,0	82,6	501,7	38°	7,9	120,7	³/ <sub>8</sub> -NPTF	41,3
P59L	177,6		_		533,4	120,7	82,6	501,7	50°	7,9	120,7	³/ <sub>8</sub> -NPTF	
P59F	88.9	425.5	88.9	152.4	590.6	108.0	82.6	514.4		7.9	114.3	<sup>3</sup> / <sub>8</sub> -NPTF	42.9



Power Team hand pumps, with the angled fill port, have a built in "relief valve" protection system. This system is designed to protect overpressurization of the reservoir from sudden back pressure. This system also works as a seal to prevent oil leaks.

				Volume	& Pressure			Rese	ervoir		
For Use	Order			ne per e (cm³)		mum re (bar)	Handle Effort	Oil Capacity	Usable Oil Capacity	Oil Port	Product Weight
With	No.	Speed	LP	HP	LP	HP	(kg)	(cm³)	(cm³)	(in)	(kg)
*Single	P19	2	5,0	1,2	22	700	45	400	328	3/8-NPTF	3,0
Acting	**P19L	2	4,1	0,9	70	700	37	475	443	3/8-NPTF	2,3
Cylinders	P59	2	10,9	2,6	22	700	66	902	738	<sup>3</sup> /8-NPTF	7,8
	** P59L	2	12	2,6	59	700	44	1131	1082	3/8-NPTF	4,1
	^	2	9,0	2,1	22	700	55	902	738	3/8-NPTF	6,4

LP = Low Pressure HP = High Pressure

<sup>\*</sup> Pump includes 2-Way Valve

<sup>^^</sup> Foot-operated

<sup>\*\*</sup> Lightweight Aluminium Hand Pumps







# PUMP AUTOMATICALLY SHIFTS INTO THE HIGH PRESSURE LIFT STAGE UPON CONTACT WITH THE LOAD.

- Rugged all metal construction for strength and durability that won't burn through in welding environments.
- Heavy-duty, formed metal handle provides less flex, and less operator fatigue than round or composite handles.
- Convenient fill port allows pumps on P157 and P159 to be filled in a horizontal or vertical position.
- Fill cap seal acts as safety valve to prevent over-pressurizing of reservoir.
- Relief valve inboard of check valve prevents loads from drifting down.
- Large valve knob gives added control for slowly metering loads down.
- Carrying handle

700 bar




Hydraulic **P** Series 2,5 I to 9,5 I Reservoir


HAND PUMP

Two-Speed, Singleand Double-Acting 700 bar (10,000 psi)



P300 hand pump and 10 ton cylinders used for a vehicle lift.





Pui No	mp ).		B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	G (mm)			K (mm)	L (mm)	M (in)	N (mm)	P
P1! P1!		197	521	123,8	175	578	98,4	76,2	502	39°	7,9	95,3	³/ <sub>8</sub> -NPTF	57,2	_
P30	00	210	533	114,3	175	575	215,9	190,5	526	39°	7,9	95,3	³/8-NPTF	57,2	_
P40	60	283	787	171,5	289	610	743	279,4	229	80°	241,3	_	³/s-NPTF	— <sup>1</sup> /	4 NPTF



No. FK59 - Foot pump conversion kit for use on P55/P59 pumps. Wt., 2,7 kg

**No. FK159B** - Foot pump conversion kit for use on P157/P159 and P300/P300D pumps. Wt., 2,7kg.

For Use	Order			& Pressure ne per (cm³)		imum re (bar)	Reservoir Handle Effort	Oil Capacity	Usable Oil Capacity	Oil Port	Product Weight
With	No.	Speed	LP	HP	LP	HP	(kg)	(cm³)	(cm³)	(in)	(kg)
* Single-	P157	2	10,7	2,6	97	700	64	2491	2245	3/8-NPTF	11,8
Acting	P159	2	42,6	2,6	22	700	64	2491	2245	³/s-NPTF	11,8
Cylinders	P300	2	42,6	2,6	22	700	64	5700	5081	3/8-NPTF	25,1
-	P460	2	120,5	4,8	22	700	41	9500	7539	3/8-NPTF	24,9
** Double-	P157D	2	10,7	2,6	97	700	64	2491	2245	³/s-NPTF	13,1
Acting	P159D	2	42,6	2,6	22	700	64	2491	2245	3/8-NPTF	12,7
Cylinders	P300D	2	42,6	2,6	22	700	64	5700	5081	³/s-NPTF	25,9
- -	P460D	2	120,5	4,8	22	700	41	9500	7539	³/8-NPTF	26,3

LP = Low Pressure HP = High Pressure

- Pump includes 2-Way Valve
- \*\* Pump includes 4-Way Valve

Hydraulic **PA6** Series 98 cm<sup>3</sup>/min. Single-Acting 700 bar (10,000 psi)


#### COMPACT, LIGHTWEIGHT AND PORTABLE. SINGLE-SPEED PUMPS DESIGNED TO DRIVE SINGLE-ACTING CYLINDERS.


- The power unit of choice for major manufacturers of auto body, frame straighteners and other equipment.
- Operate at 3-8 bar shop air pressure, 570 l/min at 7 bar (20 cfm at 100psi).
- Internal relief valve protects circuit components, air inlet filter protects motor.
- Serviceable pump motor is not a "throw away", providing economical repair.
- Permanently vented reservoir cap.
- dBA 85 at 700 bar.














Pump No.	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	G (mm)
PA6	197	149	111	241	127	102 x 229
PA6A	197	149	111	241	127	102 x 229
PA6AM	197	149	111	241	127	102 x 229
PA6M	197	149	111	241	127	102 x 229
PA6R	197	149	111	241	127	102 x 229
PA6RM	197	149	111	241	127	102 x 229
PA6M-1	200	152	111	321	187	_
PA6AM-2	254	197	171	292	241	203 x 254
PA6-2	260	203	178	292	241	130 x 181

		Air Supply	Res	ervoir	Oil	Prod.
Description	Order No.	Req'd (bar)	Cap. (I)	Usable (I)	Port (in)	Wt. (kg)
Base model pump with high density polyethylene reservoir.	PA6	3-8	1,7	1,6	³/s-NPTF	6,3
PA6 with externally adjustable relief valve.	PA6A	3-8	1,7	1,6	3/8-NPTF	6,8
PA6A with metal reservoir.	PA6AM	3-8	1,7	1,6	3/8-NPTF	7,7
PA6, except has metal reservoir.	PA6M	3-8	1,7	1,6	³/s-NPTF	8,2
PA6 with 3,7m remote control.	PA6R	3-8	1,7	1,6	3/8-NPTF	9,3
PA6R, except has metal reservoir.	PA6RM	3-8	1,7	1,6	³/s-NPTF	9,8
PA6, except has 3,8 I metal reservoir.	PA6M-1	3-8	3,8	3,0	³/s-NPTF	10,7
PA6, except has 7,6 l, high density polyethylene reservoir.	PA6-2	3-8	7,6	7,3	³/s-NPTF	11,1
PA6, except has 9,5 I metal reservoir.	PA6M-2	3-8	9,5	9,1	³/s-NPTF	14,5





- Operate at 3 8 bar shop air pressure, 570 l/min at 7 bar (20 cfm at 100psi).
- Internal relief valve protects circuit components, air inlet filter protects motor.
- Serviceable pump motor is not a "throw away", providing economical repair.
- Permanently vented reservoir cap.
- dBA 85 at 700 bar for all PA6 pumps.


Hydraulic **PA6D** Series 98 cm<sup>3</sup>/min. Double-Acting 700 bar (10,000 psi)



PA6D









Pump No.	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	G (mm)
PA6D	264	149	111	241	127	102 x 229
PA6DM	264	149	111	241	127	102 x 229
PA6DM-1	279	146	111	321	187	_
PA6D2	324	203	178	287	235	130 x 181
PA6DM-2	318	197	171	292	241	203 x 254


			Air Supply	Res	ervoir		Prod.
Description	Order No.	Valve No.	Req'd (bar)	Cap. (I)	Usable (I)	Oil Port (in)	Wt (kg)
Base model pump with high density polyethylene reservoir.	PA6D	9504, 3-way/ 4-way	3-8	1,7	1,6	³/ <sub>8</sub> -NPTF	8,3
PA6D, except has metal reservoir.	PA6DM	9504, 3-way/ 4-way	3 – 8	1,7	1,6	³/ <sub>8</sub> -NPTF	9,2
PA6D, except has 3,8 I metal reservoir.	PA6DM-1	9504, 3-way/ 4-way	3 – 8	3,8	3,0	³/ <sub>8</sub> -NPTF	12,7
PA6D, except has 7,6 I, high density polyethylene reservoir.	PA6D2	9504, 3-way/ 4-way	3-8	7,6	7,3	³/s-NPTF	13,0
PA6D, except has 9,5 I metal reservoir.	PA6DM-2	9504, 3-way/ 4-way	3 – 8	9,5	9,1	³/8-NPTF	16,4

Hydraulic **PA60** Series 98 cm<sup>3</sup>/min Two-Speed 700 bar (10,000 psi) TWO-SPEED PUMP FOR RAPID OIL DELIVERY AT LOW PRESSURE QUICKLY ADVANCES CYLINDER OR TOOL.


- Equipped with air pressure regulator, air filter and lubricator.
- Serviceable air motor for economical repair.
- Internal relief valve protects circuit components.
- Permanently vented reservoir cap.














								Max. Pressure		0i	l Del. * (l/m	in)	
Pump No.	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	G (mm)	Output bar	0 bar	7 bar	70 bar	350 bar	700 bar
PA60	_	240	206	362	244	181	130	700	6,24	5,6	0,8	0,19	0,1
PA64	362	_	206	362	244	181	130	700	6,24	5,6	0,8	0,19	0,1

 $<sup>\</sup>ensuremath{^{*}}$  Typical delivery. Actual flow will vary with field conditions.


Description	Order No.	Valve No.	Valve Function	Air Supply Req'd bar	Res Cap. (I)	ervoir Usable (I))	Oil Port (in)	Prod. Wt (kg)	
For use with remote valves.	PA60	Manifold	_	3 - 8	7,6	6,8	³/⊱NPTF	24,5	
For use with single- or double-acting cylinders.	PA64	9507, 3-way/ 4-way	Advance Hold Return	3 –8	7,6	6,8	³/&NPTF	24,5	


Notes: Air inlet port 1/4" NPTF. Requires 570 I/min at 7 bar (20 cfm at 100psi) shop air pressure at the pump.




- Easier to operate than a hand pump,
- Easy and economical to service; not a
- Unique bladder design for all-position operation and storage.
- Hard-coat anodized aluminum housing.
- Oil filler with integral safety relief bladder if overfilling occurs.
- dBA 80 at 700 bar for all PA9 pumps.

# **IDEAL FOR POWERING**







- minimizes chance of damage to reservoir



AIR PUMP

Hydraulic PA9 Series

148 cm<sup>3</sup>/min.

Single-Acting

700 bar (10,000 psi)





РА9Н **Hand Control** 


**Foot Control** 



700 bar







		Air Supply	Rese	rvoir	Oil	Max. Pressure	Prod.
For Use with Cyl. Type	Order No.	Req'd (bar)	Cap. (cm³)	Usable (cm³)	Port (in)	Output (bar)	Wt. (kg)
Single-Acting	PA9	3 – 8	574	549	³/s-NPTF	700	6,8
Single-Acting	РА9Н	3-8	574	549	³/s-NPTF	700	6,8

Hydraulic **PA17** Series 279 cm<sup>3</sup>/min. Two-Speed 700 bar (10,000 psi)

8,4

6,44,8

3,2


1,6


0,8


Oil Volume (liters/min.)

# ROTARY-STYLE AIR MOTOR. USE WHERE AIR IS PREFERRED SOURCE OF ENERGY, WHERE ELECTRICITY IS UNAVAILABLE OR SPARKS ARE A CONCERN.


- Two-speed operation for high speed cylinder advance.
- Durable 7.6 liter (two gallon) thermoplastic reservoir. (Metal reservoir conversion kits are available.)
- Features air motor capable of starting under full load.











								Max. Pressure		Oil				
Pump No.	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	H (mm)	Output bar	0 bar	7 bar	70 bar	350 bar	700 bar	
PA172	359	289	235	178	181	130	³/ <sub>8</sub> -NPTF	700	4,6	3,8	0,4	0,4	0,3	
PA174	359	289	235	178	181	130	³/s-NPTF	700	4,6	3,8	0,4	0,4	0,3	

<sup>\*</sup> Typical delivery. Actual flow will vary with field conditions.

PA554
--- PA172, PA174
---- PA464R,
PA464RA

280 350 420 480 580 630 700

Hyd. Pressure (bar)

					Air Supply	Res	Prod.	
For use with Cyl. Type	Description	Order No.	Valve No.	Valve Function	Req'd bar	Cap. (I)	Usable (I)	Wt (kg)
Single-Acting	Base model pump with 7.6 liter 2 gallon thermoplastic reservoir.	PA172	9517, 2-way	Advance/Return*	3-8	7,6	4,7	18,1
Single- and Double Acting	PA172, except has 9500 valve for use with single- or double-acting cylinders.	PA174	9500, 4-way	Advance Hold Return*	3-8	7,6	4,7	18,6

**Note:** Requires 570 I/min at 6 bar (20 cfm at 80psi) shop air pressure at the pump. dBA 85/90 at 700 bar.





<sup>\*</sup> Holds pressure in advance position when valve motor is shut off, in return position with motor running. Pump will build pressure when motor is shut off, oil returns to reservoir.




POWER TEAM

PA464R


#### **ROTARY-STYLE AIR MOTOR. USE WHERE AIR IS THE PRE-**FERRED SOURCE OF ENERGY.


- 2.2 kW (3 hp) motor starting under full load.
- Two-speed operation for rapid cylinder advance.
- Models available with full remote control over advance and return (except PA554).
- · Tandem center valve holds the load when pump is shut off.



#### AIR PUMP

Hydraulic PA46/55 Series 754 to 902 cm<sup>3</sup>/min. Two-Speed 700 bar (10,000 psi)







							Max. Pressure		Oil Del. * (I/min)				
Pump No.	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F H (mm) (mm)	Output bar	0 bar	7 bar	70 bar	350 bar	700 bar	
PA462	381	292	241	178	254	203 <sup>3</sup> / <sub>8</sub> NPTF	700	7,4	7,2	0,8	0,8	0.7	
PA464	381	292	241	178	254	203 <sup>3</sup> / <sub>8</sub> NPTF	700	7,4	7,2	0,8	0,8	0,7	
PA464R	381	292	241	178	254	203 <sup>3</sup> / <sub>8</sub> NPTF	700	7,4	7,2	0,8	0,8	0,7	
PA464RA	381	292	241	178	254	203 <sup>3</sup> / <sub>8</sub> NPTF	700	7,4	7,2	0,8	0.8	0,7	
PA554	483	292	241	178	254	203 <sup>3</sup> / <sub>8</sub> NPTF	700	7,4	7,2	1,3	1,1	0,9	

Typical delivery. Actual flow will vary with field conditions.

Note: Four mounting holes 1/2" - 20

For use with CyL Type	Description	Order No.	Valve No.	Valve Function	Air Supply Req'd bar	Reso Cap. (I)	ervoir Usable (I)	Prod. Wt (kg)
Single-Acting	Base model pump with 9,5 I steel reservoir.	PA462	9584, 2-way	Advance/Hold/ Return	3 – 8	9,5	9,4	27,2
Single- and Double Acting	PA462, except has 9500 valve capable of running 2 single-acting cylinders or one double-acting cylinder.	PA464	9500, 4-way	Advance/Hold/ Return*	3-8	9,5	9,4	27,6
Single- and Double Acting	PA462 with air actuated valve for full remote control over advance and return. Includes 3,7m remote control.	PA464R <sup>†</sup>	9594, 4-way	Advance/Hold/ Return	3 – 8	9,5	9,4	35,3
Single- and Double Acting	PA464R except, has automatic dump feature. 7,6 m remote control.	PA464RA**†	9594,	Advance/Hold/ 4-way	3 – 8 Return*	9,5	9,4	35,8
Single- and Double Acting	High performance pump with 9,5 I steel reservoir.	PA554	9500, 4-way	Advance/Hold/ Return*	3-8	9,5	8,4	22,2


Note: Requires 1417 I/min at 6 bar (50 cfm at 80psi) shop air pressure at the pump. dBA 85/90 at 700 bar.

- Holds when motor is shut-off and valve is in "advance" position.
- The PA464RA has an "automatic dump" feature. Pressure is not held when operator releases "advance" or "return" button. PA464R will "hold" only in the "advance" position with the motor shut off.
- Not to be used for lifting.

Hydraulic **PA50** Series 460 cm<sup>3</sup>/min. Low Pressure 220 bar (3190 psi) max.


# SINGLE-SPEED, LOW PRESSURE (220 BAR) OUTPUT PUMPS.


- Serviceable air motor for economical repair.
- Air inlet filter protects motor.
   Filter in outlet port protects against contaminated systems.
- Assorted reservoirs to suit your application's requirements.











Pump No.	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	G (mm)	Max. Pressure Output bar	0 bar	Oil Del. * 7 bar	(I/min) 70 bar	220 bar	
PA50, PS50R PA50M, PA50RM	197	149	111	241	127	_	102 x 229	220	2,05	1,76	1,41	0,45 †	
PA50R2	260	203	178	292	241	_	130 x 181	220	2,05	1,76	1,41	0,45 †	
PA50D	264	149	111	241	127	229	102	220	2,05	1,76	1,41	0,45 †	

- \* Typical delivery. Actual flow will vary with field conditions.
- † PA50 Series measured at 220 bar.

				Air Supply		ervoir	Oil	Prod.
For use with Cyl. Type	Description	Order No.	Valve No.	Req'd bar	Cap. (I)	Usable (I)	Port (in)	Wt (kg)
Single-Acting	Base model pump with high density polyethlene reservoir.	PA50	_	3 - 8	1,7	1,6	³/8-NPTF	6,4
Single-Acting	PA50, except has metal reservoir.	PA50M	_	3 – 8	1,7	1,6	³/8-NPTF	7,3
Single-Acting	PA50, except has 3.7 meter 12 foot remote control.	PA50R	_	3-8	1,7	1,6	³/8-NPTF	8,4
Single-Acting	PA50R, except has metal reservoir.	PA50RM		3 - 8	1,7	1,6	³/8-NPTF	9,3
Single-Acting	PA50R, except has 7.6 liter reservoir 2 gallon reservoir.	PA50R2	_	3 - 8	7,6	7,3	3/8-NPTF	12,9
Single- and	PA50, except designed to operate either	PA50D	9504,	3-8	1,7	1,6	³/8-NPTF	8,3
Double	single- or double-acting systems.		3-way/					
Acting	Valve function: Advance/Return.		4-way					

**Notes:** Air inlet port 1/4" NPTF. Requires 570 I/min at 7 bar (20 cfm at 100psi) shop air pressure at the pump.



#### INTENSIFIER

Hydraulic **HB44** Series
Pressure ratio 5:1
700 bar (10,000 psi)


# CONVERTS LOW-PRESSURE PORTABLE HYDRAULIC PUMPS OR ON-BOARD HYDRAULIC SYSTEMS, INTO HIGH PRESSURE POWER SOURCES.

- Applications include utilities, railroads, construction, riggers and others.
- Operates single- or double-acting cylinders, jacks, and tools such as crimpers, spreaders, cable cutters, or tire tools.
   Version for use with double-acting torque wrenches available.
- May be used to operate two separate, single-acting tools (with integral valves) independently, without need for additional manifold.
- Compact and rugged for use inside a utility vehicle aerial bucket or stowing in a vehicle.
- Control valve included. Other Power Team valves available as an option to suit your specific application, if needed; consult factory.
- No reservoir level to maintain; uses low pressure system as oil supply.
- Has 3/8" NPTF ports; compatible with standard fittings for low and high pressure systems.





700 bar



Pump No.	Output Flow at 700 bar	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	Prod. Wt. (kg)
HB44- Series	0,7 l/min.	210	368	156	70	114	267	7,2

For use with Cyl. Type	Description	Order No.	Valve Type	Valve No.	Output Flow Valve Function	Input Flow Range (I/min)	Input Flow Pressure (bar)	Output Flow Range (I/min)
Single-Acting	Hydraulic intensifier for single-acting systems	HB443	3-Way 3-Position	9520*	Advance Hold Return	0 -38	20 - 138	0 - 9,5
Single-Acting/ Double-Acting	Hydraulic intensifier for double-acting systems	HB444	4-Way 3-Position	9506*	Advance Hold Return	0 -38	20 - 138	0 - 9,5
Double-Acting	Hydraulic intensifier for HI double-acting torque wrench tools	B445-RR	4-Way 3-Position	_	Advance Hold Return	0 -38	20 - 138	0 - 9,5

<sup>†</sup> For maximum efficiency, recommended input flow is 19 I/min at a maximum pressure of 140 bar. Higher flows and/or pressures must be compensated for at the system pump (e.g., relief valve, variable flow devices, etc.).

<sup>\*</sup> Posi-Check®" valve design, "Posi-Check®" guards against pressure loss when valve is shifted from "advance" position to "hold" position.

## ELECTRIC/ BATTERY PUMP


Hydraulic **PE10** Series Up to 25 Ton Quarter Horse® Two-Speed 700 bar (10,000 psi)











#### HIGH PERFORMANCE IN COM-PACT PACKAGE, ELECTRIC AND BATTERY POWERED MODELS FOR POWERING TOOLS AND CYLINDERS UP TO 25 TON.

- Portable power source for hydraulic cylinders, and tools.
- 0.19 kW (¹/₄ hp) permanent magnet motor starts easily under load, even with reduced voltage conditions.
- Battery-operated models have 2,4 m power cord with alligator clips to connect to any 12 volt battery.
- Optional rechargeable battery pack with shoulder strap for maximum portability.

- Pump typically delivers 15 minutes of continuous operation at 700 bar on a single battery.
- Pump can be operated in any position.
- 24 volt hand and foot switches available for all AC powered models.
- High-impact housing with flameretardant construction.
- Base mounting holes for fixed installations.

For use with Cyl. Type	Description	Order No.	Valve Type	Valve No.	Valve Function	Control Switch	Motor	Reservoir Usable Cap. (I)
Single-Acting	Base model pump with 0,19 kW motor. Bladder type reservoir.	PE102-220	2-Way/ Auto. Dump	9561	Advance Return (Auto.)*	Rocker Type off, Momentary on	0,19 kW, 220/230V 50/60 Hz, Single Phase	1
Single-Acting	Base model pump with 0,19 kW motor. Bladder type reservoir with automatic dump valve	PE102A-22	O Auto. Dump	9562	Advance Return	Rocker Type off, Momentary on	0,19 kW, 220/230V 50/60 Hz, Single Phase	1
Single-Acting	PE102-220, except requires 12 volt DC.	PR102	2-Way/ Auto. Dump	9561	Advance Return (Auto.)*	Rocker Type off, Momentary on	0,19 kW, 12V†	1
Single-Acting	PE102A-220, except requires 12 volt DC.	PR102A	Auto. Dump	9562	Advance Return**	Rocker Type off, Momentary on	0,19 kW, 12V†	1
Single-Acting/ Double-Acting	Base model pump has 4-way valve for operating double-acting systems.	PE104-220	4-Way	9563	Advance Hold Return	Rocker Type off, Momentary on	0,19 kW, 220/230V 50/60 Hz, Single Phase	1
Single-Acting/ Double-Acting	PE104-220, except requires 12 volt DC.	PR104	4-Way	9563	Advance Hold Return	Rocker Type off, Momentary on	0,19 kW, 12V†	1

<sup>\* &</sup>quot;Advance" position holds pressure with motor shut off. "Return" position advances cylinder with motor running and returns cylinder with motor shut off.

Available with 115V, 60 Hz motor (to order, remove suffix "-220" behind pump order number).

<sup>\*\*</sup> Cylinder advances with motor running and automatically returns with motor shut off.

<sup>†</sup> Comes with an 2,4 m. alligator clip cord for 12 volt DC use.





The Quarter Horse pump has a maximum operating pressure of 700 bar, which handles a wide variety of hand held hydraulic tools.



#### **Accessories**



**BP212VQ** – Optional 12 volt battery pack. Includes sealed lead acid battery, 115V charger, 1,2 m cord, carrying case and shoulder strap. Wt., 8 kg.



**RB12V** – Battery only. **BP12INT** – Battery with cord and carrying case. Wt., 5 kg.

**RC12V** – Replacement 1,2 m battery cord only. Wt., 0,2 kg.

Max.	Pressure	dBa @ Idle and	Oil DeL (l/	min at)		Prod. Wt.
Pump No.	Output (bar)	700 (bar)	0 (bar)	700 (bar)	Overall Dimensions (mm)	with Oil (kg)
PE10 Series PR10 Series	700	68-74*	1,9	0,16 3	30 L x 197 W x 203	3 H 9,1

\* Measured at 0,9 m distance, all sides.

**NOTE:** PR10 rechargeable model is equipped with 2,4 m cord with alligator clips. Order optional battery pack (No. BP212VQ) or use with any 12 volt battery.

**NOTE:** Amp draw at 700 bar; 3 amp at 230 volt and 35 amp at 12 volt. 6 amp at 115 volt.




9560 – Pressure regulator. Adjustable from 70 to 700 bar. All mounting hardware included. Wt., 1,4 kg.



**251660** – Foot switch with 3 m cord. Single pole, double throw, 15 amp @ 125-250 VAC. Wt., 0,45 kg.


Hydraulic **PE17** Series 262 cm<sup>3</sup>/min, 0,37 kW Two-Speed 700 bar (10,000 psi)





#### FOR MAINTENANCE AND CONSTRUCTION APPLICATIONS.

- For use with single-acting or double-acting cylinders at operating pressures to 700 bar.
- For intermittent duty; starts under full load.
- Equipped with 0,37 kW (1/2 hp), 3,450 rpm, single-phase, thermal protected induction motor; 3 m remote control cord (PE172S has 7,6 m cord)
- Low amperage draw; small generators and low amperage circuits can be used as power source.
- Extremely quiet noise level (67-81 dBA).









	Max. Pressure		dBA at Idle	Amp Draw 220 V –	Oil	Del. (lit	ers./min.									Prod. Wt.
Pump No.	Output bar	rpm	and 700 bar	at 700 bar	0 bar	7 bar	350 bar	700 bar	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	G (mm)	with Oil (kg)
PE17 Series	700	2850	67/81*	5.3	4,8	3,1	0,33	0,26	470	178	289	181	378	235	130	20,4
PE17M Series	700	2850	67/81*	5.3	4,8	3,1	0,33	0,26	460	168	292	_	368	241	_	24,0

<sup>\*</sup> Measured at 0.9 m distance, all sides.

Amp Draw 115V - at 700 bar: 9.5 Amps.

For use with Cyl. Type	Description	Order No.	Valve Type	Valve No.	Valve Function	Control Switch ††	Motor	Reservoir Usable (I)
Single-Acting	Base model pump with 0,37 kW pump with 7,6 I thermoplastic reservoir.	PE172- 50-220	2-Way	9517	Advance Return (Auto†)	Remote Motor Control (3,1m) on/off	0,37 kW, 220 V* 50/60 Hz, Single Phase	4,8
Single-Acting	PE172-50-220, except has 9,5 I aluminum reservoir,	PE172M- 50-220	2-Way	9517	Advance Return (Auto†)	Remote Motor Control (3,1m) on/off	0,37 kW, 220 V* 50/60 Hz, Single Phase	6
Single-Acting	PE172-50-220, except has solenoid operated valve.	PE172S- 50-220	3-Way	9570	Advance Hold Return	Remote Motor & Valve (7,6 m)	0,37 kW, 220 V* 50/60 Hz, Single Phase	4,8
Single-Acting	PE172S-50-220, except has aluminum reservoir.	PE172SM- 50-220	3-Way	9570	Advance Hold Return	Remote Motor & Valve (7,6 m)	0,37 kW, 220 V* 50/60 Hz, Single Phase	6
Single-Acting	Best suited for crimping, punching, pressing. Not for lifting.Thermoplastic reservoir.	PE172A- 50-220 ∞	Auto./Dump Manifold	45554	Advance Return	Remote Motor Control (3,1 m) on/off	0,37 kW, 220 V* 50/60 Hz, Single Phase	4,8
Single-Acting	PE172A, except has aluminum reservoir.	PE172AM- 50-220 ∞	Auto./Dump Manifold	45554	Advance Return	Remote Motor Control (3,1 m) on/off	0,37 kW, 220 V* 50/60 Hz, Single Phase	6
Single-Acting / Double-Acting	PE172-50-220, except has 9500 double-acting valve.	PE174- 50-220	4-Way	9500	Advance Hold Return**	Remote Motor Control (3,1 m) on/off	0,37 kW, 220 V* 50/60 Hz, Single Phase	4,8
Single-Acting / Double-Acting	Same as PE174-50-220, except has aluminum reservoir.	PE174M- 50-220	4-Way	9500	Advance Hold Return**	Remote Motor Control (3,1 m) on/off	0,37 kW, 220 V* 50/60 Hz, Single Phase	6

Available with 115V., 60 Hz motor (to order , remove suffix

Not to be used for lifting.

The remote motor control switch on 220V., 50 cycle NOTE:

PE17 series pumps is 24 volt.

Usable oil is calculated with the oil fill at the recommended level of 38 mm below reservoir cover plate.



<sup>†</sup> Typical delivery. Actual flow will vary with field conditions.

<sup>&</sup>quot;50-220" behind pump order number).
"Advance" position holds pressure with motor shut off.
"Advance" position holds pressure with motor shut off. "Return" position advances cylinder with motor running and returns cylinder with motor shut off.


Control switch on PE17 series wired with line voltage.




# IDEAL FOR USE WITH SMALL HYDRAULICALLY POWERED TOOLS.

- Vanguard Jr.® pumps provide two-speed high performance in a light-weight, compact package.
- Gauge port provided on pump. Metal reservoir on all models.
- Equipped with a 0,37 kW (1/2 hp), 12,000 rpm, 220 volt, 50 Hz single phase universal motor that starts under load, even at reduced voltage.
- Low amperage draw permits use with smaller generators and low amperage circuits.
- All pumps have a 3 m remote control (PE183C has 7,6 m remote control).
- CSA rated for intermittent duty. Noise level of 85-90 dBA.







**ELECTRIC PUMP** 

Hydraulic **PE18** Series

295 cm<sup>3</sup>/min, 0,37 kW

Two-Speed Vanguard Jr.® Series

700 bar (10,000 psi)



Pump No.	Max. Pressure Output bar	rpm	dBA at Idle and 700 bar	Amp Draw 220 V at 700 bar	Oil O bar	Del. (lite 7 bar	ers./min. ( 350 bar	⊉) † 700 bar	A (mm)	B (mm)	C (mm)	D (mm)	F (mm)	G (mm)	Prod. Wt. with Oil (kg)
PE182	700	12.000	85/90**	6.5 Amp.	3,7	3,0	0,4	0,3	406	121	203	181	152	130	13,6
PE183	700	12.000	85/90**	6.5 Amp.	3,7	3,0	0,4	0,3	406	121	203	181	152	130	13,6
PE183A	700	12.000	85/90**	6.5 Amp.	3,7	3,0	0,4	0,3	406	121	203	181	152	130	13,6
PE184	700	12.000	85/90**	6.5 Amp.	3,7	3,0	0,4	0,3	406	121	203	181	152	130	13,6
PE183-2*	700	12.000	85/90**	6.5 Amp.	3,7	3,0	0,4	0,3	470	184	292	254	241	203	19,0
PE184-2*	700	12.000	85/90**	6.5 Amp.	3,7	3,0	0,4	0,3	470	184	292	254	241	203	19,0
PE183C ††	700	12.000	85/90**	6.5 Amp.	3,7	3,0	0,4	0,3	406	121	203	181	152	130	13,6
PE184C ††	700	12.000	85/90**	6.5 Amp.	3,7	3,0	0,4	0,3	406	121	203	181	152	130	13,6

- 9,5 I reservoir.
- \*\* Measured at 0,9 m distance, all sides. Amp Draw 115V at 700 bar: 10.2 Amps.


- † Typical delivery. Actual flow will vary with field conditions.
- †† Special application pumps for cutting, crimping or pressing.

For use with Cyl. Type	Description	Order No.	Valve Type	Valve Function	Control Switch	Motor	Reservoir Usable (I)
Single-Acting	Base model pump has 0,37 kW pump with 2-Way valve and 1,9 I reservoir.	PE182- 50-220	2-Way	Advance Return†	Remote Motor Control (3,1 m) on/off	0,37 kW, 220 V** 50/60 Hz, A.C., Single Phase	1,7
Single-Acting	PE182-50-220, except has 3-way valve.	PE183- 50-220	3-Way	Advance Hold Return	Remote Motor Control (3,1 m) on/off	0,37 kW, 220 V** 50/60 Hz, A.C., Single Phase	1,7
Single-Acting	PE183-50-220, except has 9,5 I reservoir.	PE183-2- 50-220	3-Way	Advance Hold Return	Remote Control (3,1 m)	0,37 kW, 220 V** 50/60 Hz, A.C., Single Phase	8,4††
Single-Acting	PE183-50-220, except has "dump valve"	PE183A- 50-220∞	Auto./Dump Pump	Advance Return	Remote (3,1 m)	0,37 kW, 220 V** 50/60 Hz, A.C., Single Phase	1,7
Single-Acting	Special crimping pump.	PE183C- 50-220∞	Special, for crimping only	Advance Hold Return	Remote Motor Control (7,6 m) on/off	0,37 kW, 220 V** 50/60 Hz, A.C., Single Phase	1,7
Single-Acting / Double-Acting	Base model pump has 0,37 kW pump for double-acting systems with 1,9 I reservoir.	PE184- 50-220	4-Way	Advance Hold Return†	Remote Motor Control (3,1 m) on/off	0,37 kW, 220 V** 50/60 Hz, A.C., Single Phase	1,7
Single-Acting / Double-Acting	PE184, except with 9,5 I reservoir.	PE184-2- 50-220	4-Way	Advance Hold Return†	Remote Motor Control (3,1 m) on/off	0,37 kW, 220 V** 50/60 Hz, A.C., Single Phase	8,4††
Single-Acting / Double-Acting	Special crimping pump.	PE184C- 50-220*	4-Way	Advance Return	Remote Control (3,1 m) on/off	0,37 kW, 220 V** 50/60 Hz, A.C., Single Phase	1,7

- \* Also for use with special single-acting cylinder applications.
- \*\* Available with 115 Volt, 60 Hz motor (to order, remove suffix "50-220" behind pump order number). Specify voltage when ordering. Universal motor run on 220V/50Hz or 60Hz/Single phase.
- † Holds when motor is shut off and valve is in "advance" position.
- †† Pumps supplied with 7,6 l oil (usable oil is 5,7 l), will hold 9,5 l when filled to within 13 mm below reservoir cover plate.
- $\infty$  Not to be used for lifting.


Hydraulic **PE21** Series 361 cm<sup>3</sup>/min, 0.75 kW Two-Speed 700 bar (10,000 psi)





#### TWO-SPEED, HIGH-TORQUE FOR HEAVY-DUTY, EXTENDED-CYCLE OPERATIONS.

- Totally enclosed, fan cooled induction motor: 0,75 kW (1 hp), 1,725 rpm, 50 Hz, single phase. Thermal overload protection.
- Remote control, with 3,1 m cord is standard on pumps with solenoid valves.
   Manual valve pumps have "Stop", "Start" and "Run/Off/Pulse" switches.
   Pump controls are moisture and dust resistant.
- Motor drip cover with carrying handles and lifting lug.
- Low noise level of 70 dBA@ 700 bar.
- In the event of electrical interruption, pump shuts off and will not start up until operator presses the pump start button.
- Units with remote have a 24 volt control circuit that provides additional user/ operator safety.







Pump No.	Max. Pressure Output bar	rpm	dBA at Idle and 700 bar	7 bar	Dil Del. (I/min. a 70 bar	nt.) 350 bar	700 bar	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	G (mm)	H (mm)	J (mm)	K*** (in)	Prod. Wt. w/Oil (kg)
PE21 Series	700	1.437	70*	4,4	0,5	0,4	0,36	543	292	241	165	254	203	359	241	82,6	¹/2-20 UNF	44,4†

- Measured at a 0,9 m distance, all sides.
- \*\*\* For 50,8 mm dia. swivel casters, order (4) No. 10494.
- † Shipping weight with manual valve; add 6,4 kg for pump with solenoid valve.

For use with Cyl. Type	Description	Order No.	Valve Type	Valve No.	Valve Function	Max. Amp Draw at 700 bar	Motor	Reservoir Usable (I)
Single-Acting	0,75 KW pump with 9,5 I Reservoir and manual valve.	PE213- 50-220	3-Way	9520*	Advance Hold Return	230 V - 9.5 amps	0,75 kW, 220 Volt 50 Hz, Single Phase	9.7
Single-Acting	PE213, except has solenoid operated remote valve.	PE213S- 50-220	3-Way	9599†	Advance Hold Return	230 V - 9.5 amps	0,75 kW, 220 Volt 50 Hz, Single Phase	9.7
††Single-Acting/ Double-Acting	0,75 KW pump with 9,5 I Reservoir and manual valve.	PE214- 50-220	4-Way	9506*	Advance Hold Return	230 V - 9.5 amps	0,75 kW, 220 Volt 50 Hz, Single Phase	9.7
Double-Acting	PE214, except has solenoid operated remote valve.	PE214S- 50-220	4-Way	9512 <sup>†</sup>	Advance Hold Return	230 V - 9.5 amps	0,75 kW, 220 Volt 50 Hz, Single Phase	9.7

- \* Manual valve. Pump is equipped with RUN/OFF/PULSE switch for control of motor.
- $\dagger$  24V Solenoid valve. Pump is equipped with a remote control switch with 3,1 m cord.
- ††For single-acting operation, off the electric motor when manual valve in "Retract" position.

Available with 115 volt, 60Hz motor (to order, remove suffix "50-220" behind pump order number) For 230V, 60Hz motor (change suffix to "-230") Amp Draw 115V at 700 bar: 19 Amps.

#### **IDEAL FOR RUNNING MULTIPLE TOOLS OR CYLINDERS** FROM ONE POWER UNIT.

- Two-speed pumps have the same low pressure and high pressure flows from both valves.
- Flows and pressures of each pump are independent.
- Delivers 4.9 I/min. of oil @ 7 bar and 0.41 I/min. @ 700 bar from each pump.
- 1.12 kW (1<sup>1</sup>/<sub>2</sub> hp), 220 volt, 50 Hz induction motor, 3m remote control and 19 I steel reservoir.
- Models available for operating single-acting or double-acting cylinders.
- Each power unit contains two separate pumps and two separate valves allowing operator to control multiple processes with one power unit.
- Both pumps on each power unit are equipped with an externally adjustable pressure relief valve.
- · Not recommended for frequent starting and stopping.

#### **ELECTRIC HYDRAULIC DUAL PUMP**

- ✓ One Electric Motor
- ✓ Two Separate Pumps
- ✓ Two Separate Valves deliver same low pressure and high pressure flows from both valves





**ELECTRIC** 


**DUAL PUMP** 


Hydraulic **PED** Series


0.41 l/min., 1.12 kW


Two-Speed

700 bar (10,000 psi)









								Prod.
	B (mm)		100 m	PROPERTY.	XXXXXX			w/O (kg
527	457	292	216	419	229	457	330	77

Noise level reading (dBA) measured at a 0.9m distance, all sides.

**	Amp draw at 700 bar	, 115 Volts 60 Hz is 22 Amps.
----	---------------------	-------------------------------

For use with Cyl. Type	Description	Order No.	Valve Type	Valve No.	Valve Function	Control Switch	Motor	Reservoir Usable (I)
Single-Acting	1.12kW hp pump with 19 I reservoir. Valve has "Posi-Check®" feature.	PED253- 50-220	3-Way	9520	Advance Hold Return	Remote Motor	1.12kW hp, 220 VAC 50 Hz, Single Phase	16.4
Double-Acting	1.12kW hp pump with 19 I reservoir. Valve has "Posi-Check" feature.	PED254- 50-220	4-Way	9506	Advance Hold Return	Remote Motor	1.12kW hp, 220 VAC 50 Hz, Single Phase	16.4
Double-Acting	PED254, except has solenoid operated remote valve.	PED254S- 220	4-Way	9513	Advance Hold Return	Remote Valve	1.12kW hp, 220 VAC 50/60 Hz, Single Phase	16.4

All remotes are 3m long.

Series

Pumps available with 115 VAC, 60 Hz Motors


(to order, remove the -50-220 suffix from pump order number)

Hydraulic **PE30** Series 480 cm<sup>3</sup>/min, 0,75 kW Two-Speed Vanguard<sup>®</sup> Series 700 bar (10,000 psi)

# Ideas for maintenance and construction applications

- Deliver a powerful punch to operate singleacting or double-acting cylinders.
- Integral roll cage protects pump from abuse.
- 0,75 kW (1 hp), single phase, permanent magnet motor.
- High performance to weight ratio.
- Starts under full load even when voltage is reduced to 50% of nominal rating.
- Quiet operation: 87 dBA @ 700 bar and 82 dBA @ 0 bar. CSA rated for intermittent duty.

















	Max Pressure	Noise level	Amp.Draw 220V at	O		/min at				Prod. Wt.
Pump No.	Output bar	at 700 bar (dBA)	700 bar (A)	7 bar	35 bar	70 bar	350 bar	700 bar	Overall Dimensions (mm)	With Oil (kg)
PE30 Series with 4,7 I re		87/82	7	4,8	3,2	0,7	0,6	0,5	254L x 229W x 406H	18,6
PE30 Series with 7,6 I re		87/82	7	4,8	3,2	0,7	0,6	0,5	343L x 241W x 419H	22,2

For use with Cyltype	Description	Order No.	Valve Type	Valve No.	Valve Function	Control Switch	Motor <sup>†</sup> (4.000 rpm)	Usable (I)
Single-act.	Base model 0,75 kW pump with 4,7 I Reservoir & 2 position valve.	PE302- 220	3-Way, 2 Pos	9584	Hold Advance Return	On/Off/ Pulse Switch	0,75 kW 220/230 VAC, 50 Hz, Single Phase	4,5**
Single-act.	PE302-220, except has 6,6 I reservoir.	PE302-2- 220	3-Way, 2 Pos.	9584	Hold Advance Return	On/Off/ Pulse Switch	0,75 kW 220/230 VAC, 50 Hz, Single Phase	6,1***
Single-act.	PE302-220, except has remote motor control.	PE302R- 220	3-Way, 2 Pos.	9584	Hold Advance Return	Remote Motor Control (3,1 m)	0,75 kW 220/230 VAC, 50 Hz, Single Phase	4,5**
Single-act.	PE302R-220, except has 6,6 I reservoir.	PE302R-2- 220	3-Way, 2 Pos.	9584	Hold Advance Return	Remote Motor Control (3,1 m)	0,75 kW 220/230 VAC, 50 Hz, Single Phase	6,1***
Single-act.	PE302R-220, except also has solenoid operated remote valve.	PE302S- 220	3-Way, 2 Pos.	9570	Hold Advance Return	Remote Motor & Valve (3,1 m)	0,75 kW 220/230 VAC, 50 Hz, Single Phase	4,5**
Single-act.	PE302S-220, except has 6,6 I reservoir.	PE302S-2- 220	3-Way, 2 Pos.	9570	Hold Advance Return	Remote Motor & Valve (3,1 m)	0,75 kW 220/230 VAC, 50 Hz, Single Phase	6,1***
Single-act.	PE302-220, except has "Auto Dump" valve	PE302A- 220∞	Auto Dump	9610	Automatic Pilot Operation	Remote Motor Control (3,1 m)	0,75 kW 220/230 VAC, 50 Hz, Single Phase	4,5**
Single-act.	Base model 0,75 kW pump with 4,7 I Reservoir & 3 position valve.	PE303- 220	3-Way, 3 Pos.	9520*	Advance Hold Return	On/Off/ Pulse Switch	0,75 kW 220/230 VAC, 50 Hz, Single Phase	4,5**
Single-act.	PE303-220, except has 6,6 I reservoir.	PE303-2- 220	3-Way, 3 Pos.	9520*	Advance Hold Return	On/Off/ Pulse Switch	0,75 kW 220/230 VAC, 50 Hz, Single Phase	6,1***
Single-act.	PE303-220, except has remote motor control.	PE303R- 220	3-Way, 3 Pos.	9520*	Advance Hold Return	Remote Motor Control (3,1 m)	0,75 kW 220/230 VAC, 50 Hz, Single Phase	4,5**
Single-act.	PE303R, except has 6,6 I reservoir.	PE303R-2- 220	3-Way, 3 Pos.	9520*	Advance Hold Return	Remote Motor Control (3,1 m)	0,75 kW 220/230 VAC, 50 Hz, Single Phase	6,1***
Double-act.	Base model 0,75 kW pump with 4,7 I Reservoir & 4-way valve for double-acting systems	PE304- 220	4-Way, 3 Pos. Tandem Ctr.	9506*	Advance Hold Return	On/Off/ Pulse Switch	0,75 kW 220/230 VAC, 50 Hz, Single Phase	4,5**
Double-act.	PE304-220, except has 6,6 I reservoir.	PE304-2- 220	4-Way, 3 Pos. Tandem Ctr.	9506*	Advance Hold Return	On/Off/ Pulse Switch	0,75 kW 220/230 VAC, 50 Hz, Single Phase	6,1***
Double-act.	PE304-220, except has remote motor control.	PE304R- 220	4-Way, 3 Pos. Tandem Ctr.	9506*	Advance Hold Return	Remote Motor Control (3,1 m)	0,75 kW 220/230 VAC, 50 Hz, Single Phase	4,5**
Double-act.	PE304R-220, except has 6,6 I reservoir.	PE304R-2- 220	4-Way, 3 Pos. Tandem Ctr.	9506*	Advance Hold Return	Remote Motor Control (3,1 m)	0,75 kW 220/230 VAC, 50 Hz, Single Phase	6,1***

<sup>\* &</sup>quot;Posi-Check®" valve design, "Posi-Check®" guards against pressure loss when valve is shifted from "advance" to "hold" position.

- \*\* Shipped with 3,8 I of oil (3,4 I usable).
- \*\*\* Shipped with 7,6 I of oil.

- Not to be used for lifting. Best suited for crimping, pressing & punching applications.
- † Available with 115V, 60Hz motor (to order, remove suffix "-220" behind pump order number)






- Two-speed high performance pump.
- For use with single- or double-acting cylinders at operating pressures up to 700 bar.
- Equipped with a 1.12 kW (1<sup>1</sup>/<sub>2</sub> hp) 3,450 rpm single-phase, 50 Hz thermal protected induction motor that starts under full load. Noise level of 77-81 dBA.
- All equipped with a 3,1 m remote control except PE462S which has a 7,6 m remote control.
- **PE462S** 24 volt control circuit on all units with remote control.
  - CSA rated for intermittent duty.




Hydraulic **PE46** Series 0.75 I/min, 1,12 kW Two-Speed 700 bar (10,000 psi)



POWER TEAM







	Max. Pressure		Noise level at Idle	Amp Draw 220 V -	Oil	Del. (I/min. at										Prod. Wt.
Pump No.	Output bar	rpm	and 700 bar (dBA)	at 700 bar (A)	0 bar	7 bar	350 bar	700 bar	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	G (mm)	w/ <b>0il</b> (kg)
PE46-Serie	s 700	2.875	77/81	11.6	8,2	7,4	0,8	0,75	499	173	292	254	378	241	203	35,8

- \* Measured at 0,9 m distance, all sides.
- † Typical delivery. Actual flow will vary with field conditions.

Amp Draw 115V at 700 bar: 25 Amps.

For use with Cyl. Type	Description	Order No.	Valve Type	Valve No.	Valve Function	Control Switch†††	Motor	Reservoir Usable*** (I)
Single-Acting	Base model 1,12 kW pump with 9,5 I metal reservoir.	PE462- 50-220	3-Way	9584	Advance Return†	Remote Motor Control (3,1 m) on/off	1,12 kW, 220 VAC* 50 Hz, Single Phase	9,7
Single-Acting	PE462-50- 220, except has solenoid valve.	PE462S- 50-220	3-Way	9570	Advance Return**	Remote Motor/ Valve (7,6 m)	1,12 kW, 220 VAC* 50 Hz, Single Phase	9,7
Single-Acting	PE462-50-220, except has "dump valve"	PE462A- 50-220∞	Auto/Dump 3-Way	9610	Advance Return	Remote Motor Control (3,1 m) on/off	1,12 kW, 220 VAC* 50 Hz, Single Phase	9,7
††Single-Acting/ Double-Acting		PE464- 50-220	4-Way	9500	Advance Hold Return†	Remote Motor Control (3,1 m) on/off	1,12 kW, 220 VAC* 50 Hz, Single Phase	9,7
Double-Acting	PE462S-50-220, except has 9592 double-acting valve.	PE464S- 50-220	3/4-Way	9552	Advance Return**	Remote Motor/ Valve (3,1m)	1,12 kW, 220 VAC* 50 Hz, Single Phase	9,7

- \* Available with 1.15 V., 60 Hz motor (to order, remove suffix "50-220" behind pump order number). Specify voltage when ordering. For 230V, 60 Hz motor (to order, change suffix to "-230" behind pump order number).
- \*\* "Advance" position holds pressure with motor shut off.
- \*\*\* Usable oil is calculated with the oil fill at the recommended level of 13 mm below reservoir cover plate.
- † "Advance" position holds pressure with motor shut off. "Return" position returns cylinder.
- †† For single-acting operation, off the electric motor when manual valve in "Retract" position.
- ††† The remote motor control switch on PE46 series pumps is 24 volt.
- $\infty$  Not to be used for lifting. When pump is shut off, oil returns to reservoir.

Hydraulic **PE55** Vanguard<sup>®</sup>
0,92 I/min, 0,84 kW
Two-Speed
700 bar (10,000 psi)

12,8 11,2 9,6

> 8,0 6,4 4,8 3,2 1,6

Volume (I/min.)

. 0



# HEAVY DUTY MULTIPLE-APPLICATIONS PUMP. HEAVY CONSTRUCTION AND CONCRETE STRESSING. LOW VOLTAGE STARTING POSSIBLE.

- 0,84 kW (1 ½ hp), 12,000 rpm, 220 volt, 50 Hz universal motor; draws 15 amps at full load, starts at reduced voltage. CSA rated for intermittent duty.
- 3,1 m remote motor control (except PE552S which has a 7,6 m remote motor and valve control).
- True unloading valve achieves greater pump efficiency, allowing higher flows at maximum pressure.
- Reservoirs available in sizes up to 38 liters. Consult factory.
- Light weight and portable. Best weight to performance ratio of all Power Team pumps.
- "Assemble to Order" System: There are times when a custom pump is required.
  Power Team's "Assemble to Order" system allows you to choose from a wide
  range of pre-engineered, off-the-shelf components to build a customized pump
  to fit specific requirements. By selecting standard components you get
  a "customized" pump without "customized" prices. All pumps come fully
  assembled, less oil and ready for work.








PE554W Weather-resistant pump

PE55TWP Torque Wrench Applications



140 210 280 350 420

Pressure (bar)



700 bar

PE554 Heavy duty pump

Pump	Max. Pressure Output		Noise level Idle and at 700 bar	Amp Draw at 700 bar (220 V.)	0	DeL (I/min 50	350	700	A	В	C	D	E	F	G	Prod. Wt. w/Oil
No.	bar	rpm	(dBA)	(A)	bar	bar	bar	bar	(mm)	(kg)						
PE55-Series	700	12,000	90/89*	15	11,5	7,2	1,2	0,92	464	292	241	178	254	203	356	29,4

<sup>\*</sup>Noise level reading (dBA) measured at a 0,9 m distance, all sides.

Amp draw at 700 bar, 115 volts 60 Hz is 25 Amps.

Hydraulic **PE55** Vanguard<sup>®</sup>
0,92 l/min, 0,84 kW
Two-Speed
700 bar (10,000 psi)











For use with Cyl. Type	Description	Order No.***	Reservoir Valve Type	Valve No.	Valve Function	Control Switch ††	Motor	Usable (I)
Single-Acting	Base model 0,84 kW pump with 9,5 I reservoir, remote motor control & 3-way valve,	PE552- 50-220	3-Way	9582	Advance Return**	Remote Motor	0,84 kW*, 220 VAC 50Hz, Single Phase	8,6
Single-Acting	PE552-50-220, except also has solenoid operated remote valve.	PE552S- 50-220	3-Way	9570	Advance Hold Return	Remote Motor & Valve	0,84 kW*, 220 VAC 50Hz, Single Phase	8,6
Single-Acting	PE552-50-220, except has "Auto Dump" valve.	PE552A- 50-220 ∞	Auto/Dump	9610	Advance Return	Remote Motor	0,84 kW*, 220 VAC 50Hz, Single Phase	8,6
Single-Acting	0,84 kW pump with 9,5 I reservoir. Valve has "Posi-check" feature.	PE553- 50-220	3-Way†	9520	Advance Hold Return	Remote Motor	0,84 kW*, 220 VAC 50Hz, Single Phase	8,6
Single-Acting/ Double-Acting	Base model 0,84 kW pump with 9,5 l res, and 4-way valve for double-acting systems.	PE554- 50-220	4-Way†	9506	Advance Hold Return	Remote Motor	0,84 kW*, 220 VAC 50Hz, Single Phase	8,6
G G	PE554-50-220, except has 9500 tandem center valve.	PE554T- 50-22.0	4-Way	9500	Advance Hold Return	Remote Motor	0,84 kW*, 220 VAC 50Hz, Single Phase	8,6
-	For use with single-acting Spring Seat, Stressing Jack or double-acting cylinder.	PE554P- 50-220	4-Way	9500	Advance Hold Return	Remote Motor	0,84 kW*, 220 VAC 50Hz, Single Phase	8,6
Double-Acting	For use with single- or double-acting Power Seat, Stressing Jacks ONLY,	PE554PT- 50-220	4-Way	9628	Advance Hold Sequenced Return	Remote Motor	0,84 kW*, 220 VAC 50Hz, Single Phase	8,6
Double-Acting	Pump suitable to run multiple . spring return tools	PE554C- 50-220	4-Way	9511†††	Advance Hold Return	Remote Motor	0,84 kW*, 220 VAC 50Hz, Single Phase	8,6
Double-Acting	Pump equipped with 3/4-way solenoid valve.	PE554S- 50-220	3/4-Way	9552	Advance Hold Return	Remote Motor & Valve	0,84 kW*, 220 VAC 50Hz, Single Phase	8,6
Single-Acting/ Double-Acting	Same as PE554-50-220, except with weather protection enclosure	PE554W- 50-220	4-Way†	9506	Advance Hold Return	Remote Motor	0,84 kW*, 220 VAC 50Hz, Single Phase	8,6

- \* Pumps available with 115 volt, 60 Hz motors. (to order remove the -50-220 suffix from the order code).
- \*\* Holds with motor shut off.
- \*\*\* To order PE55 series pumps with CSA approval, add "\_C" to the Order No.
- † Valves have "Posi-Check®" feature. Universal motor run on 220V/50Hz or 60Hz/Single phase.
- †† Control switch wired with line voltage. All remotes are 3,1m long except for PE552S which is 7,6m long.
- ††† Valving allows alternate and independent operation of two different spring return tools. Valve holds pressure only while valve is in "A" or "B" port position with pump motor shut off.
- $\infty$  Not to be used for lifting.


Hydraulic **PQ60** Series 0,98 l/min, 1,49 kW Two-Speed 700 bar (10,000 psi)


# PUMP DESIGNED SPECIFICALLY FOR HEAVY DUTY, EXTENDED CYCLE OPERATION.

- For operating single- or double-acting cylinders.
- Metal shroud keeps dirt and moisture out of motor and electrical components.
- Electrical shut-down feature prevents unintentional restarting of motor following an electrical service interruption.
- Internal relief valve limits pressure to 700 bar. External relief valve is adjustable from 70 to 700 bar.
- Pumps operate below maximum OSHA noise limitation (74-76 dBA).
- Start and operate under full load, even with voltage reduced 10%.
- Equipped with a 1.49 kW (2 hp), 1,725rpm, single-phase, 50Hz induction motor.











Pump No.	Max. Pressure Output bar	rom	Noise level at Idle and 700 bar (dBA)	Amp Draw at 700 bar (A)	7 bar	Oi <b>l</b> D 70 bar	el. (L/min 350 bar	at) 700 bar	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	G (mm)	H (mm)	J (mm)	K''' (in)	Prod. Wt. w/Oil (kg)
NO.	vai	ı pılı	(uDA)	( <b>n</b> )	vai	vai	vai	vai	(11111)	(11111)	(11111)	(11111)	(11111)	(11111)	(11111)	(11111)	(11111)	(111)	(ng/
PQ60 Series	700	1.437	74/76*	See below	12,0	1,1	1,1	0,98	638	362	394	184	308	338	373	237	122,2	<sup>1</sup> / <sub>2</sub> –20 UNF	76,6**

Amp draw 220V at 700 bar: 11 Amps.

Amp draw 115V at 700 bar: 22 Amps.

- Measured at a 0,9 m distance, all sides.
- \*\* Total weight with oil and 3-way solenoid valve. Subtract 4,5 kg to obtain weight of pump with manual valve.

\*\*\* For 50,8 mm dia. swivel casters, order (4) No. 10494.

For use with CyL Type	Description	Order No.	Valve Type	Valve No.	Valve Function	Max. Amp Draw at 700 bar (A)	Motor	Reservoir Usable (I)
Single-Acting	1,49 kW pump with 21,6 I reservoir and manual valve,	PQ603- 50-220	3-Way	9520*	Advance Hold Return	230V - 11 amps	1,49 kW, 220 Volt 50 Hz, Single phase	20
Single-Acting	PQ603-50-220, except has solenoid operated remote valve.	PQ603S- 50-220	3-Way	9599†	Advance Hold Return	230V - 11 amps	1,49 kW, 220 Volt 50 Hz, Single phase	20
††Single-Acting Double-Acting	1,49 kW pump with 21,6 l reservoir and manual valve.	PQ604- 50-220	4-Way	9506*	Advance Hold Return	230V - 11 amps	1,49 kW, 220 Volt 50 Hz, Single phase	20
Double-Acting-	PQ604-50-220, except has solenoid operated remote valve.	PQ604S- 50-220	4-Way	9512†	Advance Hold Return	230V - 11 amps	1,49 kW, 220 Volt 50 Hz, Single phase	20

Manual valve. Pump is equipped with RUN/OFF/PULSE switch for control of motor.

Available with 230 Volt, 60Hz motor (to order, remove suffix "-50-220" behind pump order number)

Available with 1.15 Volt, 60Hz motor (to order, remove suffix "-50-220" & add "-115" behind pump order number)

<sup>24</sup>V Solenoid valve. Pump is equipped with a remote control switch with 3,1 m cord.

<sup>††</sup> For single-acting operation, off the electric motor when manual valve in "Retract" position.






#### TWO-SPEED, HIGH TORQUE PUMP DESIGNED SPECIFICALLY FOR HEAVY DUTY, EXTENDED CYCLE OPERATION. IDEAL FOR PRESS OPERATION.


- Start and operate under full load, even with voltage reduced 10%.
- Electrical shut-down feature prevents unintentional restarting of motor following an electrical service interruption.
- Internal relief valve limits pressure to 700 bar. External relief valve is adjustable from 70 to 700 bar.
- Pump prewired at factory with a 2,24 kW (3 hp), 1,725rpm, 380 volt, 50 Hz. 3
   Phase induction motor. Other electrical configurations are available. See ordering information below.
- 24 volt control circuits on units with remote controls for added user/ operator safety.
- 2,24 kW (3 phase) motor with thermal overload protection. Motor starter and heater element supplied as standard equipment; no hidden charges!
- Metal shroud keeps dirt and moisture out of motor and electrical components.
- Pumps operate below maximum OSHA noise limitation.

## **ELECTRIC PUMP**

Hydraulic **PQ120** Series 2,0 I/min, 2,24 kW Two-Speed 700 bar (10,000 psi)







	Max. Pressure		Noise level at Idle	Amp Draw	Oil	De <b>L</b> (I/mi													Prod. Wt.
Pump	Output		and 700 bar	at 700 bar	7	70	350	700	A	B	C	D ()	E ()	F ()	G	H /\	J /\	(;) K	w/Oil
No.	bar	rpm	(dBA)	(A)	bar	bar	bar	bar	(mm)	(mm)	(in)	(kg)							
PQ120-	700	1.437	73/78*	See	12,0	2,6	2,1	2,0	638	362	394	184	308	338	373	237	122,2	1/2-20	74,3**
Series				below														UNF	

- Measured at a 0,9 m distance, all sides.
- \*\* Total weight with oil and 3-way solenoid valve. Subtract 4,5 kg to obtain weight of pump with manual valve.
- \*\*\* For 50,8 mm dia. swivel casters, order (4) No. 10494.

Amp draw 230V at 700 bar: 10.5 Amps. Amp draw 460V at 700 bar: 5.3 Amps.

For use with Cyl. Type	Description	Order No.	Valve Type	Valve No.	Valve Function	Motor	Reservoir Usable (I)
Single-Acting	2,24 kW pump with 21,6 l reservoir and manual valve.	PQ1203- 50-380	3-Way	9520*	Advance Hold Return	2,24 kW, 380 Volt 50 Hz, 3 Phase	20
Single-Acting	PQ1203-50-380, except has solenoid operated remote valve.	PQ1203S- 50-380	3-Way	9599†	Advance Hold Return	2,24 kW, 380 Volt 50 Hz, 3 Phase	20
†† Single-Acting/ Double-Acting	2,24 kW pump with 21,6 l reservoir and manual valve.	PQ1204- 50-380	4-Way	9506*	Advance Hold Return	2,24 kW, 380 Volt 50 Hz, 3 Phase	20
Double-Acting	PQ1204-50-380, except has solenoid operated remote valve.	PQ1204S- 50-380	4-Way	9512†	Advance Hold Return	2,24 kW, 380 Volt 50 Hz, 3 Phase	20

Manual valve. Pump is equipped with RUN/OFF/PULSE switch for control of motor.

Available with 460 Volt, 60Hz, 3 phase motors (to order, remove suffix "50-380" behind pump order number), suitable for 440V, 50Hz, 3 phase For 230 Volt, 60Hz, 3 phase motors (to order, change suffix to "-230" behind pump order number) 380V/50Hz/3 phase also suitable for 415V/50Hz/3 phase.

 $<sup>\</sup>dagger$  24V Solenoid valve. Pump is equipped with a remote control switch with 3.1 m cord.

<sup>††</sup>For single-acting operation, off the electric motor when manual valve in "Retract" position.

Hydraulic **PE400** Series 6,9 I/min, 7,46 kW Two-Speed 700 bar (10,000 psi)

# HIGH TONNAGE DOUBLE-ACTING CYLINDERS – SINGLE OR MULTIPLE CYLINDER APPLICATIONS. UP TO 1,000 TONS

- Two-speed high output pump delivers up to 20 I/min of oil.
- Low noise level of 73-80 dBA.
- Integral electrical shut-down feature prevents unintentional restarting of motor following an electrical service interruption. Over-current protection prevents damage to motor as a result of overheating.
- "Stop" and "Start" control buttons are 24 volt. PE4004 has a 4-way/3-position manual valve. The PE4004S has a 4-way/3-position solenoid valve with a 24 volt remote hand switch.
- External pressure relief valve is adjustable from 100 to 700 bar.
- Heavy duty 101,6mm dia. casters assure easy maneuvering.
- 75,7 l (64,4 l usable) reservoir has a low oil level sight gauge.
- Powered by a dual voltage 7,46 kW (10 hp), 3 phase, 1,725rpm induction motor.
- 3 phase motor has all the electrical components necessary to operate the pump. The customer has no hidden charges when making purchase.
- Deliver 20 I/min. of oil at 15 bar, 6,9 I/min. of oil at 700 bar.





Pump No.	Max. Pressure Output bar	rpm	Noise level at Idle and 700 bar (dBA)	Amp Draw at 700 bar (A)	Oil I 15 bar	Del. (I/min 90 bar	at) 350 bar	700 bar	A* (mm)	B (mm)	C (mm)	D (mm)	E Caster Mfg. (mm)	F Caster Mfg. (mm)	Prod. Wt. w/Oil (kg)
PE4004-50-380 PE4004S-50-380		1.437 1.437	73/80 73/80	See below	20 20	19,7 19,7	7,4 7,4	6,9 6,9	924 924	635 635	610 610	540 540	394 394	546 546	223 229

<sup>\*</sup> Add 127mm and 3,6 kg when casters are mounted. (Units are supplied with four 102 mm dia. swivel casters.)

Amp draw 230V at 700 bar: 34 Amps.

Amp draw 460V at 700 bar: 17 Amps.

For use with Cyl. Type	Description	Order No.	Valve Type	Valve No.	Valve Function	Motor††	Reservoir Usable (I)
†††Single-Acting/	7,46 kW pump with 75,5 I	PE4004-	4-Way	9506	Advance Hold	7,46 kW, 380 volt	64,4†
Double-Acting	reservoir and manual valve.	50-380			Return	50 Hz, 3 Phase	
Double-Acting	PE4004, except has solenoid	PE4004S-	4-Way	9512*	Advance Hold	7,46 kW, 380 volt	64,4†
	operated remote valve.	<b>50-380</b>			Return	50 Hz, 3 Phase	

<sup>\* 24</sup>V Solenoid valve with remote control.

380V/50Hz/3 phase also suitable for 415V/50Hz/3 phase.

NOTE: Valves for spring return cylinders are available upon request. Consult factory.



<sup>†</sup> Usable oil is calculated with oil fill at recommended level at 57 mm below cover plate.

<sup>††</sup> PE400 series also available in 230V, 60Hz and 460V, 60Hz. Please specify when ordering. Example: 460V, 60Hz order PE4004 (also suitable for 440V, 50Hz, 3 phase) or for 230V, 60Hz order PE4004-230.

<sup>†††</sup>For single-acting operation, off the electric motor when manual valve in "Retract" position.



#### PG303

# PG554

700 bar

PG553 and PG554

# GASOLINE POWER SUPPLY IDEAL FOR REMOTE LOCATIONS.


- A logical choice at work sites where electricity or compressed air are unavailable.
   For single-acting or double-acting cylinders at operating pressures up to 700 bar.
- All gasoline engine/hydraulic pumps feature "Posi-Check®" valve to guard against pressure loss when valve is shifted from "advance" to "hold".


#### **PG303 and PG304**

- Powered by a 4-cycle, 1.49 kW (2 hp) HONDA engine giving it the lowest weight to horsepower ratio of all gasoline driven pumps. Has an aluminum reservoir with 6 I of usable oil.
- PG30 series pumps are equipped with roll cages to protect pump from damage.
- PG30 series pumps weigh in at only 14,5 kg with oil.

#### PG553 and PG554

- 4.5 kW (6 hp) Intek "Diamond Edge" 4-cycle,by Briggs & Stratton 21,3 I reservoir.
- Same basic pump as PE55 series electrical Vanguard®pumps.





	Max. Pressure		0i	l Del. (I/mi	n at)								Prod. Wt.
Pump No.	Output bar	rpm	7 bar	70 bar	350 bar	700 bar	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	w/Oil (kg)
PG303, PG304	700	8,000	4,5*	0,6	0,6	0,5	378	264	241	406	130	343	14,5
PG553, PG554	700	3,600	7,9	1,2	1,1	0,9	559	457	318	219	422	229	54,4

\* First stage oil delivery from 0-28 bar at 3,7 I/min minimum.

For use with Cyl. Type	Description	Order No.	Valve Type	Valve No.	Valve Function	Reservoir Usable (I)	Horsepower (hp)	Cycle
Single-Acting	1.49 kW pump with 7,6 I reservoir and single-acting valve.	PG303	3-Way	9520	Advance Hold Return	6	2	4
Single-Acting	4.5 kW pump with 21,6 I reservoir and single-acting valve.	PG553	3-Way	9520	Advance Hold Return	21,3**	6	4
Double-Acting	PG303, except has double-acting valve.	PG304	4-Way	9506	Advance Hold Return	6	2	4
Double-Acting	PG553, except has double-acting valve.	PG554	4-Way	9506	Advance Hold Return	21,3**	6	4

 $<sup>^{**}</sup>$  Usable oil is calculated with oil fill at recommended level at 13 mm below cover plate.



Hydraulic **PG30/55** Series 0,5 to 0,9 I/min, 1,49 & 4,5 kW Two-Speed Gasoline driven 700 bar (10,000 psi)




#### **GASOLINE PUMP**


PG120 - PG400 Series
2,1 - 6,6 I/min, 4,1 - 14,9 kW
Two-Speed
Maximum Output
Gas-Powered Pumps
700 bar (10,000 psi)



- Two-speed high performance pumps ideal for construction, structure moving and rigging applications.
- A logical choice at work sites where electricity or compressed air are unavailable. For single-acting or double-acting cylinders at operating pressures up to 700 bar.
- All gasoline engine/hydraulic pumps feature "Posi-Check®" valve to guard against pressure loss when valve is shifted from "advance" to "hold".
- PG1200 Series pumps powered by a Honda 4-cycle, 4.1 kW (5.5 hp) engine with automatic decompression and electronic ignition. Deliver over 2,1 l/min at 700 bar.
- A 19 liter 5 gallon reservoir means adequate capacity for multi-cylinder applications. Dual element air cleaner protects engine from dusty environments.
- Heavy duty "roll cage" provides pick-up points for lifting. Horizontal bars on PG1203, PG1204 and PG1204S protect unit, provide hand holds for carrying.
- Rubber anti-skid insulation on bottom of reservoir resists skidding and dampens vibration. PG1200M-4 and PG1200M-4D include a pump cart with 305 mm wheels.
- Adjustable external pressure regulator.













#### PG1200M-4D

#### PG1200M-4

- For single-acting cylinders. Has 9520 3-way/3-position (tandem center) valve, 9596 load lowering valve and 9644 4-port manifold with individual needle valves at each port.
- Has a 9796 coupler and 9797 dust cap at each port.
   Valving permits precise individual control of up to four cylinders.
- A 9052 heavy duty, fluid filled pressure gauge (0-700 bar) is included.

#### PG1200M-4D

- For single- or double-acting cylinders with precise individual control of up to four cylinders possible.
- Equipped same as PG1200M-4, except has 9506
   4-way/3-position (tandem center) valve, and second
   4-port manifold without needle valves mounted
   beneath 9644 manifold for operating
   double-acting cylinders.

#### **PG400 Series Maximum output Hydraulic Power Package**

- Ideal for single or multiple cylinder applications.
   Has a 4-cycle, 14,9 kW (20 hp) Honda engine and 76 l reservoir (64,4 l usable) with low oil level sight gauge.
- Steel "roll cage" protects pump, has a lifting hook;
   102 mm dia. swivel casters provide mobility.
- Delivers 6,6 I/min of oil at maximum operating pressure.
- Has a 9506 4-way valve. On/off switch and speed control are protected by a panel. Sturdy molded case protects battery (not included).



For use with Cyl. Type	Description	Order No.	Valve Type	Valve No.	Valve Function	Reservoir Usable (I)	Horsepower (hp)	Cycle
Single-Acting	Base model 4.1 kW gasoline pump with 22 I reservoir.	PG1203	3-Way	9520	Advance Hold Return	21,3	5 <b>.</b> 5	4
Single-Acting	PG1203 with cart, rollcage, load lowering valve, 4 port manifold & gauge.	PG1200M-4	3-Way Manifold	9520 9644	Advance Hold Return**	21,3	5.5	4
Single-Acting/ Double-Acting	PG1200M-4D, except without "Roll Cage" and cart. Ideal for house moving industry.	PG120HM	4-Way Manifold	9506 9642 (2 nos.)	Advance Hold Return**	21,3	5 <b>.</b> 5	4
Double-Acting	Base model 4.1 kW gasoline pump, with 22 I reservoir and double-acting valve.	PG1204	4-Way	9506	Advance Hold Return	21,3	5 <b>.</b> 5	4
Double-Acting	PG1204, except has roll cage, cart, solenoid valve and 7,6 m cord.	PG1204S	4-Way Solenoid***	9516	Advance Hold Return	21,3	5.5	4
Single-Acting/ Double-Acting	PG1200M-4, except for double-acting systems.	PG1200M-4D	4-Way Manifold	9506 9644	Advance Hold Return**	21,3	5.5	4
Double-Acting	Base model 14,9 kW pump with 76 I reservoir.	PG4004	4-Way	9506	Advance Hold Return	64,4*	20	4
Double-Acting	PG4004, except has solenoid operated remote valve.	PG4004S	4-Way Solenoid***	9516	Advance Hold Return	64,4*	20	4

Usable oil is calculated with oil fill at recommended level at 57 mm below cover plate.

<sup>\*\*</sup> Control up to 4 cylinders independently.

<sup>\*\*\*</sup> Has 7,6 m remote control cord.

#### HYDRAULIC PUMP

Accessories



#### ON/OFF MOTOR CONTROL

The following remote control switches will give you momentary "ON" control of your hydraulic pump. These switches are deadman type, spring loaded to the "OFF" position. They can be used with any Power Team electric hydraulic pumps.

**No. 25017** - Remote hand control. Has a push button switch, with a 3.1 m cord. Wt., 0.4 kg.

**No. 203225** - Remote hand control. Heavy-duty with single push button switch in a neoprene housing with 3,1 m cord. Housing seals out dust, lint and liquids (unit is not submersible). Wt., 0,4 kg.

No. 10461 - Remote foot control, with 3,1 m cord. Wt., 1,4 kg.No. 251660 - Remote foot control, with 3,1 m cord.For use with the PE10 style pumps. Wt., 0,4 kg.

#### **SOLENOID & MOTOR CONTROL**

For use on solenoid valves that are used on single-acting cylinders: **No. 202777** • Remote hand control. Has rocker style switch that is momentary advance, spring center hold and detented retract. It comes with a 3,1 m cord, for use with 3-way/2 or 3-position valves. Wt.,0,4 kg. For use on solenoid valves that are used on double-acting cylinders:

No. 202778 - Remote hand control. Has rocker style switch that is momentary advance, spring center hold and momentary retract. It comes with a 3,1 m cord, for use with 4-way/3-position valves. Wt., 0,4 kg

**No. 309653** – Remote foot control. Can be used in place of either of the above hand controls to control the same type of valves. The switch is momentary on both the advance and retract position and is spring centered to the hold position. This foot switch comes with 3,1 m cord. Wt., 1,8 kg.

**No. 17627 –** Remote foot control. Same as the No. 309653 but without a cord. Wt., 0,9 kg.

**No. 304718** - Remote hand control. Has a rocker style switch that is momentary advance, spring center hold and momentary retract. The switch is wired to start and stop the motor when the valve is energized. It comes with a 3,1 m cord. To be used with 4-way/2-position valves. Wt., 0.4 kg.

No. 309652 – Remote foot control. Has same functions as No. 304718. Supplied with a 3,1 m cord. To be used with 4-way/2-position valves. Wt., 1,8 kg.

**No. 216209** – Remote foot control. Same as the No. 309652, but without a cord. Wt., 0,9 kg.

NOTE: See valves listing to determine which remote to use (See page 76-81, 84).

#### REMOTE AIR MOTOR CONTROLS

This remote hand control has two momentary push buttons, one for advance and one for retract with spring offset to hold. To be used with 4-way/2-position air pilot valves.

No. 209593 - Remote hand control with 3,7 m cord. Wt., 0,9 kg.

#### **SUBPLATES**

For remote mounting of control valves. They convert pump mounted valves to remote mounted valves quickly and easily.

**No. 9510 -** Subplate for remote mounting the following valves; 9500, 9501, 9502, 9504, 9506, 9507, 9511, 9552, 9572, 9575, 9576, 9592, 9594 and 9609. Wt., 1 kg 1.5 lbs.

**No. 9620 -** For use with 9500, 9501, 9502, 9552, 9572, 9592 and 9594. Same as No. 9510 but has integral pressure regulating valve. Wt., 1,7 kg.

# 9510 9515






9510 and 9620 attach to the bottom of valve for remote mounting. The 9515 and 9521 mount between the pump cover plate and valve.

#### PUMP-MOUNTED SUBPLATES

When fitted between pump cover plate valve mounting flange and control valve, provides a separate 3/8" NPTF female port, open to "return" regardless of position of valve. Also provides a separate 3/8" NPTF female pressure port. This subplate can be useful when you desire to use one pump with a deck-mounted control valve, plus a separate remote-mounted valve to control another function. For use with the following valves: 9500, 9501, 9502, 9504, 9506, 9507, 9511, 9552, 9572, 9575, 9576, 9592, 9594 and 9609.

No. 9515 - Subplate, Wt., 0,6 kg.

No. 9521 - Subplate for use under most pump mounted valves to provide adjustable pressure control on units not equipped with an external pressure regulator. Wt., 1,7 kg.






#### PRESSURE SWITCH

**Application:** Used in a hydraulic circuit where system pressure must be "held". Automatically (electrically) turns off pump motor when predetermined system pressure is reached. Attaches directly to control valve manifold or can be mounted "in-line" to read system pressure. Has a 1/4" NPTF male thread, and a 1/4" NPTF fitting for gauge mounting if required. Adjustable from 70 to 700 bar. Can also be used to actuate other electrical devices in the system. Wired "normally open" and held closed by spring pressure.

IMPORTANT: Electrical rating of switch is 5 amps at 250 volts max. To prevent permanent damage to switch, a control relay must be installed to handle currents or voltage exceeding these limits. Pressure switch should never be used to directly actuate the electrical motor.

**No. 9625 -** In-line pressure switch with 1/4" NPTF gauge port. Wt., 0,5 kg.





#### PILOT OPERATED AIR CONTROL VALVES

**Application:** For use when an air pilot signal is required at a set hydraulic pressure. Can be used to shift valves, and start or stop pneumatic pumps. Attaches directly to control manifold or can be mounted "in-line" to read system hydraulic pressure. Automatically turns on an air pilot signal when a predetermined system pressure is reached. Has 1/4" NPTF male thread and 1/4" NPTF fitting for gauge mounting if required. Adjustable from 35-700 bar. Maximum rating of 700 I at 7 bar.

No. 9641 - Pilot operated control valve, normally closed, with 1/4" NPTF male thread. Wt., 0,4 kg.

No. 9643 - Same as 9641 except normally open. Wt., 0,4 kg.



#### HYDRAULIC PUMP

Accessories









350431





#### **OIL COOLER KITS**

**No. 252511 -** Oil cooler kit designed for use with PE604T or PE604PT pumps with 115 VAC. Wt.,2,2Kg.

No. 252512 - Oil cooler kit designed for use with PE604T or PE604PT pumps with 220 VAC. Wt.,2,2 kg.

#### **RESERVOIR BREATHER KITS**

**No. 206767 -** Reservoir breather kit designed for use on PA17, PA55, PE17, PE55, PE84, PE90, PE120, PG55, PG120, PQ60 and PQ120 series pumps. Wt., 0,6 kg.

**No.** 250175 - Reservoir breather kit designed for use on PE21 and PE46 series pumps. These kits replace the reservoir filler cap when the pump is used in dusty and dirty environments. Wt., 0,6 kg.

#### **CASTERS**

50,8 mm diameter casters attach to the bottom of large reservoir for portability. Sold individually; order the amount you need.

No. 10494 - Single caster wheel. Wt., 0,1kg.

#### FLUID LEVEL/TEMPERATURE GAUGE

Displays fluid level and temperature of hydraulic oil in reservoir. 32°-212°F, 0°-100°C. 32 mm wide and 162 mm high.

No. 350431 - Fluid level/temperature gauge.

#### **FOOT CONTROL GUARD**

Guard for use with 10461 and 251660 foot controls. **No. 16339 -** Wt., 2 kg.

#### **MAGNETIC STRIP**

Magnetic strip with adhesive back can be added to No. 25017, 202777, 202778 and 304718 hand controls. Provides 2,7 kg. of holding force.

No. 207762 - Wt., 0,1 kg.



VITON*	SEAL KITS		
Order Number	Use With	Model	
300507	P12	AII	
300472	P23, P55	All	
300510	P59	All	
300508	P157, P159, P300	Α	
300690	P157, P159	В	
300696	P300	В	
300508	P157D, P159D, P300D	Α	
300693	P157D, P159D	В	
300699	P300D	В	
	Order Number 300507 300472 300510 300508 300690 300696 300508 300693	Number         With           300507         P12           300472         P23, P55           300510         P59           300508         P157, P159, P300           300690         P157, P159           300508         P157D, P159D, P300D           300693         P157D, P159D	Order Number         Use With         Model           300507         P12         All           300472         P23, P55         All           300510         P59         All           300508         P157, P159, P300         A           300690         P157, P159         B           300696         P300         B           300508         P157D, P159D, P300D         A           300693         P157D, P159D         B

**VITON\* SEAL KITS** Can be used in all "C" and "RH" series cylinders, as well as the P12, P55, P59, P157/P159, P157D/P159D and P300/P300D series of hand pumps. These seals are required when fire resistant hydraulic fluids are used. For use with phosphate ester fluids. Not required with Flame-Out fluid.

<sup>\*</sup> Viton is an E.I. duPont De Nemours & Co., Inc, trade name.

#### **UNIVERSAL PUMP CART**


Mobilize your hydraulic pumps with the PC200. The rugged tubular frame can easily handle pumps weighing up to 90 kg. With 305 mm wheels, the cart rolls easily. Just load the pump onto the cart and wheel it right to the job. The universal mounting hole pattern lets you handle a wide variety of Power Team pumps.


No. PC200 - Universal pump cart with 305 mm wheels. Cart can be used with the following pumps: PA60, PA64 and PA554 air/ hydraulic pumps; PE55 series, PE183-2 and PE184-2 electric/ hydraulic pumps: PE21. PO60 and PO120 series "Ouiet" pumps: PG55 series gas engine/hydraulic pumps; and pumps with optional 19- and 38 I - reservoirs; Nos. RP50, RP51, RP101 and RP103. Wt., 12,3 kg (Shown with pump, pump not included)

#### PROTECTIVE PUMP ROLL CAGE

Safeguards pump, gas engine and valves on the job site. Horizontal bars provide convenient hand holds for carrying pump, a pick-up point permits lifting unit with an overhead crane or other device. Standard roll cage (RC5) on PG1203 and PG1204. Can be ordered as an option with any other gas, air, or electrically driven hydraulic pump equipped with a 38 I reservoir.

pumps with 38 liter reservoirs.) Wt., 16 kg.





Four mounting holes: 1/2"-20, for 50.8 mm diameter swivel casters (No. 10494)

NOTE: All metal reservoirs are equipped with drain plugs and all necessary conversion items. Hydraulic oil is not included with reservoir kits. Please order separately.

PC200RC

#### METAL RESERVOIR CONVERSION KITS FOR PUMPS \*INCLUDES GASKETS AND FASTENERS.

Metal Pump Number	Res. Order Number	Metal Reservoir Capacity (I)	Reservoir Weight (kg)	Metal Pump Number	Res. Order Number	Metal Reservoir Capacity (I)	Reservoir Weight (kg)	Metal Pump Number	Res. Order Number	Metal Reservoir Capacity (I)	Reservoi Weight (kg)
PA6	213896	1,7	1,4	PA50	213896	1,7	1,4	PA174	213895	9,5	4,1
PA6A	213896	1,7	1,4	PA50R	213896	1,7	1,4	PE172	213895	9,5	4,1
PA6D	213896	1,7	1,4	PA6R	213896	1,7	1,4	PE172A	213895	9,5	4,1
PA6-2	213895	9,5	4,1	PA50R2	213895	9,5	4,1	PE172S	213895	9,5	4,1
PA6D2	213895	9,5	4,1	PA172	213895	9,5	4,1	PE174	213895	9.5	4,1



PC200

RC5

(Pump not included)



<sup>\*\*</sup> High density polyethylene reservoir. † Aluminum reservoir.

# HYDRAULIC ACCESSORIES



	Page					
	FLUIDS 69					
No. of Contract						
	Standard Oil 0,9   , 3,8   , 9,5   , 208   Flame Out 3,8   , 9,5					
	Flame Out 3,8  , 9,5   Bio Degradable 3,8					
	Low Temperature 3,8					
	Low lemperature 5,01					
	Dogo					
	Page					
	HOSES 70					
	Rubber					
	Urethane					
	Non-Conducting					
	COUPLERS 71 Quick Connect Flush Face					
	Dete					
755	Page					
	<b>GAUGES</b> 72, 73					
	Heavy Duty Hydraulic Pressure Gauges					
T	Digital and Analog					
. 4	Page					
	MANIFOLDS 74					
1000	Standard Blocks					
	Blocks with Valves					
	Page					
	700 BAR FITTINGS 75					
	Connectors Tees					
	Couplings Swivels					
	Crosses Special Adapters					
	Elbows					
	Page					
711	VALVES 76-84					
	Directional Control In-Line / Flow					
	III-LIIIE / FIUW					
_						

#### **FLUIDS**

Hydraulic Standard, Flame Out®, Biodegradable and Low Temperature



Oil Description	Qty.	Order No.
Standard Oil	0,9 ℓ (1 qt.)	9636
Standard Oil	3,8 ℓ (1 gal.)	9637
Standard Oil	9,5 $\ell$ (2 $^1/_2$ ga	l.) <b>9638</b>
Standard Oil	208 ℓ (55 gal.)	9616
Flame-Out®	3,8 ℓ (1 gal.)	9639
Flame-Out®	9,5 $\ell$ (2 $^{1}/_{2}$ gal	l.) <b>9640</b>
Biodegradable	3,8 <i>l</i> (1 gal.)	9645
Biodegradable	9,5 $\ell$ (2 $^1/_2$ ga	l.) <b>9646</b>
Low Temp.	3,8 <i>l</i> (1 gal.)	9647

		S	PECIFICATIONS							
		Spec. Gravity					Vis	cosity		Foam
	Grade	at 16°C	Color	Flash	Fire	Pour	SUS @	SUS @	Viscosity	Test
Description	(ASTM)	(kg /ℓ)	(ASTM)	Point	Point	Point	(38°C)	(99°C)	Index	(ASTM)
Standard Oil	215	0.88	2.0	204°C	221°C	-34°C	215	48	100	Pass
									min.	
Flame-Out®	220	0.91	Light Amber	260°C	288°C	-26°C	220	55	140	Pass
									min.	
Biodegradable	_	0.92	2.0	224°C	NA*	-30°C	183	53	213	Pass
									min.	
Low Temp.	_	0.87	6.5	180°C	204°C	-45°C	183	52	190	Pass
			(Red)						min.	

<sup>\*</sup>Not available.

#### Standard Hydraulic Oil

- For dependable performance of all your hydraulic pumps and cylinders.
- Contains foam suppressant additives and has a high viscosity index.

#### Flame-Out® 220 Fire Resistant Hydraulic Fluid

- Contains anti-rust, anti-foam and anti-sludge additives.
- Provides fire resistant protection.

(**Note:** Will burn if heat source is extreme enough. Will not, however, propagate the flame and is self-extinguishing when there is no ignition source.)

- Provides maximum lubrication and heat transfer.
- Offers a wider operating temperature range.
- No need to change seals in your Power Team equipment. Just drain the standard oil and replace it with Flame-Out 220.

#### **Biodegradable Hydraulic Fluid**

- Biodegradable, non-toxic fluid withstands moderate to severe operating conditions; provides excellent protection against rust.
- Offers superior anti-wear properties, has excellent multi-metal compatibility.

Developed to meet stringent performance requirements and satisfy growing environmental needs for hydraulic fluids which are readily biodegradable and non-toxic. Can be used with all Power Team pumps, cylinders, valves and other accessories using standard seals. Depending on the contamination or degradation levels which might be present in used fluid, small amounts of this substance, if spilled, will not affect ground water or the environment. Acceptable methods of disposal include use as a fuel supplement. Since this fluid will not typically be hazardous waste, additional disposal options may be available, including land farming or processing through sewage treatment facilities, if necessary approvals are obtained from appropriate regulatory authorities. This fluid has been tested against EPA 560/6-82-003 and OECD 301 for biodegradability, and toxicity has been tested against EPA 560/6-82-002 and OECD 203: 1-12. Not recommended for operation in temperatures below -7°C or above 71°C. Recommended storage temperatures not below -23°C or above 77°C.

#### Low-Temperature Oil

Provides smooth, reliable operation in the coldest climate conditions.

For additional technical information or to order a **MATERIAL SAFETY DATA SHEET** call **1-800-477-8326** or go to **www.powerteam.com** 



#### HOSES

Polyurethane Rubber Non-Conductive 700 bar (10,000 psi)

- All have plastic hose guards except for the 1/4" I.D. polyurethane hoses which have spring guards.
- 3/8" NPTF fittings on both ends.
- Operating pressure is 700 bar (10,000psi). All comply with MHI standard IJ100.

#### Non-conductive hose

For applications requiring electrical isolation by the hose, non-conductive hose has a leakage factor of less than 50 microamperes, considered a safe level of conductivity by SAE standards. The covering is polyurethane and colored orange for easy identification as non-conductive hose. The covering is not perforated, preventing moisture from entering the hose and affecting its overall conductivity. All non-conductive hoses have a minimum burst pressure of 2800 bar (40,000 psi).

#### **Rubber hose**

2-ply rated hose reinforced with two braids of high tensile steel wire. The rubber covering is oil and weather resistant.

#### **Polyurethane hose**

Made up of nylon core tube with polyester fiber reinforcement which will withstand the minimum SAE bend radius without shortening service life. These hoses last up to seven times longer than rubber hose, and are suitable for continuous service at temperatures from -40° to 150° F (-40° to 66°C).

#### Hydraulic hose assembly

**No. 9764** – Hose assembly consisting of 9767 (1,8 m hose), 6,4mm I.D. polyurethane with 9798 hose half coupler and 9800 dust cap.

**No. 9754** – Hose assembly consisting of 9756 (1,8 m hose), 6,4 mm I.D. rubber with 9798 hose half coupler and 9800 dust cap.







A = 3/8" I.D. Polyurethane B = 1/4" I.D. Polyurethane

C = 1/4" & 3/8" L.D. Rubber D = 1/4" L.D. Non-Conductive

CYLINDER RETURN TIME									
	No. 9769	No. 9781							
	3,1 m Hose	3,1 m Hose							
Cylinder	6,4 mm I.D.	9,5 mm I.D							
C2514C	51 sec.	14 sec.							
C556C	1 min., 30 sec.	24 sec.							
C5513C	4 min., 12 sec.	59 sec.							
C10010C	6 min., 56 sec.	1 min., 3 sec.							


	Hose Type	Hose I.D.	Hose Length	Burst Rating	Order No.	Hose Type	Hose I.D.	Hose Length	Burst Rating	Order No.
	Polyurethane	6,4 mm	0,6 m	1 400 bar	9765	Rubber, Wire-braid	6,4 mm	2,4 m	1 400 bar	9757
	Polyurethane	6,4 mm	0,9 m	1 400 bar	9766	Rubber, Wire-braid	6,4 mm	3,1 m	1 400 bar	9758
	Polyurethane	6,4 mm	1,8 m	1 400 bar	9767	Rubber, Wire-braid	6,4 mm	3,7 m	1 400 bar	9759
	Polyurethane	6,4 mm	1,8 m	1 400 bar	9764*	Rubber, Wire-braid	6,4 mm	6,1 m	1 400 bar	9760
	Polyurethane	6,4 mm	2,4 m	1 400 bar	9768	Rubber, Wire-braid	6,4 mm	9,1 m	1 400 bar	9761
	Polyurethane	6,4 mm	3,1 m	1 400 bar	9769	Rubber, Wire-braid	6,4 mm	15,3 m	1 400 bar	9762
	Polyurethane	6,4 mm	3,7 m	1 400 bar	9770	Rubber, Wire-braid	9,5 mm High Flow	0,9 m	1 400 bar	9733
	Polyurethane	6,4 mm	6,1 m	1 400 bar	9771	Rubber, Wire-braid	9,5 mm High Flow	1,8 m	1 400 bar	9776
	Polyurethane	6,4 mm	15,3 m	1 400 bar	9772	Rubber, Wire-braid	9,5 mm High Flow	3,1 m	1 400 bar	9777
	Polyurethane	6,4 mm	22,9 m	1 400 bar	9750	Rubber, Wire-braid	9,5 mm High Flow	4,6 m	1 400 bar	9734
	Polyurethane	6,4 mm	30,5	1 400 bar	9751	Rubber, Wire-braid	9,5 mm High Flow	6,1 m	1 400 bar	9778
	Polyurethane	9,5 mm High Flow	1,8 m	2 100 bar	9780	Rubber, Wire-braid	9,5 mm High Flow	9,1 m	1 400 bar	9735
	Polyurethane	9,5 mm High Flow	3,1 m	2 100 bar	9781	Rubber, Wire-braid	9,5 mm High Flow	12,2 m	1 400 bar	9736
	Polyurethane	9,5 mm High Flow	6,1 m	2 100 bar	9782	Rubber, Wire-braid	9,5 mm High Flow	15,3 m	1 400 bar	9779
_	Polyurethane	9,5 mm High Flow	15,3 m	2 100 bar	9783	Non-Conductive	6,4 mm	1,8 m	2 800 bar	9773
	Rubber, Wire-brai	id 6,4 mm	0,9 m	1 400 bar	9755	Non-Conductive	6,4 mm	3,1 m	2 800 bar	9774
	Rubber, Wire-brai	id 6,4 mm	1,8 m	1 400 bar	9756	Non-Conductive	6,4 mm	6,1 m	2 800 bar	9775
	Rubber, Wire-brai	id 6,4 mm	1,8 m	1 400 bar	9754*					

NOTE: Polyurethane hoses not recommended for use where heat or weld splatter conditions exist.

<sup>\*</sup> Furnished with 9798 hose half coupler and 9800 dust cap.

#### COUPLERS

Standard & Flush-Face 700 bar (10,000 psi)



#### **CYLINDER AND HOSE COUPLERS**

Designed for use up to 700 bar with hydraulic jacks, cylinders, etc. They are the threaded union type for interchanging cylinders in seconds. Each half is valved with a precision ball for a tight shutoff when disconnected. These couplers also permit the separation of cylinders or hose from pump when at 0 psi with minimal oil loss.

**No. 9795** – Complete quick coupler, 3/8" NPTF. (Includes two 9800 dust caps.)

**No.** 9798 – Male (hose) half coupler (less hose half dust cap), 3/8" NPTF.

**No.** 9796 – Female (cylinder) half coupler with No. 9800 dust cap, 3/8" NPTF.

No. 9796-V - Same as 9796, but with Viton seals.

No. 9796-E - Same as 9796, but with EPR seals.

No. 9799 - Optional metal dust cap (hose half).

No. 9797 - Optional metal dust cap (cylinder half).

#### NO-SPILL, PUSH-TO-CONNECT HYDRAULIC HOSE COUPLERS

High flow, no-spill, push-to-connect couplers with locking collar and flush face designed for high pressure applications. The flush-face concept makes it easy to clean both coupler ends before connecting. Our unique push-to-connect, "dry-break" design eliminates oil spillage. The locking collar makes accidental disconnects a thing of the past. For 700 bar operation. Designed to permit high oil flow.

**No. 9792** – Female (cylinder) half quick coupler only. Wt., 0.1 kg.

**No.** 9793 – Male (hose) half quick coupler only. Wt., 0,1 kg. **No.** 9794 – Complete quick coupler (male and female). Dust caps not included. Wt.,0,2 kg.

#### **HYDRAULIC COUPLER DUST CAP**

Dust cap fits either male or female half couplers. **No. 9800** – Dust cap. For male or female 3/8" NPTF half couplers. Wt., 0.1 kg.



#### **GAUGES**


Analog & Digital 700 bar (10,000 psi)



ASME B40.1 GRADE B



- Gauges feature an easily readable and highly visible, red day-glo needle.
- High strength steel bourdon tube ensures high cycle life.
- Stainless steel cases and lens locking rings.
- Have 1/4" NPT connections.
- 4" and 6" dry gauges\* shipped 'dry' and user can convert to 'wet' using liquid silicone (#9046).



		H.C. Charak	Maian	865	C:I!	11 14/241-	0
		U.S. Short	Major	Minor	Silicone	Use With	Gauge
Face Dia.	psi / Bar	Tons	Graduations	Graduations	Filled	Cylinder Series	No.
63,5 mm	0-10,000 / 0-690	_	2500 psi, 100 Bar	500 psi, 20 Bar	No	All	9041
63,5 mm	0-10,000 / 0-690	_	2500 psi, 100 Bar	500 psi, 20 Bar	Yes	All	9040
100 mm	0-10,000 / 0-690	_	1000 psi, 100 Bar	200 psi, 10 Bar	No*	All	9051
100 mm	0-10,000 / 0-690	_	1000 psi, 100 Bar	200 psi, 10 Bar	Yes	All	9052
		0-17.5,		200 psi, .5 Ton on			
100 mm	0-10,000 / 0-690	0-30 and	2000 psi, 5 Ton	30, 50 Ton Scales; .2	No*	RT172, RT302, RT503	9059
		0-50		Ton on 17.5 Ton Scale			
100 mm	0-10,000 / 0-690	0-5	2000 psi, 1 Ton	200 psi, .1 Ton	No	C & RLS	9053
100 mm	0-10,000 / 0-690	0-10	2000 psi, 1 Ton	200 psi, .1 Ton	No*	C, RD, RH, RLS & RSS	9055
100 mm	0-10,000 / 0-690	0-25	2000 psi, 5 Ton	200 psi, .5 Ton	No*	C & RD	9063
100 mm	0-10,000 / 0-690	0-30	2000 psi, 5 Ton	200 psi, .5 Ton	No*	RH†, RLS & RSS	9065
100 mm	0-10,000 / 0-690	0-50	2000 psi, 5 Ton	200 psi, .5 Ton	No*	RH†, RLS & RSS	9067
100 mm	0-10,000 / 0-690	0-55	2000 psi, 5 Ton	200 psi, .5 Ton	No*	C, R, RA & RD	9069
100 mm	0-10,000 / 0-690	0-60	2000 psi, 5 Ton	200 psi, 1 Ton	No*	RH	9071
100 mm	0-10,000 / 0-690	0-100	2000 psi, 10 Ton	200 psi, 1 Ton	No*	C, R, RA, RD, RH,	9075
						RLS†, RSS† & RT1004†	
100 mm	0-10,000 / 0-690	0-150	2000 psi, Initial	200 psi, 2 Ton	No*	C, R, RD & RLS	9077
			10 Then 20 Ton				
100 mm	0-10,000 / 0-690	0-200	2000 psi, 20 Ton	200 psi, 2 Ton	No*	R, RD & RH†	9079
			10 Then 20 Ton				
150 mm	0-10,000 / 0-690		1000 psi, 100 Bar	100 psi, 10 Bar	No*	All	9089

 $<sup>\</sup>ensuremath{\dag}$  The tonnage scale on the gauge is based on a different effective area.

Note: Remarking & calibration of **9062** pressure gauge to metric tonne or kN scale based on given effective area of cylinder bore for load test or measurement available upon request. (See page 73)



A slight error in tonnage reading will occur relative to the different effective area.



#### No. 9062

100mm (4") dial pressure gauge, calibratable, vibragauge:-

- Top blow out relief grommet.
- · Laminate safety glass window.
- Red aluminum micro-adjustable pointer.
- · Stainless steel case & bayonet ring.
- · Pulsation restrictor screw in socket.
- Accuracy: +/- 1% of full scale, up to 10,000psi (700bar).
- ASME B40.1 Grade 1A.
- 1/4" NPT lower mount.
- Gauge dial face scales in 'psi' (primary) & 'bar' (secondary). (Remarking to metric tonnes or kN scale based on given effective area of cylinder bore & calibration are optional).

#### **Standard Analog Pressure Gauge Accessories**

No. 9046 – Silicone fill kit. 0,2 kg Requires one bottle to fill 100 mm gauge; four bottles to fill 150 mm gauge.

**No. 9048** – Replacement lens and pointer for 100mm dia. gauge except 9062. Indicating pointer for maximum peak reading.

No. 9049 - High performance pulsation dampener.

1/4 " NPTF male x 1/4" NPTF female.



#### **Digital Pressure Gauge**

**No. DG100** – Pressure range 0-10,000 psi.

No. DG100B - Pressure range 0-700 bar.

Note: Serviced only at factory. Wt.,1 kg.

Standard Adapter 115V - For 220V adapter, please request when ordering.

#### Digital Pressure Gauges - DG100 / DG100B

- Accurate to within 1%.
- Larger display characters than ordinary digital gauges.
- Long-life pressure transducer.
- 1/4" NPTF male threads for the pressure connection.
- 1,8 m signal input cable connects to back of display unit.

#### FFATURES

- Pressure values are displayed on large red LEDs in 10 psi increments.
- "Peak" hold feature with reset toggle switch and "Peak On" indicator; Hi/Low set point feature with relay outputs for Hi/Low alarms and/or control signals.
- A slow flashing display indicates pressure below the low limit; fast blinking display alerts if limit is exceeded.
- $\bullet$  High and low limit relays are rated to 5 amps at 115 volts.
- Operating temperature of 18 to 60 °C for the electronic display and -29 to 82 °C for the transducer. Gauge housings are extruded aluminum 1/8 DIN enclosures (NEMA 1 rating).
- When power cable is connected to gauge, display will scroll all characters, performing a self-diagnostic routine.







#### **Digital Pressure Gauge Accessories**


**No. 420778** – Gauge stand for DG100. Has angled base mounting to hold gauge at a convenient viewing angle. Wt., 0,5 kg.

**No. 37045** – Auxiliary power cord for use with any 12 or 24V battery. Wt., 0,1 kg.

Caution: For use on negative ground systems only.

#### **MANIFOLDS**

Remote and Pump Mounted 700 bar (10,000 psi)



#### No. 9691 - "Y" Manifold

Extremely useful when connecting two hydraulic cylinders to a single line. Has three 3/8" NPTF ports. Wt. 0,45 kg.

#### No. 9634 - Manifold block

This manifold is for multiple-cylinder installations, has four 3/8" NPTF ports and two 1/4" mounting holes. Wt. 0,7 kg.

#### No. 9635 - Manifold block

This hex-shaped manifold offers extra versatility with six 3/8" NPTF ports and two 1/4" mounting holes. Wt. 0,9 kg.

#### No. 9617 - Manifold block

When a multiple-cylinder installation is required, this manifold is invaluable.

Has six 3/8" NPTF ports to handle larger multiple-cylinder systems. Wt. 1.4 kg.

#### No. 9648 - Manifold block

This 178 mm long manifold block has seven 3/8" NPTF ports and two 6,4 mm mounting holes. Wt.1,2 kg.

#### No. 9627 - Manifold block

This 406,4 mm long manifold block allows you to mount the 9575 or 9596 valves without interference. Has seven 3/8" NPTF ports and two 6,4 mm mounting holes. Wt. 2,7 kg.

#### No. 9626 - Pump mounted manifold block

Converts pumps with pump mounted valves for use with remote mounted valves. This manifold block is subplate mounted on the pump cover plate and

provides 3/8" NPTF pressure and return ports. Maximum recommended flow rate is 19 l/min. Note: If used on PE30 or PG30 series pump, 12,7mm longer mounting screws are required. Order four (4) No. 11956 screws separately.

# 9642 AND 9644 MANIFOLD BLOCKS WITH NEEDLE VALVES

For independent multiple-cylinder operation, feature needle valves for precise manual control. Designed for remote-mounted applications. Can be used with all Power Team pumps.

No. 9642 – Manifold with two needle valves for control of two cylinders.
Has four 3/8" NPTF ports. Wt. 3,7 kg
No. 9644 – Manifold with four needle valves for control of four cylinders.
Has six 3/8" NPTF ports. Wt. 7,4 kg

**ACCESSORIES** 

#### **FITTINGS**

#### Hydraulic Fittings: All applications. 700 bar (10,000 psi)



=======================================	9190	Hyd. tubing. 3/8" O.D. x .065" wall, 15,3 m. (10 pieces 1,53 m long.) Wt. 5,5 kg.
	9670	Tee adapter. For installing gauge between pump and hose coupling. Has 1/4" and 3/8" NPTF female and 3/8" NPTF male ports. Wt. 0,2 kg.
	9671	Double tee adapter. Permits use of more than one cylinder in series with one pump. Three 3/8" NPTF female ports, Wt. 0,5 kg.
	9672	Service tee. Two 3/8" NPTF female internal, one 3/8" NPTF male external. Wt. 0.3 kg.
	9673*	Swivel connector. 3/8" NPSM male, 1/4" NPSM female. Wt. 0,1 kg.
	9674	Male connector. 43 mm long, 1/4" x 3/8" NPTF. Wt. 0,1 kg.
	9675*	Swivel connector. 3/8" NPTF male, 3/8" NPSM female. Wt. 0,1 kg.
	9676*	Swivel connector. 1/4" NPTF male, 3/8" NPSM female. Wt. 0,1 kg.
	9677*	45° swivel connector. 3/8" NPTF male, 3/8" NPSM female. Wt. 0,1 kg.
	9678	45° fitting. Used when mounting gauge at an angle on connection such as 9670. Male and female 1/4" NPTF ends. Wt. 0,1 kg.
	9679	Connector. 1/4" NPTF female and 3/8" NPTF male. Wt. 0.1 kg.
	9680	Coupling. Both ends 3/8" NPTF female. Wt. 0.1 kg.
	9681	Street elbow. Male and female 3/8" NPTF ends. Wt. 0,1 kg.
	9682	Male connector, 43 mm long, 3/8" NPTF male ends, Wt, 0,1 kg,
	9683	Male connector, 57 mm long, 3/8" NPTF male ends. Wt. 0,1 kg.
	9684	Male connector. 57 mm long, 1/4" NPTF male ends. Wt. 0,1 kg
	9685	Coupling, 1/4" NPTF female and 3/8" NPTF female, Wt. 0.1 kg,

9686	90° elbow. 3/8" NPTF female ends. Wt. 0.2 kg.
9687	Pipe plug. Heat-treated, 3/8" NPTF. Wt. 0.1 kg.
9688	Pipe plug, Heat-treated, 1/4" NPTF, Wt. 0.1 kg.
9689	Connector. 1/4" NPTF male and 3/8" NPTF female, Wt. 0.1 kg,
9690	Male connector. 43 mm long, 1/4" NPTF male ends. Wt. 0.1 kg.
9692	Straight connector, 3/8" tube x 3/8" male NPTF, Wt, 0.1 kg,
9693	90° elbow. 3/8" tube x 3/8" male NPTF. Wt. 0.1 kg.
9694	45° elbow. 3/8" tube x 1/4" male NPTF. Wt. 0.1kg.
9695	Tee. 3/8" tube. Wt. 0.1 kg.
9696	Male run tee. 3/8" tube x 1/4" male NPTF, Wt. 0.1 kg.
9697	Male branch tee. 3/8" tube x 1/4" male NPTF, Wt. 0.1 kg.
9698	Cross. 3/8" tube. Wt. 0.2 kg.
9699	45° gauge fitting, 3/8" NPTF male and female, and 1/4" NPTF female at 45°. Wt. 0.3 kg.
9705	Fitting, swivel. 3/8" NPTF male to 3/8" NPTF female. 90° fitting with internal 370 micron screen. May be rotated 360° about male thread axis.

**NOTE:** Power Team hydraulic fittings are intended for use with our high pressure hydraulic products and are suitable for use at max. working pressures of 700 bar unless otherwise noted.



<sup>\*</sup> CAUTION: On part numbers 9673, 9675, 9676 and 9677 the female swivel end of these adapters is a straight pipe thread (NPSM) with a 30° seat. All male pipe fittings that are used with these female swivel adapters must have an internal 30° seat in order to effect a proper seal. All Power Team male fittings are manufactured with a 30° seat except 9687 and 9688.

#### **VALVE SELECTION**

Choosing The Right Valve

- **Step 1 -** Select the hydraulic cylinder that best suits the application (See page 11-32).
- **Step 2 -** Select the series of hydraulic pump with adequate oil output and reservoir capacity to power cylinder (See page 33-67). Check speed chart (See page 36).
- **Step 3** Select pump within series with the valve option that is best matches cylinder, pump and application (See page 78-81, 84).

#### CONSIDERATIONS:

- Will the valve be used with single- or double-acting cylinders?
- Will the valve be mounted on the pump, away from the pump or directly into the hydraulic lines?
- Will the valve be manually-operated or is remote control preferred?
- Is independent control of multiple cylinders, or hydraulics tools preferred?
- What directional control and pressure control valve functions are needed for the application?

Basic valve types include manually operated, air or solenoid operated and pilot operated. Special application valves for pre-stressing and post-tensioning are also offered. Consult selection chart on page 84 for listings of all Power Team valves.



#### **DIRECTIONAL CONTROL VALVES**

#### 2-WAY, 2-POSITION

(FOR CONTROL OF SINGLE-ACTING CYLINDERS):

POSITION 1 CENTER POSITION POSITION 2



Oil goes from pump to cylinder; pressure is held from valve to cylinder when pump is shut off.

None



Oil goes from pump to cylinder; pressure is released to reservoir when motor is turned off.

#### 3-WAY, 2-POSITION

(FOR CONTROL OF SINGLE-ACTING CYLINDERS)

#### POSITION 1 CENTER POSITION POSITION 2



Oil goes from pump to cylinder and holds when pump is shut off. Return line to reservoir is blocked.

None



Cylinder retracts, oil returns to reservoir.

#### 3-WAY, 3-POSITION

(FOR CONTROL OF SINGLE-ACTING CYLINDERS)

#### POSITION 1 CENTER POSITION POSITION 2



Oil goes from pump to cylinder and holds when pump is shut off. Return line to reservoir is blocked.



Cylinder pressure is held; pump can remain running and oil returns to reservoir.



All oil is open to reservoir through return line.

#### Remote Mounted Valves Available: Consult Factory

IN-LINE HYDRAULIC VALVES (see page 82, 83)

**Load Lowering Valve** – Provides precision metering for controlled return of the cylinder piston.

**Sequence Valve** – Used when a cylinder in a multiple cylinder application must advance before any other.

**Pressure Reducing Valve** – Permits independent pressure control to two or more clamping systems operated by a single power source.

**Shut-off Valve** – For fine metering of hydraulic oil. Several may be used to control multiple single-acting cylinders.

**Check Valve** – Permits flow of hydraulic oil in one direction only.

**Pressure Relief Valve** – Used at remote locations in a hydraulic circuit where maximum pressure requirements are less than the setting of the basic overload valve in the pump. Protects a hydraulic system against over pressurization.

**Metering Valve** – Restricts surges by restricting flow to a certain level; when flow subsides, valve reopens automatically. For systems using large cylinders or extended lengths of hose.

**Pressure Regulator Valve** – Permits external adjustment of operating pressures at various values below the internal relief valve setting of the pump.

#### **DIRECTIONAL CONTROL VALVES**

#### 4-WAY, 2-POSITION

(FOR CONTROL OF SINGLE- OR DOUBLE-ACTING CYLINDERS):

CENTER POSITION POSITION 2



Oil goes to the "extend" side of the cylinder. The oil from the "retract" side returns to reservoir. Cylinder holds with pump shut off.

**POSITION 1** 

None



Oil goes to the "retract" side of the cylinder, oil from the "extend" side returns to reservoir.

#### 4-WAY, 3-POSITION

(FOR CONTROL OF DOUBLE-ACTING CYLINDERS)

#### POSITION 1 CENTER POSITION



Oil goes to the "extend" side of the cylinder, oil from the "retract" side returns to reservoir. Cylinder holds with pump shut off.



Holds pressure even if pump is running. Oil from pump goes through valve, back to reservoir.



Oil goes to "retract" side of cylinder. Oil from "extend" side returns to the reservoir.

**POSITION 2** 

#### TYPICAL CENTERS

#### TANDEM CENTER CLOSED CENTER OPEN CENTER



Cylinder ports are blocked, oil from pump goes to reservoir. Used when pump remains running. Example: gasoline-driven pumps.



Generally used when running multiple valves in series from one pump.




Open Center Used when holding is not a requirement, as when running tow separate hydraulic tools such as cutters and crimpers.

Hydraulic Pump Mounted


Manual Operated


3-Way/2-3 Position

700 BAR (10,000 PSI), 3/8" NPTF PORTS, 19 L/MIN MAX FLOW RATE.









#### 3-WAY/2-POSITION MANUAL VALVES

**Applications** – Single-acting cylinders. **Actuation** – Lever operated.

Functions - Cylinder piston "advance", "hold" and "return".

Used on these pumps - P460, PE17, PE21, PE30, PE46, PE55, PE84, PE90, PE120, PQ60 and PQ120 series.

No. 9582 - 3-way/2-position manual valve. Wt. 1,13 kg.

No. 9584 - Same as 9582, but has "flipper" control. Wt.,0,8 kg.



#### 2-WAY/2-POSITION MANUAL VALVE

Application – Single-acting cylinders. Actuation – Flipper lever operated.

Functions - Cylinder piston "advance", "hold" and "retract".

Used on these pumps - PE172, PA172 and PE84 series.

**No. 9517 –** 2-way/2-position manual valve. Wt.,1,45 kg.

# 3-WAY/3-POSITION (CLOSED CENTER) NON-INTERFLOW MANUAL VALVE WITH "POSI-CHECK"

**Application** – Single-acting cylinders. **Actuation** – Lever operated, detent positioned.

**Functions** – Pos. 1 – Oil is directed from pump to cylinder and "holds" with pump shut off; line to reservoir is blocked. Pos. 2 – All oil is open to reservoir through tank line.

Center pos. - Cylinder pressure is held; pump should be shut off.

**Used on these pumps** – P460, PA17, PA46, PA55, PA60, PE17, PE21, PE30, PE46, PE55, PE84, PE90, PE120, PE200, PE400, P060 and PO120 series.

NOTE: The 9502 can be remote mounted if a 9510 subplate is used (see page 65).

No. 9502 – 3-way/3-position (closed center) manual valve. Wt.,1,9 kg.

#### 3-WAY/3-POSITION (TANDEM CENTER) MANUAL VALVE WITH "POSI-CHECK®"

Application - Single-acting cylinders.

**Actuation** – Lever operated, detent positioned.

**Functions** – "Advance" "hold" and "return". When shifted to "return" position, pump and cylinder return oil through their own separate return lines, allowing faster retraction of piston. The "Posi-Check®" feature guards against pressure loss when shifting from "advance" to "hold" position.

**Used on these pumps** – P460, PA17, PA46, PA55, PE17, PE21, PE30, PE46, PE55, PE84, PE90, PE120, PQ60, PQ120, PE200, PE400, PG30, PG55, PG120 and PG400 series.

No. 9520 - 3-way/3-position (tandem center) manual valve. Wt., 2,3 kg.

**NOTE:** A pressure switch and/or gauge may be attached to any valve on this page. (refer to page 65, 72, 73) Gauge ports monitor pump pressure only, not pressure to the hydraulic cylinder(s).

CAUTION: To prevent sudden, uncontrolled descent of a load as it is being lowered, use a No. 9596 Load Lowering Valve or No. 9720 Counter Balance Valve (see page 82) in conjunction with the directional valve used in your application.

**IMPORTANT:** Conversion kit 251528 must be used when mounting any of the valves on this page on PA17 or PE17 pumps.

**IMPORTANT:** When ordering any valve for a PE30 or PG30 series pump, ½" longer mounting screws are required. For valves 9584, 9502 and 9520, order four 12001 cap screws. For valve 9582, order two 12001 and two 10856 cap screws.

Hydraulic Pump Mounted
Manual Operated
4-Way/3 Position

700 BAR (10,000 PSI), 3/8" NPTF PORTS, 19 L/MIN MAX FLOW RATE.

#### 4-WAY/3-POSITION (TANDEM CENTER) VALVE WITH "POSI-CHECK®"


**Application** – Single or double-acting cylinders.

**Actuation** – Lever operated, detent positioned.

**Functions** – "Advance", "hold" and "return". The "Posi-Check®" feature guards against pressure loss when shifting from "advance" to "hold" position.

**Used on these pumps** – P460, PA6D, PA17, PA46, PA55, PE17, PE21, PE30, PE46, PE55, PE84, PE90, PE120, PE200, PE400, PED, PG30, PG55, PG120, PG400, PQ60 and PQ120 series

No. 9506 - 4-way/3-position (tandem center) manual valve. Wt., 2,3 kg.



#### 4-WAY/3-POSITION (TANDEM CENTER) MANUAL VALVE


Application - Single- or double-acting cylinders.

Actuation - Lever operated, detent positioned.

Functions - The 9500 provides "advance", "hold" and "return".

**Used on these pumps** – P460, PA17, PA46, PA55, PE17\*, PE21, PE30, PE46, PE55, PE84, PE90, PE120, PE200, PE400, PG30, PG55, PG120, PG400, PQ60 and PQ120 series. \*Does not mount without 251528

No. 9500 - 4-way/3-position (tandem center) manual valve. Wt., 1,9 kg.





# 4-WAY/3-POSITION (CLOSED CENTER) MANUAL VALVE WITH "POSI-CHECK®"


**Application –** Single- or double-acting cylinders.

**Actuation** – Lever operated, detent positioned.

**Functions** – Similar to 9506, but is a closed center valve with "Posi-Check®". Generally used to operate multiple cylinders with a single pump. Provides "advance", "hold" and "return". The "Posi-Check®" feature guards against pressure loss when shifting from the "advance" to "hold" position. See note below regarding plugging of ports and resulting heat build-up.

**Used on these pumps** – P460, PA17, PA46, PA55, PA60, PA6D, PE17, PE21, PE30, PE46, PE55, PE84, PE90, PE120, PE200, PE400, PQ60 and PQ120 series.

No. 9507 – 4-way/3-position (closed center) manual valve. Wt., 2,3 kg.



#### 4-WAY/3-POSITION (CLOSED CENTER) MANUAL VALVE


**Application** – Single- or double-acting cylinders.

**Actuation** – Lever operated, detent positioned.

**Functions** – "Advance", "hold" and "return". Closed center design makes valve suitable for operating multiple cylinders from a single pump. See note below regarding plugging of ports and resulting heat build-up.

**Used on these pumps –** P460, PA17, PA46, PA55, PA60, PE17, PE21, PE30, PE46, PE55, PE84, PE90, PE120, PE200, PE400, PQ60 and P120 series.

No. 9501 - 4-way/3-position (closed center) valve. Wt., 1,9 kg.



**NOTE:** A pressure switch and/or gauge may be attached to valves 9500, 9501, 9506, 9507, 9511 if desired (see page 65, 72, 73). Gauge ports monitor pump only, not pressure to the hydraulic cylinder(s).

Also, all valves on this page may be remote mounted with a 9510 subplate (see page 65).

**NOTE:** Valves 9500, 9501, 9506 and 9507 can have a port blocked or have a closed center position for use with single-acting cylinder or tool. When a port is blocked and the valve is shifted to the blocked port, the pump will generate excessive heat. An electric or rotary air pump can either be turned off manually or with a pressure switch. Reciprocating air pumps may be adjusted to stall out and stop.

# Hydraulic Pump Mounted Solenoid or Air Operated



700 BAR (10,000 PSI), 3/8" NPTF PORTS, 19 L/MIN MAX FLOW RATE.

#### 3-WAY/2-POSITION SOLENOID VALVE

Application - Single-acting cylinders.

Actuation - Solenoid operated, 115 volt, 50/60 Hz.

**Functions** – Cylinder piston advances when solenoid is de-energized and pump is running. When solenoid is energized, oil is directed to reservoir, and piston returns. For "hold" position, pump is stopped with solenoid de-energized.

**Used on these pumps** – PE17, PE21, PE30, PE46, PE55, PE84, PE90, PE120, PE200, PE400, PQ60 and PQ120 series.


No. 9579 - 3-way/2-position solenoid valve, 115 volt, 50/60 Hz. Wt., 4,4 kg.

**No. 9569 –** Same as 9579, except with 24 volt, 50/60 Hz solenoid.

No. 9570 - Same as 9579 except with 230 volt, 50/60 Hz solenoid.

**NOTES:** Valves above are shipped without control switch. Use 202777 remote hand switch (see page 64). When this valve is mounted, the pump must be equipped with an outlet check valve.





#### 3/4-WAY/2-POSITION SOLENOID VALVES

**Application** – Single- or double-acting cylinders. When used with single-acting cylinders, one port should be plugged.

**Actuation** – Solenoid operated.

**Functions** — Oil is directed to "extend" side of cylinder, oil from "retract" side goes to reservoir; cylinder "holds" with pump shut off. Oil is directed to "retract" side of cylinder; oil from "extend" side goes to reservoir.

**NOTE:** Cylinder will not "hold" in the "return" position with motor running or shut off. **Used on these pumps** – 9552, 9572 and 9592 are used with PE17, PE30 (with carrying handles removed), PE46, PE55, PE84, PE90, PE200, PE400, PO60 and PO120 series.


**No.** 9592 – 3/4-way/2-position solenoid valve, 115 volt, 50/60 Hz. Wt., 6,6 kg. **No.** 9552 – Same as 9592, except with 230 volt, 50/60 Hz solenoid.

No. 9572 - Same as 9592, except with 24 volt, 50/60 Hz solenoid.

NOTE: Valves above are shipped without controls. The 9552, 9572 and 9592 can be used

with the 304718 remote hand control. (see page 64)

Note: Ports are 1/4" NPTF.



#### AIR ACTUATED VALVE

**Application** – Single- or double-acting cylinders. When used with single-acting cylinders, one port should be plugged.

Actuation - Air operated.

**Functions** – Oil is directed to "extend" side of cylinder, oil from "retract" side goes to reservoir; cylinder "holds" with pump shut off. Oil is directed to "retract" side of cylinder; oil from "extend" side goes to reservoir.

**NOTE:** Cylinder will not "hold" in the "return" position with motor running or shut off. **Used on these pumps** – PA17, PA46 and PA55 series.

**No.** 9594 – 3/4-way/2-position solenoid valve, air operated (minimum of 3.5 bar air pressure required). Wt., 5 kg.

**NOTES:** Valve above is shipped without controls. 9594 can be used with the 209593 remote hand control (see page 64).

**A CAUTION:** To prevent sudden, uncontrolled descent of a load as it is being lowered, use a No. 9596 Load Lowering Valve or No. 9720 Counter Balance Valve (see page 82) in conjunction with the directional valve used in your application.


**IMPORTANT:** Conversion kit 251528 must be used when mounting any of the valves on this page on PE17 pumps.

**IMPORTANT:** When ordering any valve for a PE30 series pump,  $\frac{1}{2}$ " longer mounting screws are required. For valves 9569, 9570 and 9579, order four 10856 cap screws. For valves 9552, 9572 and 9592, order four 12001 cap screws.



Hydraulic Pump Mounted
Solenoid Operated

#### 700 BAR (10,000 PSI), 3/8" NPTF PORTS, 19 L/MIN MAX FLOW RATE.



# 3-WAY/3-POSITION (TANDEM CENTER) SOLENOID VALVES WITH "POSI-CHECK®"

**Application –** Single-acting cylinders.

**Actuation** – Solenoid operated: 9605 is 115 volt, 50/60 Hz; 9599 is 24 volt, 50/60 Hz.


**Functions** – "Advance", "hold" and "return" positions. When in "advance", solenoid "B" is energized and oil goes from pump to cylinder through pressure port. In "return" position, solenoid "A" is energized and oil is directed from cylinder and pump to reservoir. With both solenoids de-energized, in "hold" position, oil from pump is directed back to reservoir while oil is checked in cylinder. The "Posi-Check®" feature holds load when shifting from "advance" to "hold" position.

**Used on these pumps** – Furnished with pilot lines and adapters for PE55, PE30 (carrying handles must be removed) and PE120 series. For application on other models, consult factory.

**No.** 9605 - 3-way/3-position (tandem center) solenoid valve, 115 volt, 50/60 Hz. Wt., 6,4 kg.

**No. 9599 –** Same as 9605 except for 24 volt, 50/60 Hz circuits.

**NOTE:** Valves above are shipped without controls. Use 202777 remote hand control (see page 64). Consult factory for field installation.



# 4-WAY/3-POSITION (TANDEM CENTER) PILOT OPERATED SOLENOID VALVE

**Application** – Double-acting cylinders.

**Actuation –** Solenoid operated, 115 volt, 50/60 Hz.

**Functions** – "Advance", "hold" and "return". The "Posi-Check®" feature holds the load when shifting from the "advance" to the "hold" position.

**Used on these pumps** – PE17, PE21, PE30 (with carrying handles removed), PE46, PE55, PE84, PE90, PE120, PE200, PE400, PQ60 and PQ120 series.

NOTE: A gauge may be attached if desired (see page 72,73).

**No. 9513** – 4-way/3-position (tandem center) solenoid valve, 115 volt, 50/60 Hz. Wt., 8,2 kg.

**No. 9512 –** Same as 9513 except for 24 volt, 50/60 Hz circuits.

**No. 9516** – Same as 9513 except for 12 volt DC. For use on the PG1204S and PG400 series pumps only.

**No. 9519** – Same as 9513 except for 230 volt, 50/60 Hz circuits. Consult factory for field installation.


**NOTE:** Valves above are shipped without control switch. Use 202778 remote hand switch (see page 64).

**CAUTION:** To prevent sudden, uncontrolled descent of a load as it is being lowered, use a No. 9596 Load Lowering Valve or No. 9720 Counter Balance Valve (see page 82) in conjunction with the directional valve used in your application.

**IMPORTANT:** When ordering any valve for a PE30 series pump,  $^1/_2$ " longer mounting screws are required. For valves 9512, 9513, 9516 and 9519, order four 11956 cap screws.



#### Hydraulic In-Line



#### 700 BAR (10.000 psi). 19 L/MIN MAX FLOW RATE.

#### LOAD LOWERING VALVE (SAFETY CHECK VALVE)


Application: Precision metering for controlled cylinder piston return. For single-acting or double-acting cylinder.


**Operation:** Permits free flow when extending cylinder, built-in pressure relief and "Posi-Check®" locks and holds load in raised position until operator opens valve. May be pre-set to provide consistent metered return, or operator may select rate of return with each actuation. Has 3/8" NPTF ports.

NOTE: Pressure relief valve setting is 830 bar. Operating pressure is 700 bar and max. flow rate is 19 I /min.

No. 9596 - Load lowering valve. Wt., 1 kg.







#### **SEQUENCE VALVE**

Application: Used when one cylinder in a multi-cylinder application must advance before any other.

Operation: Pump is connected to port "P" and separate cylinders to ports "A" and "B". When pressure is applied to port "P", cylinder "A" advances. Cylinder "B" will not advance until a predetermined pressure setting is reached in cylinder "A". Pressure setting is adjustable from 35 to 550 bar with adjustment screw; factory preset at 70 bar Has 3/8" NPTF ports.

No. 9597 - Pressure control sequencing valve. Wt., 2,5 kg.




#### PRESSURE REDUCING VALVE

Application: Provides complete, independent pressure control to two or more clamping systems operated by a single power source.

Operation: Can be used to provide different pressures in various stages of a single system. Virtually zero leakage across valve means each system can be operated by a single continuous pressure source. Adjustable from 70 to 350 bar at outlet port "B" (secondary). Has 1/4" NPTF ports.

No. 9608 - Pressure reducing valve. Wt., 2,6 kg.



#### **COUNTER BALANCE VALVE**

Application: : Double-acting cylinders. Provides positive holding and controlled, "chatter-free" lowering of a load.

Operation: Load is raised at flow rate of pump, and held when pump is shut off. When the pump is shifted to "retract", the counter balance valve will continue to hold the load until system pressure exceeds pressure caused by load. The load can then be lowered smoothly

to the flow rate of the pump. The counter balance valve is designed to operate with pumps having a high pressure flow rate of up to 1,9 I /min. and cylinder ratios of 3 to 1.

No. 9720 - Counter balance valve, including two male and two female half two hydraulic hoses, fittings and dust caps. Wt., 4,5 kg.

No. 9721 - Same as 9720, but does not include couplers, hoses, fittings and dust caps. Wt.,4,2 kg.



CAUTION: The 9720 patented counter balance valve has a pilot pressure as high as 210 bar. Because this pressure is applied to the rod end of the cylinder while it is already under load, the system should not be sized for loads greater than 80% of cylinder rated capacity.



CAUTION: To prevent sudden, uncontrolled descent of a load as it is being lowered, use a No. 9596 Load Lowering Valve or No. 9720 Counter Balance Valve in conjunction with the directional valve used in your application. See above, this page.



Application: This needle valve permits fine metering of hydraulic oil. **Operation:** Can be used for controlling multiple single-acting cylinders.

No. 9575 - Shut off valve with 3/8" NPTF ports. Wt., 0,6 kg.







#### Check valve

Application: Permits flow of hydraulic oil in one direction only.

Operation: Installs right in hydraulic line.

No. 9580 - Check valve with 3/8" NPTF male ends. Wt., 0,2 kg.







#### Pilot operated check valve

Application: For use with open or tandem center valves. Permits free flow of fluid in one direction. Operation: Flow is blocked in opposite direction until pilot oil pressure is applied. This prevents the loss of pressure if the valve is inadvertently shifted or the pump line is broken. Minimum cracking pressure is 4,1 bar. Required pilot pressure is approximately 16% of checked system pressure.

No. 9581 - Pilot operated check valve with 3/8" NPTF ports. Wt., 1,7 kg.







#### "In-line" pressure relief valve

Application: Single- or double-acting cylinders. For remote locations in a hydraulic circuit where maximum pressure requirements are less than basic overload valve setting in pump.

Operation: Adjustable from 70 to 700 bar. Valve is spring-loaded and direct-acting.

No. 9623 - Pressure relief valve with 3/8" NPTF ports. Wt., 0,9 kg.



#### 9623



Application: For systems using large cylinders or extended lengths of hydraulic hose.

Operation: Controls surges by restricting flow if it exceeds 26,5 I / min. When flow subsides, valve reopens automatically. Has 3/8" NPTF male end to thread into return port of system control valve, and a 3/8" NPTF female end, permitting return hose to be directly connected.

No. 9631 - Metering valve. Wt., 0.1 kg.







#### "In-line" pressure regulator valve

Application: Single- or double-acting cylinders. Permits adjusting operating pressures at various values below relief valve setting of pump.

Operation: Regulator valve is easily adjusted to maintain pressures between 20 and 700 bar. Maintainsa given pressure setting within 3% over repeated cycles. Flow range is 0,3 I/ min to 23 I / min.


No. 9633 - In-line pressure regulator valve with two 3/8" NPTF inlet ports, one 1/8" NPTF tank port and 1 m drain line kit. Wt., 0,9 kg.

Simply turn the handle clockwise to increase the pressure setting, counter-clockwise to reduce pressure.

Note: 1 m Drain Line Kit is included.

right for ordering information.





Operation: These factory preset valves are designed for maximum flow rate of 19 I / min. Furnished with 1/8" NPTF male port. All valves weigh 0.1 kg. See chart to the


1/8 NPT

**RV21278 Series** 

Valve	Pressure	Valve	Pressure
Order No.	Setting (bar)	Order No.	Setting (bar)
RV21278	697/738	RV21278-52	366/407
RV21278-6	41/44	RV21278-55	386/428
RV21278-10	62/69	RV21278-57	400/442
RV21278-15	103/117	RV21278-60	421/462
RV21278-20	131/152	RV21278-65	455/497
RV21278-28	186/207	RV21278-70	490/531
RV21278-30	207/235	RV21278-75	524/566
RV21278-32	214/228	RV21278-80	559/600
RV21278-35	241/262	RV21278-83	580/621
RV21278-40	283/310	RV21278-86	600/642
RV21278-43	304/331	RV21278-88	614/662
RV21278-48	338/366	RV21278-90	628/669
RV21278-50	352/393	Preset — Non-Sei	rviceable

NOTE: Care should be exercised to protect workers from hot, pressurized hydraulic oil, Install these valves only in an enclosed or shielded area.

Selection Information Pump Mounted Valves 700 bar (10,000 psi)



	m n		1177	VALVES
- 2	MIP.	100		WAINES
				TABLE .




<sup>\* &</sup>quot;S.A." represents single-acting cylinders, "D.A." represents double-acting cylinders Some of the pump-mounted valves may be mounted remotely using a subplate (See page 65). CF: Consult Factory

Remote Mounted Valves Available: Consult Factory



# SHOP EQUIPMENT



THE UNIQUE BENEFITS OF THE POWER TEAM PRESS



#### 1 2 TO 1 SAFETY FACTOR

on hydraulic cylinders and they meet ASME B30.1 standards. Cylinders are easily removed for other applications. Single-acting or double-acting cylinders are available; built-in relief valve on double-acting cylinders.

#### <sup>2</sup> FULL RATED CAPACITY

across width of upper frame, even with workhead moved to one side. (Heavy-duty presses only.)

#### 3 LARGER WORK AREA

than most competitors' models.

#### 4 ALIGNMENT LEVER

for simple pin replacement after raising or lowering the bed.

# 5 CLOSE MANUFACTURING TOLERANCE

allows even load distribution over four alloy steel pins; not two, like some competitors. (Heavy-duty presses only.)

#### 6 OPEN THROAT® FEATURE

on 25 ton press provides additional work area by mounting cylinder on outside for C-frame advantage.

# 7 FRAMES CAN BE USED HORIZONTALLY

for pressing jobs on extra-long shafts (see photo above).

# 8 ELECTRIC, AIR OR HAND HYDRAULIC PUMPS

are available. All are standard Power Team pumps.

#### Externally adjustable relief valve

for precise operator control of working pressure is standard on all electric pumps except PE10 and PE17 series.

#### 24 volt hand switch

for remote control on pumps equipped with solenoid valves.

#### 9 ONE-MAN OPERATION

for bed adjustment. Winch unit quickly raises or lowers bed to desired height. Self-locking winch mechanism prevents bed from dropping when handle is released.

#### 10 **9.5 MM I.D. HOSE** on

spring return cylinders on heavy-duty presses provides up to six times faster cylinder return than standard 6,4 mm I.D.hose.

#### 11 FAST CYLINDER APPROACH

to work provided by 2-speed hand, air or electric pumps.

#### 12 RUGGED UPRIGHTS,

50 percent stronger than channel iron. Four post design means open side for easy loading of long material.


**NOTE:** Certain features do not apply to Power Team 10 ton, Roll-Bed, or economy presses.

**NOTE:** Certain press applications may require guarding. Because of the multitude of possible press uses, it is impossible to design a guard that will meet every customer need. The end user must provide their own guarding where the situations dictate.


# **SHOP PRESS**

#### C Frame 25 Ton Press

- Can be bench mounted or on optional pedestal base.
- Bench mount requires less than 1.4 sq. m. of space;
   on optional pedestal, only 0,4 sq.m. of floor space is needed.
- "Open Throat" design makes loading and unloading of work easy.
- Cylinder head adjusts to three convenient working positions, providing up to 514 mm of "daylight."
- Hydraulic cylinder delivers a 159 mm stroke, is driven by a P59 two-speed hand pump.
- Pedestal Base No. 60846 Provides a stable base for SPM256C. Includes a bracket for mounting the pump on the side of pedestal press. Wt., 34,5 kg. (Available as optional)







	DIMENSIONS														
		C				G	H (Cyl. Retracted)	J	K	L	M	N	P	R	Floor Space
(mm)						(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)
1.972	2 622	610	1.057	914	152	127	260, 387, 514	165	318	$1^{1}/_{2} - 16$	203	1.092	51	178	610 x 622

ORDERING INFORMATION												
Capacity	Туре	Stroke	Cyl.	Order	Speed**		Type	Pump	Prod.Wt.			
(Tons)	Cyl. Used	(mm)	Model	No.	Advance	Pressing	Pump	Model	(kg)			
25	Single-	159	C256C	SPM256C*	3,3 mm/	0,8 mm/	Hand	P59	108			
	Acting				stroke	stroke						

<sup>\*</sup> SPM256C does not include No. 60846 pedestal base.


<sup>\*\*</sup> Typical performance based on pump specifications. Actual speeds may vary with operating conditions.

#### SHOP PRESS

H Frame
10 Ton Bench/Floor Presses



- Ideal for small pressing jobs; repairing small motors, armatures, removing and installing gears, bearings, other press-fit parts.
- Bench press has 391 x 457 mm work area; floor press bed height is adjustable from 127 mm to 1.041 mm with horizontal "daylight" of 553 mm.
- Choices of power sources: single-speed hand pump, electric/hydraulic or air/hydraulic.
- · Hydraulic gauges, hoses and fittings included.
- Pump electrical specification PE10 series -0.19kW 220/230V 50/60Hz, Single Phase.





	niwer2in42													
								H		K	L	Bench Space	Floor Space	
					(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	
Bench	622	841	641	182	391	_	559	279	102	40	102	182 x 641	_	
Floor	1.499	1.718	641	711	127-1.041	152	559	63,5-470*	102	40	102		711 x 730	

#### \*Lateral head movement

				ORDERING I	INFORMATION					
	Cap.	Type of		Cylinder	Order	Speed (	mm./min.)†††	Type	Pump	Prod. Wt.
Frame	(Tons)	Cyl. Used	Stroke	Model	No.	Advan	ce Pressing	Pump	Model †	(kg)
222481 Bench	10	Single-Acting	257	C1010C	SPM1010	1,5 mm	n/stroke	Hand	P55	41,2
222480 Floor	10	Single-Acting	257	C1010C	SPH1010	1,5 mm	n/stroke	Hand	P55	77,5
222480 Floor	10	Single-Acting	257	C1010C	SPE1010-220	55,7	5,1	Elec. ††	PE102-220	79,3
222480 Floor	10	Single-Acting	257	C1010C	SP1010A	93,7	7,6	Air	PA9H	78,1
222480 Floor	10	Double-Acting	254	RD1010	SPE1010D-220	55,7	5,1	Elec. ††	PE104-220	87,0

- † Optional air/hydraulic pumps available on request. Other Power Team pumps can be substituted.
- †† "Advance" position holds pressure with motor shut off. "Return" position advances cylinder with motor running and returns cylinder with motor shut off.
- ††† Typical performance based on 7 bar and 700 bar pump specifications. Actual speeds may vary with operating conditions.

Available with 110/115V, 50/60Hz, Single Phase motor:-

- SPE 1010 (Single-Acting) comes with PE102 Pump.
- SPE 1010D (Double-Acting) comes with PE104 Pump.

Optional: **PE17** series 2-speed pump with 0.37 kW motor.

#### **PRESS**

H Frame
Open Throat® & Economy Press
25 Ton Presses

#### **OPEN THROAT PRESSES**

- Design permits use as both "H" frame and "C" frame press; cylinder can be mounted on frame extension to handle jobs which won't fit between uprights.
- Open throat press models are also available with remote control to enable the operator to view work from all sides with fingertip control of cylinder piston travel.
- Off-center pressing loads of full capacity can be applied across entire width of frame.


#### **ECONOMY PRESSES**

 Rugged, yet reasonably priced. Handles many "big press" tasks, and perfect for many of the "in-between" jobs you see almost daily.

Note: Stroke length limited to 159 mm on economy models.

#### FEATURES OF BOTH OPEN THROAT AND ECONOMY PRESSES

- Press bed height easily adjustable with winch. Bed will not drop when handle is released.
- Choice of power sources for rapid cylinder advance: two-speed hydraulic hand pump, electric/hydraulic or air/hydraulic.




SPE2514

"Open Throat!



**PE17 Series -** 0,37 kW

**PE21 Series** – 0,75 kW (Available in 115 volt,60 cycle or 220 volt, 50 cycle, single phase)



Open Throat feature enables cylinder to be mounted on outside of press frame for fast bearing removal and more.





0							DIMEN	ISIONS					
'n	Α		C	D*			G	H	J	K	L	M	Floor Space
					(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)
	1.727	1.092	711	76-737	175-1.102	114	813	140	165	178	64	203	1.092 x 711

				ORDERING I	NFORMATIC	DN				
Cap. (Tons)	Type of Cylinder Used	Stroke (mm)	Cylinder Model	Order No.	Speed (mm Advance	/min.) ††† Pressing	Type Pump	Valve Type	Pump‡ Model	Prod.Wt. (kg)
"Open	Throat" presses	s								
25	Single-Acting	362	C2514C	SPA2514	249	30	Air	2-Way Foot	PA6	309
25	Single-Acting	362	C2514C	SPM2514	12,4 mm/	0,8 mm/	Hand	Load -	P159	314
					stroke	stroke		Release		
25	Single-Acting	362	C2514C	SPE2514-220	1184	84	Elec.	2-Way††	PE172-50-220	301
25	Single-Acting	362	C2514C	SPE2514S-220	1321	102	Elec.	3-Way†	PE213S-50-220	344
25	Double-Acting	362	RD2514	SPE2514DS-22	0 1321	102	Elec.	4-Way†	PE214S-50-220	357
"Econo	my" presses									
25	Single-Acting	159	C256C	SPA256	249	30	Air	2-Way Foot	PA6	197
25	Single-Acting	159	C256C	SPM256	3,0 mm/	0,8 mm/	Hand	Load -	P59	205
					stroke	stroke		Release		
25	Single-Acting	159	C256C	SPE256-220	1184	84	Elec.	2-Way††	PE172-50-220	210

- † Solenoid valve with 12 volt remote control hand switch.
- †† Holds pressure with motor shut off. Also has an automatic dump setting. Furnished with a 3.1m remote motor control.
- †††Typical performance based on 7 bar and 700 bar pump specifications. Actual speeds may vary under operating conditions.
  - ‡ Pump standard with press. Other Power Team pumps can be substituted.
    dBA at idle and 700 bar: PE172–67/81 dBA; PE 21-70 dBA measured at 0,9 m distance, all sides.

Available with 115 Volt, 60Hz motor (to order, remove suffix "-220" from SPE no.)



#### **PRESS**

H Frame
55 Ton Presses

- Full off-center pressing at full rated capacity across width of upper frame without buckling or bending.
- Maximum "daylight" is 1.067 x 914 mm, making positioning of even bulky work pieces easy.
- Height of press bed is easily adjusted with winch; friction brake prevents bed from dropping and handle from spinning upon release.
- Presses with single-acting cylinder offer choice of 2-speed hand operated, electric/hydraulic, or air/hydraulic pump. Models with double-acting cylinder have an electric/hydraulic pump.
  - No. SF50 Straightening
    fixtures for use with 55-ton
    shop or 80-ton Roll-Bed®
    presses (2 ea.). Wt., 47,2 kg.
    Not part of press, order
    separately.

\*Lateral head movement

- Press models equipped with remote control enable operator to view work from all sides with fingertip control of cylinder piston travel.
- Press can be used horizontally for special applications with user-supplied support legs.
- Pump electrical specifications

**PE 17 series** - 0.37 kW

PE 21 series - 0.75 kW

**PQ 60 series** - 1.49 kW

Available in 115V/60Hz or 220V/50Hz Single phase.



						DIMENSIO	NS				_
		C				G	Н	J	L	M	Floor Space
				(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)
1.829	1.232	914	83-832	152-1.067	152	914	171	203	76	305	1.232 x 914

				ORDERIN	G INFORMA	TION				
Cap. (Tons)*	Type of Cylinder Used	Stroke (mm)	Cylinder Model	Order No.	Speed (n Advance	nm/min.) <sup>†††</sup> Pressing	Type Pump	Valve Type	Pump‡ l Model	Prod.Wt. (kg)
55	Single-Acting	159	C556C	SPA556	114	12,7	Air	2-Way Foot	PA6	318
55	Single-Acting	159	C556C	SPM556	5,8 mm/	0,4 mm/	Hand	Load-	P159	323
					stroke	stroke		Release		
55	Single-Acting	337	C5513C	SPM5513	18,9 mm/	0,7 mm/	Hand	2-Way	P460	435
					stroke	stroke				
55	Single-Acting	159	C556C	SPE556-220	551	38	Elec.	2-Way††	PE172-50-220	333
55	Single-Acting	337	C5513C	SPE5513-220	551	38	Elec.	2-Way††	PE172-50-220	444
55	Single-Acting	337	C5513C	SPE5513S-220	620	48	Elec.	3-Way†	PE213S-50-220	478
55	Double-Acting	333	RD5513	SPE5513D-220	551	38	Elec.	4-Way	PE174-50-220	450
55	Double-Acting	333	RD5513	SPE5513DS-220	1679	137	Elec.	4-Way†	PQ604S-50-220	505

<sup>\*</sup> Frame is shipped assembled.

Available with 115 Volt, 60Hz motor (to order, remove suffix "-220" from SPE no.)

<sup>†</sup> Solenoid valve with 24 volt remote control hand switch.

<sup>††</sup> Holds pressure with motor shut off. Also has an automatic dump setting. Furnished with a 3,1 m remote motor control.

<sup>†††</sup> Typical performance based on 7 bar and 700 bar pump specifications. Actual speeds may vary with operating conditions.

<sup>‡</sup> Pump standard with press. Other Power Team pumps can be substituted. dBA at idle and 700 bar: PE172—67/81; PE21-70; PQ 60-74/76; measured at 0,9 m distance, all sides.

#### **PRESS**

H Frame 100, 150 & 200 Ton Presses



No. SF150 – Straightening fixtures for use with 100-ton shop press and 100-, 150-, and 200-ton RollBed® presses (2 ea.).
Wt., 89 kg. Not part of press, order separately.

- Cylinder workhead glides across upper frame on rollers, locks in place for off-center pressing jobs. May be used horizontally for special pressing applications with user-supplied supports.
- Press bed is raised and lowered by winch which locks in place for insertion of bed retaining pins. Upper bolster can be lowered for convenient positioning on repetitive jobs.
- Generous "daylight" accommodates bulky work pieces, uprights are placed for easy side entry of bars or shafts for straightening or bending.
- Choice of single- or double-acting cylinder. Hydraulic pump options include: 2-speed hand pump with large 7,6 I reservoir, PE172 electric/hydraulic pump or "PQ" series "Quiet" electric/hydraulic pump with low noise level.

# PUMP ELECTRICAL SPECIFICATIONS

**PE17 Series** – 0,37 KW, 220 volt, 50 cycle, single phase. Also available in 115 volt, 60 cycle, remove suffix "-220" from order no.


**PQ60 Series** – 1.49 KW, 220 volt, 50 cycle, single phase.
Also available in 115 volt, 60 cycle, remove suffix "-220" from order no.

**PQ120 Series** – 2,24 KW, 380V, 50 Hz, three phase. (Suitable for 415V/50Hz/3 Phase) Also available in 460V/60Hz/3 phase, remove suffix "-380" from order no. (Suitable for 440V/50Hz/3 Phase)



are included with presses.





	NI O	 NS

			C	D*	E	F	G	Н	J	L	М	Floor Space
Сар			(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)
100T:	1.962	1.626	914	178-1.092	51-1.067	203	1.270	203	254	86	381	914 x 1.988
200T:	2.286	1.803	1.118	279-991	228-1.111	279	1.270	318	381	105	457	1.117 x 1.803

\*Lateral head movement

	ORDERING INFORMATION												
Cap.	Type of	Stroke	Cylinder	Order	Speed (mi	m/min.)††	Type	Valve	Pump‡	Prod. Wt.			
(Tons)	Cyl. Used	(mm)	Model	No.	No. Advance Pr		Pump	Туре	Model	(kg)			
100	Single-Acting	260	C10010C	SPM10010	9,0 mm/	0,3 mm/	Hand	3-way	P460	769			
					stroke	stroke							
100	Single-Acting	260	C10010C	SPE10010-220	889	74	Elec.	3-way	PQ603-50-220	813			
100	Single-Acting	260	C10010C	SPE10010R-220	292	20	Elec.	2-way	PE172-50-220	766			
100	Double-Acting	333	RD10013	SPE10013DS-380	889	147	Elec.	4-way**	PQ1204S-50-380	854			
150	Double-Acting	333	RD15013	SPE15013DS-380	610	99	Elec.	4-way**	PQ1204S-50-380	1.366			
200	Double-Acting	333	RD20013	SPE20013DS-380	457	74	Elec.	4-way**	PQ1204S-50-380	1.484			


- † Frame is shipped assembled.
- \*\* Solenoid valve with 24 volt remote control hand switch.
- †† Typical performance based on 7 bar and 700 bar pump specifications. Actual speeds may vary under operating conditions.
- ‡ Pump standard with press. Other Power Team pumps can be substituted.
  dBA at idle and 700 bar: PE172—67/81; PQ60—74/76; PQ120—73/78. Measured at 0,9 m distance, all sides.


#### **MOBILE FLOOR**

# **CRANES**

1000 - 2000kg







#### DIMENSIONS

Order No	o.: FC2200	FC4400
Capacity, boom retract (kg)	1,000*	2,000**
Capacity, boom extend (kg)	750	1,500
A Max. boom hgt., ret (mm)	2,718	2,819
B Max. boom hgt., ext. (mm)	2,972	3,099
C Overall hgt., boom horiz. (mm)	2,032	2,083
D Overall length (mm)	2,108	2,261
E Min. throat width (mm)	610	635
F Inside leg length (mm)	1,372	1,461
G Eff. boom reach -ret.(mm)	838	902
H Eff. boom reach -ext. (mm)	1,219	1,238
J Inside leg width (mm)	610 - 914 - 1,219	660 - 1,016 - 1,333
	(3 –position)	(3 –position)
K Leg height (mm)	203	241
L Dolly wheel diameter (mm)	127	127
M Wheel diameter (mm)	152	203
N Caster diameter (mm)	152	152
space, folded (mm)	686 x 965	787 x 1,067
Height, folded (mm)	2,007	2,184



SHOP EQUIPMENT

- Adjustable legs spread to clear obstacles, telescoping boom for extra reach.
   Rugged construction, reliable hydraulics.
- Boom collapses completely and legs fold for compact storage.
- 2-speed hydraulic hand pump provides fast boom travel and precise operator controlled descent.
- Roller bearing wheels and a steering dolly provide ease of mobility. Lifting chain is included.

**No. FC4400** – \*\*2000 kg cap. crane with fold-away feature, adj. leg spread, lifting chain and 2-speed hand pump. Wt.293 kg.

#### **ROLL-BED® PRESS**

H Frame 80 to 200 Ton Presses






#### Heavy-Duty Straightening Fixtures



No. SF50 – Fixtures for use with 80-ton Roll-Bed® presses or 55-ton heavy-duty shop presses. (2 ea.). Wt. 47,2 kg. Not part of press, order separately.



No. SF150 – Fixtures for use with 100-, 150- and 200-ton Roll-Bed® presses and 100-ton shop presses only (2 ea.). Wt. 89 kg. Not part of press, order separately.



- Movable workhead glides easily side-to-side for full off-center load capacity across width of upper frame.
- "Daylight" is 1.283 x 1.524 mm for 80- and 100-ton models; 1.302 x 1.625 mm on 150- and 200-ton presses.
- Fast approach of double-acting, 334 mm stroke cylinder is provided by PQ1204S "Quiet" electric/ hydraulic pump with remote control hand switch. Operator can view work from all sides with fingertip control of cylinder piston travel.

#### **PRESS FEATURES:**

 Roll-Bed® design – Bed glides in or out on bearings to make loading and unloading fast and easy.

- Adjustable lower bed width For secure balancing and centering of heavy jobs.
   Loosen adjusting bolts to adjust bed from 102 to more than 686 mm. See dimension "H."
- Movable workhead For off-center pressing jobs, workhead moves on bearings across upper bolster. Presses can be used at full capacity, regardless of where workhead is placed.
- Lifting mechanism Simply turn crank handle
  to raise or lower upper bolster. Screw
  mechanism raises or lowers both sides evenly
  (a heavy-duty 1/2" drill motor can replace
  handle for automatic adjustment). Four locking
  pins hold bolster in place for pressing.

Optional heavy-duty straightening fixtures –
 Make straightening jobs easy and accurate
 to within 0.1 mm! Rollers are ball bearing
 mounted and handle raises or lowers for
 easy turning of the work.

#### PUMP ELECTRICAL SPECIFICATIONS

**PQ120 Series** – 2,24 KW, 380 volt, 50 cycle, three phase.

**NOTE:** Different voltage and valve options can be obtained by substituting certain PA, PE or PQ series pumps. Consult the factory.





Lifting screw and locking pins make bolster raising a one-man job.




Bearings make bed positioning smooth and easy.



Lever lowers bed for pressing, raises it for rolling.



Cylinder is easily moved across width of upper bolster.





Width adjusts from 102 mm to over 686 mm; is secured with locking bolts.



	DIMENSIONS												
Сар			C			F	G	H	J	K	L	M	Floor Space
(Tons)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)
80	2.861	1.632	1.283	686	305-1.524	368-914	76,2	102-692	203	927	86	381	1.632-1.537
100	2.861	1.632	1.283	686	305-1.524	368-914	76,2	102-692	203	927	86	381	1.632-1.537
150	3.131	1.734	1.302	762	229-1.626	352-949	76,2	102-689	279	946	105	457	1.734-1.607
200	3.131	1.734	1.302	762	229-1.626	352-949	76,2	102-689	279	946	105	457	1.734-1.607

		ORDERING INFORMATION													
Capacity	Type of	Stroke	Cylinder	Order	Speed (m	m/min.)††	Type	Valve	Pump‡	Prod. Wt.					
(Tons)†	Cylinder Used	(mm)	Model	No.	Advance	Pressing	Pump	Type	Model	(kg)					
80	Double Acting	333	RD8013	RB8013S-380	1168	190	Elec.	4-way*	PQ1204S-50-380	1.307					
100	Double Acting	333	RD10013	RB10013S-380	889	147	Elec.	4-way*	PQ1204S-50-380	1.334					
150	Double Acting	333	RD15013	RB15013S-380	610	99	Elec.	4-way*	PQ1204S-50-380	2.019					
200	Double Acting	333	RD20013	RB20013S-380	457	74	Elec.	4-way*	PQ1204S-50-380	2.059					

- \* Solenoid valve with 24 volt remote control hand switch.
- † Frame is shipped assembled.

  ‡ Pump standard with press. Other Power Team pumps can be substituted. dBA at idle and 700 bar: PQ120-73/78; measured at 0,9 mdistance, all sides.
  †† Typical performance based on 7 bar and 700 bar pump specifications. Actual speeds may vary with operating conditions.

Available with 460Volt, 60Hz, 3-phase motors (to order, remove suffix "380" behind press order number), suitable for 440V, 50Hz, 3 ph ase. 380V/50Hz/3 phase also suitable for 415V/50Hz/3 phase.

# JACKS

BOTTLE JACKS...95
2-110 Ton



Page ....97 **TOE JACKS** 5½ - 27½ Ton



...95 LOW PROFILE BOTTLE JACKS



Page
...98-101
PORTABLE HIGH
TONNAGE RAILROAD
JACKS 55-300 Ton



Page ...96
BOTTLE JACKS
TELESCOPING
6-15 TON



Page ....102
POST TENSION JACKS
20-30 Ton



JACKS

Page ....96 SIDEWINDER JACKS



Page ....103 MAINTENANCE SETS



ECONOMY TOE JACKS...97 2-10 Ton



...104, 105
INFLATABLE JACKS
1-74 Ton



# INDUSTRIAL LIFTING AND PUSHING APPLICATIONS.

- Choose from this complete line of premium—quality, standard bottle jacks.
   Ideal for use in any number of industrial lifting and pushing applications.
- The 9110B, 9015B, 9022B and 9033B feature a beveled base which allows the jack to "follow" the load, reducing the chance of dangerous side-loading.
- Many jacks feature screw extensions and all can be used in the vertical, angled or horizontal positions.
- Serrated or contoured saddles help stabilize the load for a safer lift.
- All jacks meet ASME B30.1 standards and carry the Power Team Marathon Lifetime Warranty.
- 110-ton jack features dual pumps for time-saving two-speed operation.

#### **BOTTLE JACKS**

2 to 110 Ton

Portable Hydraulic Power

Sta	ndar	d				ORDERIN	NG INFO	RMATION					
			Retracted Height	Length of Screw	Height w/Screw	No. Pump Strokes to	Saddle	Base	Pump Handle	Handle Effort at		Metric tons	Product
Cap.	Stroke	Order	Min.	Ext.	Ext.	Ext. Piston	Dia.	Size	Length	Rated Cap.	Carry	at 700	Weight
Tons	(mm)	Number	(mm)	(mm)	(mm)	completly	(mm)	(mm)	(mm)	(kg)	Handle	(bar)	(kg)
2	114	9002A	181	49	344	5	25	110x65	311	34	No	1,8	2,2
3	114	9003A	191	60	365	10	29	114x72	489	20,4	No	2,7	2,6
5	121	9005A	200	70	391	12	35	132x76	545	24,9	No	4,5	3,6
8	121	9008A	200	70	391	18	38	152x89	605	34	No	7,3	5,5
12	149	9112A	241	79	470	26	48	165x106	605	27,2	Yes	10,9	7,9
15	156	9015B	230	110	495	27	60	130x140†	700	40,8	No	13,6	8,3
20	159	9120A	270	40	429	22	51	183x129	800	31,7	Yes	18,1	12,9
22	156	9022B	240	110	505	36	60	165x160†	700	40,8	Yes	20,0	10,7
30	159	9030A	279	_	438	35	60	192x141	1.000	22,7	Yes	27,2	18,7
33	143	9033B	240	100	483	56	65	184x176†	700	39,9	No	29,9	14,5
50	171	9050A	305	_	476	35	76	237x187	1.000	38,6	Yes	45,4	35,4
110	156	9110B	300	_	456	40/160‡	111	339x291	700	35,8	Yes	99,8	70
+ Com	oc with	a Povolo	1 Paca										

<sup>†</sup> Comes with a Beveled Base

#### **For Low Clearance Jobs**

Beveled BASE

9033B

9008A

9112A

- All the quality, features and lifting capacity of the standard jacks in short form. The 12-ton and 20-ton models feature screw extensions for added versatility.
- All jacks meet ASME B30.1 standards and carry the Power Team Marathon Lifetime Warranty.
- All jacks operate both vertically and horizontally for use in a variety of lifting, pushing and spreading applications.





	Lo	w Prof	file				ORDERIN	G INFORM	MATION					
	Cap. Tons	Stroke (mm)	Order Number	Retracted Height Min. (mm)	Length of Screw Ext. (mm)	Height w/Screw Ext. (mm)	No. Pump Strokes to Ext. Piston (mm)	Saddle Dia. (mm)	Base Size (mm)	Pump Handle Length (mm)	Handle Effort at Rated Cap. (kg)	Carry Handle	Metric tons at 700 bar	Product Weight (kg)
ľ	12	95	9012A	171	76	343	26	48	165x106	605	27	Yes	10,9	6,4
	20	86	9020A	181	40	305	22	51	183x129	800	32	Yes	18,1	10,1
	30	79	9130A	181	_	260	35	60	192x141	1.000	23	Yes	27,2	13,7
	‡ 2 Spe	ed: Rapi	d advance	≈40 strokes	; Lift mode≈	160 stroke								

<sup>† 2</sup> Speed: Rapid advance≈40 strokes; Lift mode≈160 strokes

#### **BOTTLE JACKS**

5 to 20 Ton

Portable Hydraulic Power



- Telescoping jacks offer all of the quality features and capabilities of the standard bottle jack line with a bonus. The super-long stroke of these jacks saves time and effort by eliminating the need to lift, crib, lift, etc. In most applications, the user can place the jack once and complete the lift.
- The 9015X offers very low clearance capability, making it the ideal choice for forklift maintenance or machine lifting.
- The taller 9006X, 9011X and 9013X all feature a unique beveled base that allows the jack to "follow" the load laterally as it is raised, greatly reducing side-loading of the piston.

Tel	lesco	ping Ja	icks			ORDERING INFORMATION							
Cap. Tons		Order Number	Retracted Height Min. (mm)	Length of Screw Ext. (mm)	Height w/Screw Ext. (mm)	No. Pump Strokes to Ext. Piston 25,4 mm	Saddle Dia. (mm)	Base Size Beveled Base (mm)	Pump Handle Length (mm)	Handle Effort at Rated Cap. (kg)	Carry Handle	Metric tons at 700 bar	Product Weight (kg)
6	305	9006X	216	_	521	14	44	121 x 133	700	36	No	5,4	6,4
11	262	9011X	200	68	530	25	41	160 x 165	700	40	No	10,0	8,8
13	254	9013X	230	84	570	35	48	176 x 186	700	36	Yes	11,8	11,3
15	181	9015X	170	70	419	32	52	143 x 194	600	43	Yes	13,6	12







- Retracted height of just 63,5 mm for the smallest jack and 130,2 mm for the 20 ton, allows you to slip this jack into the narrowest of crevices.
- Jacks operate either horizontally or vertically. Handles function in line with base for easier use in confined spaces.
- The perfect addition to any toolbox, this remarkable little jack has multiple uses that are limited only by your imagination. Use it as a jack or a spreader. Use it to turn your mechanical gear puller (puller capacity must match jack capacity) into a hydraulic puller. Use it vertically or horizontally in limited clearance.


Sid	ewinde	r Jacks			ORD	ERING IN	IFORMATIO	N				
Сар.	Stroke	Order	Retracted Height Min.	Max Height	No. Pump Strokes to Ext. Piston	Saddle Dia.	Base Size Dia.	Pump Handle Length	Handle Effort at Rated Cap.	Carry	Metric tons at 700	Product Weight
Tons	(mm)	Number	(mm)	(mm)	25 mm	(mm)	(mm)	(mm)	(kg)	Handle	bar	(kg)
5	19	9105A	63,5	85,7	30	29	73,8	240	26	No	4,5	1,9
5	38	9205A	88,9	130,2	38	29	73,8	240	26	No	4,5	2,4
10	30	9210A	120,7	149,2	36	42,1	109,9	440	28	No	9,1	5,5
20	30	9220A	130,2	160,3	46	52,8	119,9	605	35	No	18,1	8,0

# TOE JACKS

2 to 27.5 Ton



- These bottle jack-style toe jacks are loaded with many of the same features as our standard bottle jacks, but the toe-lift feature and swiveling pump handle socket make them ideal for machinery lifting and positioning.
- An internal pressure relief provides added safety by limiting the jack's lifting capability to the capacity of the toe.
- Spring return is an added feature on the larger jacks.
- Swiveling pump handle assembly available on the 5- and 10-ton models.
   The swiveling jack assembly allows you to access and pump the unit from numerous positions.



	Д		,	DNS				
Order	Ret.	Ext.	Ret.	Ext.	C	D	E	F
Number	(mm)							
J24T	16	140	232	356	47,5	181	51	125
J55T	25	149	292	476	47,5	257	191	157
J106T	32	181	327	476	64	292	100	241

Meets ASME B30.1 standard

			ORDERING I	NFORMATION			
	Max Lift		Strokes to	Handle Effort		Metric	Product
Cap.	Stroke	Order	<b>Extend Pistor</b>	ı at Max Load	Carry	tons at	Wt.
Tons	(mm)	Number	25 mm	(kg)	Handle	700 bar	(kg)
2	121	J24T	14	19	Yes	1,8	8,3
5	121	J55T	22	27	Yes	4,5	24
10	146	J106T	31	33	Yes	9,1	38
2 5	121 121	J24T J55T	14 22	19 27	Yes Yes	1,8 4,5	8,3 24




#### **GET UNDER EQUIPMENT WITH ONLY 27MM OF GROUND CLEARANCE**

- With lifting points on the toe and on the top, these extremely rugged jacks are ideal for machine lifting, rigging, lift truck service and much more.
- Choose from 5.5-ton, 11-ton, and now, an amazing 27.5-ton lifting capacity.
- All jacks operate both vertically and horizontally.
- Base, toe and pumping assembly swivel independently, allowing the jack to work in confined areas.



DIMENSIONS											
		A	:	3	C	D	E	F	G	Н	J
Order	Ret.	Ext.	Ret.	Ext.							
Number	(mm)										
J58T	27	238	375	584	368	451	71	56	176	41	130
J109T	27	264	419	654	368	451	76	56	183	64	171
J259T	54	289	505	738	210	756	146	102	267	89	270




Cap.	Max Lift Stroke (mm)	Order Number	Strokes to Extend Piston 25,4 mm	Handle Effort at Max Load (kg)	Carry Handle	Metric tons at 700 bar	Product Wt. (kg)
$5^{1}/_{2}$	210	J58T	8	38,1	Yes	5,0	19,5
11	235	J109T	13	40	Yes	10,0	29
<b>27</b> <sup>1</sup> / <sub>2</sub>	233	J259T	21	40	Yes	24,9	92,1

ORDERING INFORMATION

# PORTABLE HIGH TONNAGE JACKS

60 & 100 Ton Railroad Edition





- Patented load lowering valve. Lowers load smoothly and safely. Eliminates dangerous chatter and bounce.
- Full range of rod extensions. Jack comes fully equipped with extensions to match lifting pad heights on most rolling stock. Max. lifting height to 1,778 mm.
- Low collapsed height, long stroke. 610 mm collapsed height for low-clearance lift pads. 360 mm stroke for maximum lift.
- Adjustable, ergonomic handle. Handle tilts to start the job and is easily locked/ unlocked without moving from operating position.
- Cribbing block set with handles and convenient storage rack. Provides solid mechanical load holding.
- High-profile, low rolling resistance, foamfilled tires. Jack can be moved and positioned with minimal effort. No chance of downtime due to punctured tires.
- Electric and air motor options. Quiet, powerful air and electric motor powered units available.
- · Contact factory for:-
  - lower collapsed height
  - custom cribbing block sizes
  - custom piston rod extensions

252	
6.00	S)
10000	JACKS

		POWER UNIT S	SPECIFICATIO	DNS		
Order No.	Motor	Power Req.	Motor Control	Valve Function	Power Cord	dBa at 700 bar
PLE6014- 220	0,84 kW, 220 VAC***, 50 Hz Single Phase	12 amps	6,1 m Remote Control	Lift Hold Lower Manual	Pigtail	80/95
PLA6014	Rotary Air Powered (	1,417 I/m at 6 bar 50 cfm at 80psi)	6,1 m Remote Air Control	Lift Hold Lower Manual	NA	82

\*\*\* For 110/115V-50/60 Hz order PLE6014





		ORDER	INFORMATIO	DN	
Capacity (Tons)	Stroke (mm)	Order Number	Retracted Height (mm)	Extended Ht. w/Extensions (mm)	Product Wt. Less Cribbing & Ext. (kg)
60 60 100	356 356 356	*PLA6014K *PLE6014K-220 Consult Factory	610 610 610	1.778 1.778 1.499	237 237 237

\*Includes cribbing block set stored on jack handle rack, and 7 extensions (25,4; 50,8; 76,2; 101,6; 127; 254 and 308 mm)

PLE6014 = Jack, Electric (115 V), includes: Cart, Pump & Cylinder PLE6014-220 = Jack, Electric (220 V.) includes: Cart, Pump & Cylinder

PLA6014 = Jack, Air, includes: Cart, Pump & Cylinder
CBS60 = Cribbing Block Set (5 cribbing blocks)
PL60EXT = Extension Set (Consists of 7 extensions)

# | CRIBBING BLOCKS (CBS60, INCLUDED) | Oty. | Height (mm) Order Number | 1 | 38,1 | 351954 | 4 | 76,2 | 351953 |



# EXTENSIONS (PL60 EXT, INCLUDED)

(I LUU	(I LUU LKI, INULUBLE)									
Extension		Extension								
Length	Order	Weight								
(mm)	Number	(kg)								
25,4	351931	2,2								
50,8	351927	4,0								
76,2	351928	6,4								
101,6	351929	8,7								
127	66053	9,5								
254	66054	13,8								
508	66055	22,1								



Lifting range (in 25,4 mm increments): 610 mm- 1.778 mm.

Only 3 extensions are needed to provide this range.

Do NOT exceed 1.778 mm lifting range on 60-ton unit or 1.489 mm on 100-ton unit.



# PORTABLE HIGH TONNAGE JACKS

55, 100, 150, 200 & 300 Ton



PORTABLE AND COMPACT, IDEAL FOR LOCOMOTIVE/RAILCAR, MINING AND HEAVY EQUIPMENT MAINTENANCE.

- Modular design pump and cart separate from cylinder and base.
- Five tonnage capacity options 55-ton, 100-ton, 150-ton, 200-ton and 300-ton.
- Three collapsed height options 660, 838 and 1,143 mm.
- Two standard power options air (PA55) and electric (PE55).
- Two control options remote motor control and remote valve/motor control.
- Accessory options 168 mm extension, load-holding rings.
- Select the collapsed height to fit your most frequent application - add jacking modules to suit your needs.

- Remote operation for maximum operator safety and control - choose "motor only" or "motor and valve" control in the hand.
- Easy to maneuver large tires and small "footprint" make it easy to scoot into the tightest quarters, then locate the exact lifting position.
- Adjustable, heavy-duty handle makes this jack easy to move, position under vehicles. Can also be used to transport jack on site with a forklift.
- Load-holding rings (optional) provide full rated mechanical load-holding capability.
- Cylinder extension (optional) adds more versatility by extending your jack's reach.


- Low-temperature oil (optional) provides smooth, reliable operation in the coldest climate conditions.
- Modular design allows you to change lifting modules to suit your tonnage or height requirements. Use the pump module as a portable power station for your other double-acting cylinders (700 bar).
- Exclusive load-control system provides positive, chatter-free control when lowering the load.
- Shielded and sheltered hydraulic lines for safer, longer, trouble-free service.



# ORDER INFORMATION CRIBBING BLOCK SETS - INCLUDES ONE JACK MODULE EXTENSION

0 2 3	Order No.	55 Ton CBS55		100 Ton CBS100		150 Ton CBS150		200 Ton CBS200		
4	No. in Set	1	4	1	4	1	4	1	4	
	А	38,1	76,2	38,1	76,2	38,1	76,2	38,1	76,2	
	В	44,5	82,5	44,5	82,5	44,5	82,5	44,5	82,5	
	С	139,7	139,7	187,3	187,3	222,2	222,2	254	254	
-	Jack Module Ext.	17	173		177,8		168,3		168,3	
	Total Stack Ht.	tack Ht. 515,9		520,7		511,2		511,2		
Ī	Product Wt. (.kg)	16	5,3	30,9		38,6		47,6		






Convert jack module into stable mechanical

cribbing device.

 Increase retracted height up to 521 mm inches.

CBS300 (300 Ton): Consult Factory





	ORDER INFORMATION  JACK MODULE EXTENSIONS									
(Tons)	No.	A (mm)	B (mm)	C (mm)	D (mm)	E (in.)	F (mm)	G (mm)	H (mm)	Prod. Wt.
55	58945	223,8		127	66,8	1 <sup>11</sup> / <sub>16</sub> –8UN	63,5	66,8	92,2	9,5
100	58943	228,6	177,8	174,7	98,6	2 <sup>3</sup> / <sub>4</sub> –12UN	95,3	98,6	95,3	18,2
150	58944	219,2	168,4	203,2	114,3	31/4-8UNC	111,3	114,3	88,9	22,7

• Increases jack's reach. • Swivel cap (5° max.) provides more secure load holding.








#### Pump & cart modules (PM)

Pump and cart modules contain hydraulic pump, cart, remote control and all hoses and fittings required to connect to a jack module. Jack modules easily separate from the pump and cart module. Extra jack modules may be purchased for a wide variety of lifting applications.





	Remote Control							
Pump	Motor Only	Motor & Valve						
Air	PMA55	PMA55S						
Electric (110V)	PME55 <sup>†</sup>	PME55S <sup>†</sup>						
Electric (220V)	PME55-50-220 <sup>††</sup>	PME55S-50-220 <sup>††</sup>						
Air	PMA355	PMA355S						
Electric (220V)	PME355-50-220 <sup>††</sup>	PME355S-50-220 <sup>††</sup>						



<sup>††220</sup>V / 50Hz / 60Hz Single phase motor.



660 mm (26") **Jack Module** 



838 mm (33") **Jack Module** 




1,143 mm (45") Jack Module


#### Jack modules (JM)

Additional Jack Modules may be purchased for varying applications.

	Cylinder		ollapsed Heig	
Tonnage	Stroke (mm)	26" 660mm	33" 838mm	45" 1,143mm
55	333	JM25	JM35	JM45
100	333	JM210	JM310	JM410
150	460	JM215**	JM315	JM415
200	460	JM220*	JM320	JM420
300**	* 333	JM300*	JM330	JM430

- \* Collapsed height: 711 mm & Cylinder Stroke: 333 mm
- \*\* Cylinder Stroke 333 mm







* *	Must use PMx355x versions of pi	ump/cart modules above.

DIMENSIONS (MM)										
Model Series	A	В	C	D	E	F	G	н		
PMA & PME	1.464	752	1.353	762	872	594	*70°	406 mm		
* Total range with varying degree increments.										

ORDER INFORMATION - Pump and Cart Modules with Assembled Jack Module

		OKDEK HAFO	KWAIION - F	unip and G	art Modules Mith Weselliblen	Jack Mouul	E	
Capacity	Ret. Height	Ext. Height	Stroke	Pump	Power	Valve	Remote	Order
(tons)	(mm)	(mm)	(mm)	Type	Required	Туре	Control	No.
55	660,4	994	333	Electric	25 amps	Manual	M	JEM5526 <sup>†</sup>
100	838,2	1.172	333	Air	1,417 I/min. at 6 bar††	Manual	M	JAM10033
100	838,2	1.172	333	Air	1,417 I/min. at 6 bar††	Air Pilot	M & V	JAR10033
<b>150</b>	660,4	994	333	Electric	25 amps	Manual	M	JEM15026 <sup>†</sup>
150	838,2	1.172	333	Air	1,417 I/min. at 6 bar††	Manual	M	JAM15033
200	711	1.044	333	Electric	25 amps	Remote	M & V	JER20026 †
300	838,2	1.172	333	Air	1,417 I/min. at 6 bar††	Air Pilot	M & V	JAR30033

Different Modules Configuration available upon request.

<sup>†110</sup>V / 115V 60Hz Single phase motor. (220V / 50Hz / 60Hz Single phase motor upon request, please specify when ordering)

#### **POST TENSION**

& Stressing Jacks 20 & 30 Ton 700 bar (10,000 psi) max.



- · Power Team Monostrand Stressing Jacks are the most durable in the industry.
- Ideally suited for work on slab-ongrade where dirt, heat and high volume use take their toll.
- Available in single- or doubleacting models.
- Standard single-acting units have
- a 254 mm stroke. Other stroke lengths are available on special order.
- Dead-end seaters for production work and field work available on special order. (Part #400120)
- · Service repair is simple; components are long lasting and easily replaced.
- 76,2 mm detachable seater nose assembly easily replaced with optional 152,4 mm nose assembly.
- The jack of choice for high-rise and elevated work, thanks to fast return time and light weight.
- All hydraulic fluid controls are interior designed; more efficient
- and safer operation during tensioning and retraction.
- Standard double-acting units have an 216 mm stroke; others available on special order.
- Specially designed Power Team Control Valves are available for post tensioning jacks.

				ORDE	ERING INFORMATION	ON					
	Description	Cyl. Cap. Tons	Stroke	Order Number	Recommended Pumps for this Stressing Jack	Oil Capacity (I)	Strand Diameter (mm)	Seater Type	Effective Area (cm²)	Tons at 700 bar	Weight (kg)
	Post tension jack with spring seater,	20	254	SJ2010	PE554T/PE604T	0,72	11,1-12,7	Spring	28.85	20,3	25
	12,7 mm (0.50") strand. Post tension jack with power seater, 12,7 mm (0.50") strand.	20	254	SJ2010P	PE604PT	0,72	11,1-12,7	Power	28.85	20,3	25
	Double-acting post tension jack with	20	215	SJ2010DA	PE554PT/PE604PT	0,85	11,1-12,7	Power	28.85	23,9	19
	power seater, 12,7 mm (0.50") strand. Post tension jack with spring seater, 15,2 mm (0.60") strand.	30	254	SJ3010	PE554T/PE604T	1	11,1-15,2	Spring	40.54	28,5	34,5
	Post tension jack with power seater,	30	254	SJ3010P	PE604PT	1	11,1-15,2	Power	40.54	28,5	34,5
ACKS	15,2 mm (0.60") strand.  Double-acting post tension jack with power seater, 15,2 mm (0.60") strand.	30	215	SJ3010DA	PE554PT/PE604PT	1,1	11,1-15,2	Power	40.54	36,0	23,5





No. 9758 Hose - 3,1 m rubber, wire-braid (2-ply, 1,400 bar burst rating) 3/8" NPTF male hose ends No. 9763 Hose - 3,1 m rubber, wire-braid (2-ply, 1,400 bar burst rating) 3/8" x 1/4" NPTF male hose ends



# **MAINTENANCE SETS**

Hydraulic System Components

IM10H

IM10E-50-220



- **APPLICATION FLEXIBILITY**
- Matched hydraulic system components, adapters and hydraulic spreader, contained in a rugged carrying and storage case.
- Portable sets are ideal for pushing, pulling, lifting, straightening, or clamping at remote job sites.
- Cylinders in set are rated at 10 tons at 700 bar. Set components are designed for full rated capacity of cylinders.
- Set IM10H / IM10L includes hand operated pump.
- Set IM10E-50-220 includes the Quarter Horse® electrically driven portable power unit (220/230V, 50/60Hz, Single Phase).

		ORDERING I	NFORMATION			
Description	CONTENTS OF SET	Order No. IM10E-50-220	<b>Description</b> (	CONTENTS OF SET	Order No.	Order No. IM10L
Hydraulic spreader		HS2000	Hydraulic sprea	ader	HS2000	HS2000
Electric hydraulic po	ump	PE102-220	Hand pump		P59	P59L
700 bar hyd. gauge		9041	700 bar hyd. g	gauge	9041	9041
Tee adapter		9670	Tee adapter		9670	9670
Hose & coupler ass	embly	9754	Hose & couple	er assembly	9754	9754
90° V base		25395	90° V base		25395	25395
Threaded coupler		25664	Threaded coup	oler	25664	25664
Serrated saddle		31772	Serrated saddl	le	31772	31772
Flat base		32325	Flat base		32325	32325
Extension rod - 127	7mm length	350897	Extension rod	- 127mm length	350897	350897
Extension rod - 254	1 mmlength	38909	Extension rod	- 254mm length	38909	38909
Extension rod - 457	7 mm length	350898	Extension rod	- 457mm length	350898	350898
Cyl. support base		420062	Cyl. support ba	ase	420062	420062
Cyl. ass'y, 10 ton, 2	257 mm stroke	C1010CBT	Cyl. ass'y, 10	ton, 156mm stroke	C106CBT	C106CBT
Cyl. ass'y, 10 ton, 1	156 mm stroke	C106CBT	Storage box*		350722	350722
Storage box*		350722			Prod. Weight	Prod. Weight
	Prod. Weight – 48,1 kg.		I		40,4 kg.	36,8 kg.

<sup>\*</sup> Actual product may differ from photo.



### INFLATABLE JACKS


1 to 74 Ton 8 bar (116 psi) Max. Air Pressure

#### **BE SAFE!**

- •INSPECT BEFORE AND AFTER EACH USE.
- REPLACE IF ANY SIGNS OF DEGRADATION OR WEAR THAT MAY AFFECT SAFETY OR PERFORMANCE.
- •KEEP THE PRODUCT CLEAN.
- STORE PROPERLY.

- Highly flexible and lightweight jacks only require an air supply of 8 bar maximum. Any non-explosive gas or water can also be used for inflation.
- Uninflated jacks are only 25,4 mm thick, making seemingly impossible lifting tasks routine.
- Space age reinforced, multi-layer aramid construction, widely overlapping on all sides.
   Tested at 12 bar.
- In rugged testing, jacks withstood tens of thousands of inflate/deflate cycles at 8 bar.
- Large surface area and material flexibility allow jacks to lift loads on soft or compressible surfaces without support cribbing being necessary.

- Safety first! The controller, shut-off and air hoses are all equipped with USA industrial interchange style air couplers. Female half coupler bodies have a locking collar, protecting operator from accidentally disconnecting jack while under load.
- Surface of jack has a non-skid pattern, assuring that the jack won't "walk away" from the job. Jacks can be used to lift a load from an uneven surface, are tolerant of side-loaded applications.
- Non-conducting material resists oil, ozone and most chemicals. Cold resistant down to -4° C, heat resistant up to 115°C(short term) or 93°C(long term).
- Field-replaceable nipples are made of tough steel, with internal thread to prevent abrasion damage. Ideal needle aperture of 6,4 mm allows rapid inflation, without risk of icing, and permits a safe lowering speed.
- Single jack controller with "dead man" control (350090). Can be used individually, or in multiples to regulate any number of jacks desired.
- Heavy attachment straps are provided on 4 largest sizes for attachment of a rope or hook to position the jack from a safe distance.
- Inflation hose system is color-coded (red and yellow) for easy recognition when using more than one jack.



#### **Maximum Effective Lifting Area**


All lifting capacities mentioned in the charts are measured at the maximum effective lifting area (A). As the jack is inflated (B), this effective area decreases (C) due to the rounded shape of the jack.Lifting capacity also decreases (see performance chart).



Stack up to two jacks together to increase effective lifting height.



The non-skid space age reinforced inflatable jack is perfect for many applications.









No. 307159 – Pressure reducing valve. Allows use of bottled gases to operate jacks (works on CGA-580 Nitrogen/Argon/Helium bottles). Contains standard bottle fitting on inlet and 1/4" industrial interchange (female) outlet. Wt., 1,8 kg.

No. 350090 – Air controller for single jack. Equipped with relief valve and pressure gauge.

**No. 350207** – Shut-off hose with shut-off valve and pressure relief valve. Includes a female and male quick coupler.

No. 350208 – Air hose. Red, 9,2 m long. Includes No. 250341 female and No. 250342 male quick coupler.

No. 350209 - Air hose. Same as 350208, except blue in color.

**No. 250343** – Female quick coupler. 1/4" industrial interchange x 1/8" NPT female. Wt.,0,1kg.

**No.** 250353 – Male quick coupler. 1/4" industrial interchange x 1/8" NPT male. Wt., 0.1 kg.


**No.** 250682 – Female quick coupler. 1/4" industrial interchange x 1/4" NPT male. Wt., 0.1 kg.

**No. 15235** – Connector 1/8" NPT male x 1/4" NPT female. Wt., 0.1 kg


No. 250341 – Female quick coupler. 1/4" industrial x 9,5 mm I.D. hose.

No. 250342 - Male Quick coupler. 9,5 mm I.D. Hose.

**NOTE:** Should compressed air is used to inflate a jack, use an external pressure regulator/filter if the pressure will to exceed 8 bar and when the air has water &/or contamination.



# 





# HYDRAULIC & MECHANICAL TOOLS



...107-111 TORQUE WRENCHES



Page ...120 PORTABLE PUNCHES



112-114... ECTRIC HYDRAULIC TORQUE WRENCH PUMPS



SPREADERS...121

1 and  $1^{1}/_{2}$  Ton



Page 114-117... AIR HYDRAULIC TORQUE WRENCH PUMPS



BEAD BREAKERS. 122

Tire Removing Tool



NUT SPLITTERS...118

15 and 25 Ton



C CLAMPS...123





...119
PIPE FLANGE
SPREADERS
5 and 10 Ton



TESTERS...124, 125

Page



...126, 127 MECHANICAL TOOLS







# MEASUREMENTS/ SPECIFICATIONS

Torque Wrench Selection Guide

#### **TORQUE WRENCH SELECTION GUIDE**

#### TOOL GUIDELINE

BOLT - TORQUE						RECOMMENDED MODEL				
SAE1 SAE 2 30,000 PSI	ASTM 193 B7 BOLT	8-7 A/F HEAVY HEX NUT	ASTM 354 B8 60000 PSI	FT. LBS.	Nm	SQUARE DRIVE MAKE-UP ONLY	LOW Clearance Make-UP	SQUARE DRIVE Break Out	LOW CLEARANCE Break Out	
1"	7/8"	1-7/16"		300	408	TWSD1	TWLC2	TWSD1	TWLC2	
1-1/8"	1"	1-5/8"	7/8"	425	578	TWSD1	TWLC2	TWSD1	TWLC2	
				500	680	TWSD1	TWLC2	TWSD1	TWLC2	
1-1/4"			1"	600	816	TWSD1	TWLC2	TWSD1	TWLC2	
1-3/8"	1-1/8"	1-13/16"		700	952	TWSD1	TWLC2	TWSD1	TWLC2	
/ -	1-1/4"	2"	1-1/8"	800	1.088	TWSD1	TWLC2	TWSD3	TWLC4	
1-1/2"	<u> </u>		ĺ	900	1,224	TWSD1	TWLC2	TW\$D3	TWLC4	
,				1,000	1,360	TWSD1	TWLC2	TWSD3	TWLC4	
1-5/8"	1-3/8"	2-3/16"	1-1/4"	1.250	1.700	TWSD1	TWLC2	TWSD3	TWLC4	
,	· ·	,	1	1,350	1.836	TWSD1	TWLC2	TWSD3	TWLC4	
	1-1/2"	2-3/8"	1-3/8"	1,500	2.040	TWSD3	TWLC2	TWSD3	TWLC4	
1-3/4"	'	,	1	1,600	2.176	TWSD3	TWLC4	TWSD6	TWLC4	
1-7/8"				1,800	2,448	TWSD3	TWLC4	TWSD6	TWLC4	
,	1-5/8"	2-9/16"		2,000	2,720	TWSD3	TWLC4	TWSD6	TWLC4	
2"	<u> </u>	ĺ		2,200	2,992	TWSD3	TWLC4	TWSD6	TWLC8	
	1-3/4"	2-3/4"	1-5/8"	2,600	3,536	TWSD3	TWLC4	TWSD6	TWLC8	
2-1/4"				3,000	4.080	TWSD3	TWLC4	TWSD6	TWLC8	
,	1-7/8"	2-15/16"	1-3/4"	3,700	5,032	TWSD6	TWLC4	TWSD11	TWLC8	
2-1/2	2"	3-1/8"	ĺ	4,000	5,440	TWSD6	TWLC8	TWSD11	TWLC15	
,,		,	1-7/8	4,400	5,984	TWSD6	TWLC8	TWSD11	TWLC15	
2-3/4"			2"	5,100	6,936	TWSD6	TWLC8	TWSD11	TWLC15	
,	2-1/4"	3-1/2"		6,000	8,160	TWSD6	TWLC8	TWSD25	TWLC15	
3"	İ	3-7/8"	2-1/4"	7,000	9,520	TW\$D11	TWLC8	TWSD25	TWLC15	
	2-1/2"	,	<b>'</b>	8,000	10,880	TWSD11	TWLC15	TWSD25	TWLC30	
3-1/4"	İ			9,000	12,240	TWSD11	TWLC15	TW\$D25	TWLC30	
3-1/2"	2-3/4"	4-1/4"	2-1/2"	10,000	13,600	TWSD11	TWLC15	TWSD25	TWLC30	
,	İ	ĺ	,	11,500	15,640	TWSD25	TWLC15	TWSD25	TWLC30	
3-3/4"	3"	4-5/8"	2-3/4"	13,000	17680.	TWSD25	TWLC15	Please Inquire	TWLC30	
4"		ĺ	ĺ í	14,500	19,720	TWSD25	TWLC15	Please Inquire		
				15,500	21.080	TWSD25	TWLC30	Please Inquire		
	3-1/4"	5"	3"	16,500	22,440	TWSD25	TWLC30	Please Inquire		
4-1/4"	· ·			19,500	26,520	TWSD25	TWLC30	Please Inquire		
	3-1/2"	5-3/8"	3-1/4"	20,500	27,880	TWSD25	TWLC30	Please Inquire:		
4-1/2"	<b>'</b>	<b>'</b>	<b>'</b>	21,500	29,240	TWSD25	TWLC30	For		
•				24,500	33,320	TWSD25	TWLC30	Higher		
4-3/4"	3-3/4"	5-3/4"	3-1/2"	25,500	34,680	Please Inquire	TWLC30	Torque		
6-1/2"	4-1/4"			29,500	40,120	Please Inquire	Please Inquire	Values		



# **TORQUE WRENCH**

Square Drive TWSD Series 33,496 Nm Max Torque 700 bar (10,000 psi)

> **HEAVY DUTY SIMPLE-TO-USE.** ACCURACY AND SPEED UNDER LOAD. **BREAKING NUTS LOOSE AND TORQUING**



- Low Weight, High Strength Design
- Superior Torsional Strength
- Fast Operation Cycle

**TORQUE WRENCHES** 

- Fine Tooth Pawl
- Floating Piston Design
- Internal Swivel Manifold Relief
- Rigid Steel Body Construction
- Compact Frame Size





**TWSD Series** 



360° Reaction Arm

Tool is shipped with standard reaction arm as shown.


- · Push Button Reversal of Square Drive
- Corrosion Resistant Finish
- 360° Reaction Arm
- Push to Click Reaction Arms
- Multi-Axis High Flow Swivel Manifold
- Simple Design
- Consistent Torque Output
- Fully Enclosed Drive Mechanism
- Accurate Torque Output
- Marathon Lifetime Warranty



**Extended** Reaction Arm (Optional)

TWSD1-ERA TWSD3-ERA **TWSD6-ERA** TWSD11-ERA TWSD25-ERA







**TWSD1-LRA TWSD3-LRA TWSD6-LRA** TWSD11-LRA TWSD25-LRA



Cut length on request



1001	LI	LZ	L3	LIT	K	WZ	AA T	
Model	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	
TWSD1	139	170	112	146	29	87	34	
TWSD3	169	196	124	176	39	105	45	
TWSD6	195	237	142	206	46	136	51	
TWSD11	234	292	179	242	55	165	61	
TWSD25	306	375	231	314	72	200	77	

Tool Model	Square I	Drive	Max.	Torque	Tool Weight
(TWSD Series)	mm	(in_)	Nm	(ft. lbs.)	kg
TWSD1	19.0	3/4	1,880	1,390	2.3
TWSD3	25.4	1	4,160	3,070	4.5
TWSD6	38.1	1-1/2	8,157	6,020	7.9
TWSD11	38.1	1-1/2	14,823	10,940	13.1
TWSD25	63.5	2-1/2	33,496	24,700	29.5



TWHC Series High Cycle Hydraulic Square Drive Torque Wrench available (Consult factory or refer www.spxboltingsystems.com)



**HEX DRIVES (Allen Drives)** 

Table for maximum recommended torque values for Hexagon Drives available upon request (Consult factory)

HEY DILLARS	LAIIGII DIIVES			
Torque Wrench	Hexagon Drive Size A/F (in.)	Part No.	Hexagon Drive Size A/F (mm)	Part No.
TWSD1	5/8"	TWD1-063	17mm	TWD1-017
	3/4"	TWD1-075	19mm	TWD1-019
	7/8"	TWD1-088	22mm	TWD1-022
	1"	TWD1-100	24mm	TWD1-024
	-	-	27mm	TWD1-027
TWSD3	5/8"	TWD3-063	17mm	TWD3-017
	3/4"	TWD3-075	19mm	TWD3-019
	7/8"	TWD3-088	22mm	TWD3-022
	1"	TWD3-100	24mm	TWD3-024
	1-1/8"	TWD3-113	27mm	TWD3-027
	1-1/4"	TWD3-125	30mm	TWD3-030
	1-3/8"	TWD3-138	32mm	TWD3-032
TWSD6	7/8"	TWD6-088	22mm	TWD6-022
	1"	TWD6-100	24mm	TWD6-024
	1-1/8"	TWD6-113	27mm	TWD6-027
	1-1/4"	TWD6-125	30mm	TWD6-030
	1-3/8"	TWD6-138	32mm	TWD6-032
	1-1/2"	TWD6-150	36mm	TWD6-036
	1-5/8"	TWD6-163	41mm	TWD6-041
TWSD11	1-1/8"	TWD11-113	27mm	TWD11-027
	1-1/4"	TWD11-125	30mm	TWD11-030
	1-3/8"	TWD11-138	32mm	TWD11-032
	1-1/2"	TWD11-150	36mm	TWD11-036
	1-5/8"	TWD11-163	41mm	TWD11-041
	1-3/4"	TWD11-175	46mm	TWD11-046
TWSD25	1-1/2"	TWD25-150	36mm	TWD25-036
	1-5/8"	TWD25-163	41mm	TWD25-041
	1-3/4"	TWD25-175	46mm	TWD25-046
	1-7/8"	TWD25-188	50mm	TWD25-050
	2"	TWD25-200	55mm	TWD25-055
	2-1/4"	TWD25-225	60mm	TWD25-060
	2-1/2"	TWD25-250	65mm	TWD25-065
	2-3/4"	TWD25-275	70mm	TWD25-070


**Heavy-duty Square Drive Impact Sockets** 

5-3/4

6-1/8

# **SOCKETS & HEXAGON DRIVES**

for TWSD Series Square Drive Torque Wrenches



Reaction Pad (Optional)	Reaction P L1 (mm)	ads for He		WIDTH (mm)
TWSD1-RP	71.5	115.5	43.5	63.0
TWSD3-RP	83.0	135.0	48.0	74.0
TWSD6-RP	91.0	154.0	57.0	90.0
TWSD11-RP	109.0	184.0	65.5	105.0
TWSD25-RP	135.0	242.0	88.5	143.0





2-1/2" Drive Part No.

TWSMF150

TWSMF155

**Reaction Pad** Sockets

Socket Size A/F (in.)	3/4" Drive Part No.	1" Drive Part No.	1-1/2" Drive Part No.	2-1/2" Drive Part No.	Socket Size A/F (mm)	3/4" Drive Part No.	1" Drive Part No.	1-1/2" Drive Part No.	2-1/2" Drive Part No.
7/8	TWSIA088	TWSIB088	-	-	22 <b>T</b>	WSMA022	TWSMB022	-	_
1-1/16	TWSIA106	TWSIB106	-	-	24 <b>T</b>	WSMA024	TWSMB024	-	-
1-1/4	TWSIA125	TWSIB125	-	-	32 <b>T</b>	WSMA032	TWSMB032	TWSMC032	-
1-3/8	TWSIA138	TWSIB138	-	-	36 T	WSMA036	TWSMB036	TWSMC036	-
1-7/16	TWSIA144	TWSIB144	-	-	41 T	WSMA041	TWSMB041	TWSMC041	-
1-5/8	TWSIA163	TWSIB163	TWSIC163	-	46 <b>T</b>	WSMA046	TWSMB046	TWSMC046	-
1-13/16	TWSIA181	TWSIB181	-	<u> </u>	50 <b>T</b>	WSMA050	TWSMB050	TWSMC050	TWSMF050
2	TWSIA200	TWSIB200	TWSIC200	<u> </u>	55 <b>T</b>	WSMA055	TWSMB055	TWSMC055	TWSMF055
2-3/16	TWSIA219	TWSIB219	TWSIC219	-	60 <b>T</b>	WSMA060	TWSMB060	TWSMC060	TWSMF060
2-3/8	TWSIA238	TWSIB238	TWSIC238	-	65	-	TWSMB065	TWSMC065	TWSMF065
2-9/16	-	TWSIB256	TWSIC256	-	70	-	TWSMB070	TWSMC070	TWSMF070
2-3/4	-	TWSIB275	TWSIC275	-	75	-	TWSMB075	TWSMC075	TWSMF075
2-15/16	-	TWSIB294	TWSIC294	-	80	-	TWSMB080	TWSMC080	TWSMF080
3-1/8	-	TWSIB313	TWSIC313	TWSIF313	85	-	TWSMB085	TWSMC085	TWSMF085
3-3/8	-	TWSIB338	TWSIC338	TWSIF338	90	-	TWSMB090	TWSMC090	TWSMF090
3-1/2	-	TWSIB350	TWSIC350	TWSIF350	95	-	TWSMB095	TWSMC095	TWSMF095
3-3/4	-	TWSIB375	TWSIC375	TWSIF375	100	-	TWSMB100	TWSMC100	TWSMF100
3-7/8	-	TWSIB388	-	TWSIF388	110	-	TWSMB110	TWSMC110	TWSMF110
4-1/8	-	TWSIB413	TWSIC413	TWSIF413	115	-	-	TWSMC115	TWSMF115
4-1/4	-	TWSIB425	TWSIC425	TWSIF425	120	-	-	TWSMC120	TWSMF120
4-5/8	-	-	TWSIC463	TWSIF463	130	-	-	-	TWSMF130
5	-	-	-	TWSIF500	135	-	-	-	TWSMF135
5-3/8	-	-	-	TWSIF538	145	-	-	-	TWSMF145

TWSIF575

TWSIF613

150

155



# **TORQUE WRENCH**

Low Clearance TWLC Series 39,024 Nm Max Torque 700 bar (10,000 psi)



#### HYDRAULIC LOW CLEARANCE **TORQUE WRENCHES**

The TWLC Wrench was designed for the most inaccessible bolting areas found in industry. Its long neck, short height and small radius have all added to its great success

- Low Weight, High Strength Design
- Superior Torsional Strength
- Fast Operation Cycle
- Fine Tooth Pawl
- Floating Piston Design
- Auto-Connect Drive Piston
- Compact Frame Size
- Rigid Steel Body Construction
- Internal Swivel Manifold Relief

- Built-in Reaction Pad
- Small Nose Radius
- Tool Free Link Change
- · Corrosion Resistant Finish
- Multi-Axis High Flow Swivel Manifold

TOPSIDE

SUB-SEA


APPLICATION

RIGID LIGHTWEIGHT

**ALL-STEEL** 

**BODY** 

- Simple Design
- Consistent Torque Output
- Marathon Lifetime Warranty



\* Links sold separately.

Tool is not shipped with link.


THE LIGHTWEIGHT, HEAVY-DUTY




**TWLC Series** 













\* Cut length on request





Tool Model		ink nge (A/F)		Max	. Torque	Tool Weight (with Link)
(Hydraulic Unit)	mm	(in.)		Nm	(ft₌ lbs)	kg
TWLC2	32 – 60	11/4 - 23/8	2	2,134	1,575	2.8
TWLC4	40 – 80	11/2 - 31/8	5	,386	3,975	5.7
TWLC8	60 – 100	23/8 – 37/8	10	0,773	7,950	10.4
TWLC15	65 – 120	29/16 – 45/8	20	0,221	14,850	16.9
TWLC30	80 – 155	31/8 - 61/8	39	9,024	28,800	35.0



**Hydraulic Unit (TWLC)** 



# Hydraulic Unit (TWLC)

Hydraulic Unit

Link (TWL) (Sold Separately)

# **LINKS & REDUCERS**

for TWLC Series Low Clearance
Torque Wrenches

AVAILABLE IN THE MOST COMMON SIZES. CUSTOM SIZES AVAILABLE (CONSULT FACTORY).


B							1						
		25	No.										
						A			-			-	
Tool	Link	Nut /		Nose Radius	Small	Reducer	Don't Ma	to the	Reducer	Don't Ma	to de	Reducer	Down No.
	Part No. TWL2-032	inch 1-1/4"	mm 32	(mm) 32	inch	mm	Part No.	inch	mm	Part No.	inch	mm	Part No.
	TWL2-036	1-7/16"	36	32	_	_	-	<u>-</u>			_	_	
2	TWL2-041	1-5/8"	41	35	1-5/8"-1-7/16"	41-36mm	TWR2-041036	1-5/8"-1-1/4"	41-32mm	TWR2-041032	_	-	
TWLC2	TWL2-046	1-13/16"	46	37	1-13/16"-1-5/8"	46-41mm	TWR2-046041	1-13/16"-1 <i>-7</i> /16"	46-36mm	TWR2-046036	1-13/16"-1-1/4"	46-32mm	TWR2-046032
≥	TWL2-050	2"	50	40	2"-1-13/16"	50-46mm	TWR2-050046	2"-1-5/8"	50-41mm	TWR2-050041	2"-1-7/16"	50-36mm	TWR2-050036
	TWL2-055	2-3/16"	55	43	2-3/16"-2"	55-50mm	TWR2-055050	2-3/16"-1-13/16"	55-46mm	TWR2-055046	2-3/16"-1-5/8"	55-41mm	TWR2-055041
	TWL2-060	2-3/8"	60	46	2-3/8"-2-3/16"	60-55mm	TWR2-060055	2-3/8"-2"	60-50mm	TWR2-060050	2-3/8"-1-13/16"	60-46mm	TWR2-060046
	TWL4-041	1-5/8"	41	37	1-5/8"-1-7/16"	41-36mm	TWR4-041036	1-5/8"-1-1/4"	41-32mm	TWR4-041032	-	-	
	TWL4-046	1-13/16"	46	39	1-13/16"-1-5/8"	46-41mm	TWR4-046041	1-13/16"-1 <i>-7</i> /16"	46-36mm	TWR4-046036	1-13/16"-1-1/4"	46-32mm	TWR4-046032
	TWL4-050	2"	50	42	2"-1-13/16"	50-46mm	TWR4-050046	2"-1-5/8"	50-41mm	TWR4-050041	2"-1-7/16"	50-36mm	TWR4-050036
TWLC4	TWL4-055	2-3/16"	55	45	2-3/16"-2"	55-50mm	TWR4-055050	2-3/16"-1-13/16"	55-46mm	TWR4-055046	2-3/16"-1-5/8"	55-41mm	TWR4-055041
≶	TWL4-060	2-3/8" 2-9/16"	60	48	2-3/8"-2-3/16"	60-55mm	TWR4-060055	2-3/8"-2"	60-50mm	TWR4-060050	2-3/8"-1-13/16"	60-46mm	TWR4-060046
-	TWL4-065 TWL4-070	2-9/10" 2-3/4"	65 70	50 53	2-9/16"-2-3/8" 2-3/4"-2-9/16"	65-60mm 70-65mm	TWR4-065060 TWR4-070065	2-9/16"-2-3/16" 2-3/4"-2-3/8"	65-55mm 70-60mm	TWR4-065055 TWR4-070060	2-9/16"-2" 2-3/4"-2-3-16"	65-50mm 70-55mm	TWR4-065050 TWR4-070055
	TWL4-075	2-3/4 2-15/16"	75	56	2-3/4 -2-7/10	75-70mm	TWR4-075070	2-15/16"-2-9/16"	75-65mm	TWR4-075065	2-15/16"-2-3/8"	75-60mm	TWR4-075060
	TWL4-080	3-1/8"	80	59	3-1/8"-2-15/16"	80-75mm	TWR4-080075	3-1/8"-2-3/4"	80-70mm	TWR4-080070	3-1/8"-2-9/16"	80-65mm	TWR4-080065
	TWL8-060	2-3/8"	60	51	2-3/8"-2-3/16"	60-55mm	TWR8-060055	2-3/8"-2"	60-50mm	TWR8-060050	2-3/8"-1-13/16"	60-46mm	TWR8-060046
	TWL8-065	2-9/16"	65	53	2-9/16"-2-3/8"	65-60mm	TWR8-065060	2-9/16"-2-3/16"	65-55mm	TWR8-065055	2-9/16"-2"	65-50mm	TWR8-065050
	TWL8-070	2-3/4"	70	56	2-3/4"-2-9/16"	70-65mm	TWR8-070065	2-3/4"-2-3/8"	70-60mm	TWR8-070060	2-3/4"-2-3-16"	70-55mm	TWR8-070055
%	TWL8-075	2-15/16"	75	59	2-15/16"-2-3/4"	75-70mm	TWR8-075070	2-15/16"-2-9/16"	75-65mm	TWR8-075065	2-15/16"-2-3/8"	75-60mm	TWR8-075060
TWLC8	TWL8-080	3-1/8"	80	62	3-1/8"-2-15/16"	80-75mm	TWR8-080075	3-1/8"-2-3/4"	80-70mm	TWR8-080070	3-1/8"-2-9/16"	80-65mm	TWR8-080065
≥	TWL8-085	3-3/8"	85	67	3-3/8"-3-1/8"	85-80mm	TWR8-085080	3-3/8"-2-15/16"	85-65mm	TWR8-085065	3-3/8"-2-3/4"	85-70mm	TWR8-085070
	TWL8-090	3-1/2"	90	67	3-1/2"-3-3/8"	90-85mm	TWR8-090085	3-1/2"-3-1/8"	90-80mm	TWR8-090080	3-1/2"-2-15/16"	90 <b>-</b> 75mm	TWR8-090075
	TWL8-095	3-3/4"	95	74	3-3/4"-3-1/2"	95-90mm	TWR8-095090	3-3/4"-3-3/8"	95-85mm	TWR8-095085	3-3/4"-3-1/8"	95-80mm	TWR8-095080
	TWL8-100	3-7/8"	100	74	3-7/8"-3-3/4"	100-95mm	TWR8-100095	3-7/8"-3-1/2"	100-90mm	TWR8-100090	3-7/8"-3-3/8"	100-85mm	TWR8-100085
	TWL15-070	2-3/4"	70	61	2-3/4"-2-9/16"	70-65mm	TWR15-070065	2-3/4"-2-3/8"	70-60mm	TWR15-070060	2-3/4"-2-3-16"	70-55mm	TWR15-070055
	TWL15-075 TWL15-080	2-15/16"	75 90	63 47	2-15/16"-2-3/4"	75-70mm	TWR15-075070	2-15/16"-2-9/16"	75-65mm	TWR15-075065	2-15/16"-2-3/8"	75-60mm	TWR15-075060
	TWL15-080	3-1/8" 3-3/8"	80 85	67 72	3-1/8"-2-15/16" 3-3/8"-3-1/8"	80-75mm 85-80mm	TWR15-080075 TWR15-085080	3-1/8"-2-3/4" 3-3/8"-2-15/16"	80-70mm 85-65mm	TWR15-080070 TWR15-085065	3-1/8"-2-9/16" 3-3/8"-2-3/4"	80-65mm 85-70mm	TWR15-080065 TWR15-085070
	TWL15-090	3-1/2"	90	72	3-1/2"-3-3/8"	90-85mm	TWR15-090085	3-1/2"-3-1/8"	90-80mm	TWR15-090080	3-1/2"-2-15/16"	90-75mm	TWR15-090075
133	TWL15-095	3-3/4"	95	78	3-3/4"-3-1/2"	95-90mm	TWR15-095090	3-3/4"-3-3/8"	95-85mm	TWR15-095085	3-3/4"-3-1/8"	95-80mm	TWR15-095080
TWICI	TWL15-100	3-7/8"	100	78	3-7/8"-3-3/4"	100-95mm	TWR15-100095	3-7/8"-3-1/2"	100-90mm	TWR15-100090	3-7/8"-3-3/8"	100-85mm	TWR15-100085
2	TWL15-105	-	105	83	-	105-100mm	TWR15-105100	-	105-95mm	TWR15-105095	-	105-90mm	TWR15-105090
	TWL15-425	4-1/4"	-	83	4-1/4"-3-7/8"	-	TWR15-425388	4-1/4"-3-3/4"	-	TWR15-425375	4-1/4"-3-1/2"	-	TWR15-425350
	TWL15-110	-	110	87	-	110-105mm	TWR15-110105	-	110-100mm	TWR15-110100	-	110-95mm	TWR15-110095
	TWL15-115	-	115	87	-	115-110mm	TWR15-115110	-	115-105mm	TWR15-115105	-	115-100mm	TWR15-115100
	TWL15-463	4-5/8"	-	87	4-5/8"-4-1/4"	-	TWR15-463425	4-5/8"-3-7/8"	-	TWR15-463388	4-5/8"-3-3/4"	-	TWR15-463375
	TWL30-080	3-1/8"	80	77	3-1/8"-2-15/16"	80-75mm	TWR30-080075	3-1/8"-2-3/4"	80-70mm	TWR30-080070	3-1/8"-2-9/16"	80-65mm	TWR30-080065
	TWL30-085	3-3/8"	85	77	3-3/8"-3-1/8"	85-80mm	TWR30-085080	3-3/8"-2-15/16"	85-65mm	TWR30-085065	3-3/8"-2-3/4"	85-70mm	TWR30-085070
1	TWL30-090	3-1/2"	90	77	3-1/2"-3-3/8"	90-85mm	TWR30-090085	3-1/2"-3-1/8"	90-80mm	TWR30-090080	3-1/2"-2-15/16"	90-75mm	TWR30-090075
	TWL30-095	3-3/4"	95	83	3-3/4"-3-1/2"	95-90mm	TWR30-095090	3-3/4"-3-3/8"	95-85mm	TWR30-095085	3-3/4"-3-1/8"	95-80mm	TWR30-095080
	TWL30-100 TWL30-105	3-7/8"	100 105	83 88	3-7/8"-3-3/4"	100-95mm	TWR30-100095 TWR30-105100	3-7/8"-3-1/2"	100-90mm 105-95mm	TWR30-100090 TWR30-105095	3-7/8"-3-3/8"	100-85mm 105-90mm	TWR30-100085 TWR30-105090
1	TWL30-105	4-1/4"	-	88	4-1/4"-3-7/8"	- -	TWR30-425388	4-1/4"-3-3/4"	103-95mm -	TWR30-103075	4-1/4"-3-1/2"	- -	TWR30-103090
0	TWL30-110	4-1/4	110	88	4-1/4 -3-7/6 -		TWR30-110105			TWR30-110100	4-1/4 -3-1/2		TWR30-110095
TWLC30	TWL30-115	-	115	92	-		TWR30-115110	_		TWR30-115105	-		TWR30-115100
₹	TWL30-463	4-5/8"	-	92	4-5/8"-4-1/4"	-	TWR30-463425	4-5/8"-3-7/8"	-	TWR30-463388	4-5/8"-3-3/4"	-	TWR30-463375
-	TWL30-120		120	99	-		TWR30-120115	-		TWR30-120110	-	120-105mm	TWR30-120105
1	TWL30-500	5"	-	99	5"-4-5/8"	-	TWR30-500463	5"-4-1/4"	-	TWR30-500425	5"-3-7/8"	-	TWR30-500388
1	TWL30-130	-	130	105	-	130-120mm	TWR30-130120	-	130-115mm	TWR30-130115	<del>-</del>	130-110mm	TWR30-130110
1	TWL30-135	5-3/8"	135	105	5-3/8"-5"	135-125mm	TWR30-135125	5-3/8"-4-5/8"	135-120mm	TWR30-135120	5-3/8"-4-1/4"	135-115mm	TWR30-135115
1	TWL30-145	5-3/4"	145	110									
1	TWL30-150	-	150	116			Α\	'AILABLE	UPON	1 REQUE	ST		
	TWL30-155	6-1/8"	155	116									

# **COMPACT TORQUE WRENCH PUMP**

Hydraulic/Electric PE39 Series 0.64 I/min, 0.97 kW 700 bar (10,000 psi)

A CAUTION: This system should not be used for lifting applications.

#### **Typical Flow Curve:**







Also suitable for Wind Power Applications

#### **COMPACT TOROUE WRENCH PUMP**

The SPX PE39 is compact and capable of being used in a vertical or horizontal orientation. It is based on proven pump design for reliability in rugged torque wrench applications to support operation and maintenance requirements.

#### **Quality means Lower Life-Cycle Costs:**

- Over 100,000 cycles
- Continuous duty up to 50°C (122°F) ambient (optional cooling kit)
- Proven design: Proven reliability

#### **Enhanced Usability:**

- VERTICAL or HORIZONTAL operation
- Light weight and portable
- Removable control pendant (5 m cord)
- Removable 100mm (4") calibration capable gauge
- 0.97 kW (1.3 hp) Universal Motor for reduced voltage applications (up to -20% nominal voltage)
- 4-way valve (not for lifting applications)
- Fits through 420mm opening

#### **Designed with Safety in Mind:**

- Easily adjusted pressure regulator (relief) valve
- Fixed 103 Bar (1500 psi) pressure retract relief valve

#### **Operating Environment:**

Temperature: -25°C to +50°C (-13°F to 122°F) (If temperatures are at extremes of the operating range, it is recommended to use hydraulic oils that are rated for those temperatures. Refer to service manuals and cooling options)

Order No.	Cooling Option*	Electric Motor (Single Phase)	Manifold	Max. Pressure Output	Oil Delivery	Oil Reservoii (l)		Overall Width (mm)	Overall Length (mm)		Pump Weight w/Oil (kg)
PE39YED1PR PE39YED1BPR	No Yes	110/115 VAC 50/60 Hz (14.5 amps)	Single	700 bar	3.7 I/min. to	1.89	1.51	274	350	600	19.5
PE39PED1PR PE39PED1BPR	No Yes	220/230 VAC 50/60 Hz (7.2 amps)	Tool	700 bai	0.64 I/min.		1.01	214	330	000	19.5

<sup>\*</sup> Auxiliary cooling fan (field installable), Part # 3000610.

Non-vented reservoir.

Sound level: 87-92 dB

#### NON-CONDUCTIVE HOSE (700 BAR) for TWSD or TWLC or TWHC Series Torque Wrench)

- For applications requiring electrical isolation.
- Quick Couplers & Plugs 1/4" fitting on both ends
- Leakage factor of less than 50 microampere.
- · Orange polyurethane for easy identification.
- Covering is not perforated, preventing moisture from entering the hose and affecting its overall conductivity.
- Maximum operating pressure: 700 bar (10,000 psi)
- Hoses feature a minimum 2,800 bar (40,000 psi) burst pressure.



**HOSES - DUAL LINE** 

4.6m, 6.4mm ID non-conductive 6.1m, 6.4mm ID non-conductive 15.2m, 6.4mm ID non-conductive



- INSPECT BEFORE AND AFTER EACH USE.
- REPLACE IF ANY SIGNS OF DEGRADATION **OR WEAR THAT MAY AFFECT SAFETY** OR PERFORMANCE.
- KEEP THE PRODUCT CLEAN.
- STORE PROPERLY.

Order No.	Couplers / Fittings	Metal Dust Cap
251410	Quick Coupler, Female Half, 1/4" NPTF Male	252364
251411	Quick Plug, Male Half, 1/4" NPTF Female	252365
12740	Coupling, 1/4" NPTF Female Both Ends	
10672	Straight Fitting, 1/4" NPTF Male Both Ends	



# VANGUARD® ELECTRIC HYDRAULIC TORQUE WRENCH PUMPS

- Light weight and portable
- Two-speed high performance pump (similar to PE55 Series)
- 0.84 kW (1 <sup>1</sup>/<sub>8</sub> hp), 12,000 rpm universal motor starts under full load and at reduced voltage
- External adjustable pressure regulator
- Retract side internal relief valve protects tool
- · Hand remote standard
- Use for double or single acting tools

POWER TEAM

PE55TWP-220

 Four-tool manifold (-4 model only) allows use of up to four tools simultaneously



**PE55TWP-220-CF** (with Oil Cooling Fan)



TORQUE WRENCH PUMP

Hydraulic/Electric

PE55 Series

0.9 I/min, 0.84 kW

700 bar (10,000 psi)

PE55TWP-4-220

**CAUTION:** This system should not be used for lifting applications.

Order No.	Manifold	Oil Delivery	Oil Reservoir (l)	Usable Oil (I)	Overall Width (mm)	Overall Length (mm)	Overall Height (mm)	Pump Weight w/Oil (kg)
PE55TWP PE55TWP-220	Single Tool	7.6 I/min @ 0 bar 0.9 I/min @ 700 bar	9.5	8.6	435	241	460	34
PE55TWP-4 PE55TWP-4-220	4 Tool	7.6 I/min @ 0 bar 0.9 I/min @ 700 bar	9.5	8.6	469	241	486	35
PE55TWP-CF PE55TWP-220-CF	Single Tool	Similar to PE55TWP bu Similar to PE55TWP-22		_	469	292	486	37
				Electrical Dat	ta			
		Flectric Motor		dR∆ at Idle & 70	n har	Flectrics	l Control	


Note: Optional Roll Cage available upon request before delivery. Calibration of pressure gauge (optional).



# **INFINITE STAGE PUMP TORQUE WRENCH**

Hydraulic/Electric **PE45** Series 0.8 I/min, 1.34 kW 700 bar (10,000 psi)

#### **Typical Flow Curve:**







(Shown with cooling option)

Vented Reservoir

Sound level: 87-92 dB









INFINITY

ISP Technology: The Next Generation is Here

**Power Team** has long been the market leader in high pressure hydraulic pumps due to durability, ease of use and life cycle cost benefits. Power Team introduces Infinite Stage Pump Technology - the first continuous pressure hydraulic pump that results in up tp 200% speed improvement making jobs faster and easier.

PE45PEE4PRS

#### **Quality means Lower Life-Cycle Costs:**

- Over 100,000 cycles
- Continuous duty up to 50°C (122°F) ambient (optional cooling kit)
- Proven design: Proven reliability

#### **Enhanced Usability:**

- Portable: 32.2 kgs (without oil)
- Up to four tools on one pump
- Removable control pendant (5 m
- Improved oil filtration
  1.34 kW (1.8 hp) Universal Motor for reduced voltage applications (up to -20% nominal voltage)
- 4-way valve (not for lifting applications)

#### **INFINITE STAGE PUMP**

The SPX PE45 is an Infinite Stage Pump which increases productivity on the job by providing continuous pressure for up to 2x the speed of typical 2-stage pumps. Jobs get done faster and easier.

(with cooling option)

#### **Designed with Safety in Mind:**

- Easily adjusted pressure regulator (relief) valve
- Fixed 103 Bar (1500 psi) pressure retract relief valve

#### **Operating Environment:**

Temperature: -25°C to +50°C (-13°F to 122°F) (If temperatures are at extremes of the operating range, it is recommended to use hydraulic oils that are rated for those temperatures. Refer to service manuals and cooling options)

#### Control:

• Normal Cycle: Push to cycle wrench each time

 Auto-Cycle : Push one button for continuous control.

Also suitable for Wind Power Applications





Order No.	Order No.	Manifold	Cooling Option	Electric Motor
(Normal Cycle)	(Auto-Cycle)			
PE45LEE4PRS	PE45LEE4APRS	single port/tool	No	110/115VAC
PE45LEE4CPRS	PE45LEE4ACPRS	single port/tool	Yes	50/60 Hz
PE45LEE4MPRS	PE45LEE4AMPRS	4 port/tool	No	Single Phase
PE45LEE4CMPRS	PE45LEE4ACMPRS	4 port/tool	Yes	(17 amps)
PE45YEE4PRS	PE45YEE4APRS	single port, plug*	No	(=: 5)
PE45YEE4CPRS	PE45YEE4ACPRS	single port, plug*	Yes	
PE45YEE4MPRS	PE45YEE4AMPRS	4 port, plug*	No	*Electrical plug on power cord
PE45YEE4CMPRS	PE45YEE4ACMPRS	4 port, plug*	Yes	alocation, bind on botto, corn
PE45PEE4PRS	PE45PEE4APRS	single port/tool	No	220/230VAC
PE45PEE4CPRS	PE45PEE4ACPRS	single port/tool	Yes	50/60 Hz
PE45PEE4MPRS	PE45PEE4AMPRS	4 port/tool	No	Single Phase
PE45PEE4CMPRS	PE45PEE4ACMPRS	4 port/tool	Yes	(8.5 amps)




www.spxboltingsystems.com)

#### AIR HYDRAULIC TORQUE WRENCH PUMP

- Use where air is the preferred source of power
- Powerful 2.25 kW (3 hp) motor starts under load
- Two-speed high performance pump
- External adjustable pressure regulator
- Retract side internal relief valve protects tool
- Hand remote standard
- Use for double or single acting tools
- Safe to use in hazardous or explosive environments
- Four-tool manifold (-4 model only) allows use of up to four tools simultaneously
- Couplers included with pump

# TORQUE WRENCH PUMP

Hydraulic/Air **PA55** Series
0.9 to 1.8 l/min, 2.25 kW
700 bar (10,000 psi)



Order No.	Manifold	Oil Delivery (I/min)	Oil Reservoir (I)	Usable Oil (I)	Overall Width (mm)	Overall Length (mm)	Overall Height (mm)	Pump Weight w/Oil (kg)	
RWP55 (Single Rotary)	Single Tool	7,6 I/min at 7 bar 0,9 I/min at 700 bar	9,5	8,4	420	241	504	35	
RWP55-4 (Single Rotary)	4 Tool	7,6 I/min at 7 bar 0,9 I/min at 700 bar	9,5	8,4	420	241	504	36	
RWP55-4-DUAL (Twin Rotary)	4 Tool	15,2 I/min at 7 bar 1,8 I/min at 700 bar	18	16	425	356	432	70	

		Motor Data	
	Air Motor	dBA at Idle & 700 bar	Air Control
Single Rotary Air Motor	2,25 kW (3 hp) 1,417 I/ min @ 6 bar (50 cfm at 80 psi)	85/90	Pneumatic remote control with 7,6 m cord
Twin Rotary Air Motor	4,5 kW (6 hp) 2,834 I/ min @ 6 bar (100 cfm at 80 psi)	85/90	Pneumatic remote control with 7,6 m cord

Note: Optional Air Servicing Unit, Exhaust Muffler and Roll Cage available upon request before delivery. Calibration of pressure gauge (optional).



# TORQUE WRENCH PUMP

Hydraulic/Air
PA60A Series
700 bar (10,000 psi)





# GET JOBS DONE FASTER: UP TO TWO TIMES THE FLOW!

#### ISP TECHNOLOGY HYDRAULIC AIR PUMPS


THE **SPX PA60A** ISP Hydraulic Air Pumps: The next generation is here! Power Team has long been the market leader in high pressure hydraulic pumps due to durability, ease of use and life cycle cost benefits. Power Team brand of SPX introduces Infinite Stage Pump Technology – the first continuous pressure hydraulic pump that results in up to 200% speed improvement - making jobs faster and easier.

Also suitable for Wind Power Applications



CAUTION: This Pump should not be

used for lifting applications






Order No.	Manifold	Required Air Pressure	Max. Pressure Output	RPM	dBa at Idle & 700 bar	51 bar	175 bar	350 bar	700 bar	Oil Reservoir Usable	A	В	С	Pump Weight w/Oil (kg)
PA60APF5FP (With Guard)	Single Tool	2,549 I/min @ 6 bar*	700 bar	3,000	75	9.31/min	3.7 I /min	1.8 l /min	0.9 I /min	5.68 l	510mm	300mm	460mm	34.1
PA60APF5FMP (With Guard)	4 Tool										D	E	F	
PA60APF5FPR (With Roll Cage)	Single Tool	2,549 I/min	700 bar	3,000	75	9.31/min	3.7 I /min	1.8 I /min	0.9 I /min	5.68 I	498mm	356mm	512mm	36.3
PA60APF5FMPR (With Roll Cage)	4 Tool	@ 6 bar*												

<sup>\* 90</sup> cfm @ 90 psi







# QUALITY MEANS LOWER LIFE-CYCLE COSTS:

- Over 100,000 cycles
- Continuous duty up to 50°C / 122°F ambient (optional)
- Proven design: proven reliability
- Roll Cage
- Sealed hydraulic reservoir
- Modular pumping cartridges
- Filter Regulator Lubricator (FRL) air preparation filter: Serviceable filter ensures a clean, lubricated and consistent air supply.

#### **ENHANCED USABILITY:**

- Up to 200% faster than 2-stage pumps
- Up to 4 tools on 1 pump with a 4-tool manifold (optional)
- Removable control pendant
   7.6m (25ft) cord length
- Built-in exhaust air heat exchanger: Internal oil path warms exhaust air to avoid freezing while cooling hydraulic oil to achieve optimum oil temperature.
- Easy-to-adjust pressure to achieve proper torque values.
- · Calibration capable gauge
- Improved oil filtration

# DESIGNED WITH SAFETY IN MIND:

- Rugged 3kW (4 hp) air motor
- Easily adjusted pressure regulator (relief) valve
- Fixed 103 Bar (1500 psi) pressure retract relief valve
- ATEX II, CAT2, GDcT4 compliant: Enables usage in applications with potentially explosive environments.
- · Quiet operation

Calibration capable, vibration damped gauge has an easy-to-read 100 mm (4") diameter, with 700 Bar (10,000 psi) indication



Up to 4 torque wrench tools can be used with one pump with the 4-tool manifold (optional)



PA60APF5FPR (with Roll Cage)

Pneumatic remote control comes standard with a 7.6m (25')

Powerful 3kW air motor starts under load and yields up to 2x the flow of other air pumps for greater application speed and productivity


Easy-to-replace pump cartridges minimize downtime and service costs

Muffled exhaust protects against elevated noise to ensure operator comfort

Optional roll bar provides a lift point as well as protection from damage in rough environments

The chart shows a traditional two stage hydraulic pump flow curve where high flow transitions to low flow at around 48 bar. The chart also shows that the ISP series pump has much higher flow and remains smooth throughout the pressure curve. Flow is continually changing based on pressure, giving the maximum horse-power and flow for that pressure. The biggest increase in flow is between 69 & 345 bar.

For tools such as torque wrenches that normally operate between 69 & 345 bar impact is significant – tools operate twice as fast, increasing productivity by getting the job done in much less time.





# **NUT SPLITTERS**

Hydraulic 15 & 25 Ton Capacity Single-acting, Spring-return 700 bar (10,000 psi)









- "Dial-in" feature on HNS150 makes adjustment of splitter simple, without the worry of damaging the bolt
- Specially designed "tool steel" cutter blade penetrates the nut to the precise point where it cracks, stopping short of the bolt threads
- Nut splitter features a dramatically improved cutter blade with an 800% greater resistance to chipping and breaking over previous models
- All models feature a rugged one-piece cutting frame coupled to a heavy-duty hydraulic cylinder
- Compact size allows you to use it in confined areas where it will deliver enough force to split the toughest "fused" or rusted-on grade 2H nuts (metric grade 12) up to Rc 38 hardness
- Simply split nut on one side, spin nut splitter 1/2 turn and make second cut on opposite side; nut separates into halves for easy removal













**ENS** Series Hydraulic Nut Splitters (Topside/Subsea) for Nut size A/F 30mm to 130mm  $(1^{1}/4"$  to  $5^{3}/8")$ available

(Consult factory or refer www.spxboltingsystems.com



Align mark on cutter blade with scale.





Cap. (Tons)	Tool Model	A	В	(S150 & )	HNS225 D	E	F	HEAD THICKNESS ((mm)	REPLACEMENT BLADE	TOOL WEIGHT (kg)
15	HNS150	73	86	200	70	264	53	25,4	308840	3,7
15	HNS150A	77	361	27	54	94	30	25,4	351985	7,2
25	HNS225	108	153	366	99	С	82	38,1	308022	13,2



		CAPACITIES	;	
Tool Model	5 (2 or A)	Nut Grade 9 (5 or B)	10 (8 or C)	12 (2 or H)
HNS150	<sup>1</sup> / <sub>2</sub> - 1- <sup>1</sup> / <sub>2</sub> " (12,7-38,1mm) hex	¹/2 - 1-¹/2" (12,7-38,1mm) hex	<sup>1</sup> / <sub>2</sub> - 1- <sup>5</sup> / <sub>16</sub> " (12,7-33mm) hex	¹/2 - 1-¹/8" (12,7-29mm) hex
HNS150A	<sup>1</sup> / <sub>2</sub> - 1- <sup>1</sup> / <sub>2</sub> " (12,7-36mm) hex	¹/2 - 1-¹/2" (12,7-36mm) hex	¹/2 - 1-⁵/16" (12,7-33mm) hex	¹/2 - 1-¹/8" (12,7-29mm) hex
HNS225	1-1/8 - 2-1/4" (29-57mm) hex	1-1/8 - 2-1/4" (54-57mm ) hex	1-1/8 - 2-1/6" (29-55 mm) hex	1-1/8 - 1-11/16" (29-43mm) hex
	Hex Size: A/F Ţ ◯			

# PIPE FLANGE

Hydraulic Spreaders
5 & 10 Ton
Single-acting, Spring-return
700 bar (10,000 psi)

#### **HYDRAULIC PIPE FLANGE SPREADERS – 5 & 10 TON CAPACITY**

- You'll never again have to resort to "hammer and chisel" methods that waste time and effort. Flange spreaders should be used in pairs to provide even spreading force.
- Standard 60° wedge is suitable for most flanges; 30° "thin" and 60° "blunt" wedges are optional.
- The HFS3A is designed for applications where total thickness of flanges and max. spread gap is 76,2mm or less and flange bolts are a min. of 17,5mm dia.
- Use HFS6A if total thickness of flanges and max. spread gap is 152,4 mm or less, and flange bolts are a min. of 20,7 mm dia.









(30° Thin wedge)









Standa		Standard	Optional Wedges		Min. Flange Opening (mm)				ax. Flange ening (mm)	Combined Flange	Max. Pin	
Capacity (Tons)	Order Number	Wedge Type	30° Thin	60° Blunt	60° Std.	60° Blunt		60° Std.	60° 30° Blunt	Opening (mm)	Dia. (mm)	Weight (kg)
5	HFS3A	60° Sharp	350823	350822	1,6	25,4	1,6	38,1	38,1 18,3	76,2	17,4	4,1
10	HFS6A	60° Sharp	350549	350550	1,6	38,1	1,6	50,8	50,8 24,6	152,4	20,6	8,2

<sup>\* 30°</sup> Thin wedge provides more than twice spreading force of 60° wedge.

<sup>\* 60°</sup> Blunt-faced wedge for wide flange openings.

## **HYDRAULIC PUNCHES**

35 Ton Single-acting, Spring-return 700 bar (10,000 psi)

- Punch smooth, precise holes in seconds; much faster than drilling.
- Fully portable for construction, maintenance and service applications, or can be mounted on a workbench for production jobs. Has carrying handle for precise locating.
- Rugged, forged steel "C" frame for great strength and durability.
- Dual action, spring loaded stripper holds material during punching operation, strips material from punch on return. Scribe lines on stripper aid in locating the punch (HP 35 only).
- The PE172 electric/hydraulic pump is an ideal power source.

**No. HP35** – Punch only, includes metal case and die change tools. Wt., 19 kg.

No. HP35S – Punch with punches and dies. Includes HP35 punch, metal case and 250459 punch/die set. Wt.,20 kg.

**No. HP35SP-220** – Punch set with pump. Includes HP35 punch, PE172-50-220 (220V/50Hz) electric/hydraulic pump, 9756 hose, 9798 hose half coupler, 250459 punch/die set, metal case. Wt., 40 kg.

NOTE: Available in 115 volt, 60 Hz. Order without suffix "-220".


**No. HP35P-220** – Punch set with pump. Same as HP35SP-220, but does not include punch/die set. Wt., 39 kg.

NOTE: Available in 115 volt, 60 Hz. Order without suffix "-220".



**HP35** 

PUNCH	PUNCH/DIE SETS FOR HP35 HYDRAULIC PUNCHES												
Punch Size (mm)	Punch Style	For use with HP35 Hyd. Punch Punch/w Flat Die Set	Punch/w Bevel Die Set										
7,9		PD313											
9,5		PD375	PD375B										
11,1		PD437	PD437B										
13,5		PD531	PD531B										
14,3	Round	PD562	PD562B										
17,5		PD688	_										
19,8		PD781	_										
20,6		PD812	_										



No. 250459 - Punch/die set for round holes.
Includes one each: PD437 11,1 mm punch/die,
PD562 14,3 mm punch/die, PD688 17,5 mm
punch/die, PD812 20,6 mm punch/die. Wt., 0,7 kg

Η														Max.						
		Max.		Max.						Mtng.			1	Throat						
		Oper.	Oil	Materia						Holes				Depth						
Cap	Order	Droce	Com	Aleka Laura															_	
J. 1	Viuci	LIG22	Cap.	tnickne	ess A	В	C	D	E	, i	G	н	J	K	L	M	N	0	Р	Q
	) Number			(mm)																

Punching holes in mild steel, structural steel, stainless steel, brass, aluminium etc. Typically used in bar size angle iron, channels, tees and zees. General reference guide for metal punching operations: Consult factory.



#### **SPREADERS**

Hydraulic  $1 \& 1^1/_2$  Ton Single-acting, Spring-return 700 bar (10,000 psi)




Tested to conform to ASME B30.1 standard


#### THE HYDRAULIC PRY BAR!

- Use to lift machines or as a clamp; spread concrete forms or rebar or perform straightening jobs.
- Conforms to ASME B30.1 standard.
- High strength alloy steel forged upper and lower jaws on HS2000.
- Jaws are spring-return; retract automatically when pressure is released.

**No. HS2000** – 1 Ton capacity spreader. Full 908 kg capacity at 700 bar with 102mm spread. Can be "dead-ended" at 102mm spread under full load. Needs only 14,2mm clearance to engage jaws.

**No. HS3000** – 1<sup>1</sup>/<sub>2</sub> Ton capacity spreader. Full 1.362 kg capacity at 700 bar with 292 mm spread. Greater than competitive units. Needs only 30,2 mm clearance to engage jaws. Can be "dead-ended" at 292 mm spread at full load.





Capacity (Tons)	Max. Spread (mm)	Order Number		B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	G (mm)	H (mm)	l (mm)	Oil Capacity (cm³)	Min. Clearance Required (mm	Weight (kg)	HYDRAULIC TOO	6
1	101,6	HS2000	101,6	50,4	14,3	252,52	236,5	50,8	176	57	_	4	14,2	2,2	ST	
<b>1</b> <sup>1</sup> / <sub>2</sub>	292	HS3000	292	108	30,2	_	451	57,2	511	143	92	20	30.2	10		



HS2000 SPECIFICATIONS	
Maximum rated capacity1 Ton at 700 bar	N
Maximum spread101,6 mm	N
Minimum clearance required14,2 mm	N
Cm³ oil required 4	(

HOSUUU SPECIFI	CATIONS
Maximum rated capacity	11/2 Ton at 700 bar
Maximum spread	292 mm
Minimum clearance required.	30,2 mm
Cm <sup>3</sup> oil required	20

# TIRE REMOVING

BB Series Tool
10 Ton Hydraulic
Single-acting, Spring-return
700 bar (10,000 psi)

TIRE REMOVING TOOL (Bead Breaker)

# UNSEAT TIRE BEADS HYDRAULICALLY ON 25" TO 49" DIAMETER EARTH MOVER RIMS WITH PRY BAR POCKETS.

- Made to fit into the pry bar pocket
- Hydraulic pressure does all the unseating.
- Lightweight and portable.
- P55 hydraulic hand pump and 9764 hose recommended to be used with BB1600.
- Ideal for field service repairs of large Off-The-Road (O.T.R.) Tractor, Truck, Grader, Farm and Earth Mover tire rims with pry bar pockets.






Tool Model	Rim Size	Cylinder Cap. (Tons)	Stroke (mm) kg.	Tool Weight
BB1600	25"-49"	10	101,6	10,25
BB1601	25"-49" (Single, two, three piece rims)	10	101,6	10,9

## **C-CLAMPS**


Hydraulic Accessories

 In 5, 10 and 25 ton capacities. For use with Power Team general purpose single-acting series cylinders of comparable capacity.

- For clamping, pressing and bending.
   Ideal for welding and metal fabrication for fit-up of sheet or plate steel.
- Clamps withstand full rated capacity of the cylinders for which they are intended.
- To minimize the effects of off-center loading, the CC5, CC10 and CC25 should be used with the optional 350144 and 350145 swivel caps.




"C" CLAMPS



Cap. (Tons)	Order Number (C-Clamp only)	Use With Cyl. No.	A (mm)	B (mm)	C (mm)	D (mm)		F (mm)		H (mm)	l (mm)	Weight (kg)
5	CC5	C51C - C57C	314	95,3	186	50,8	63,5	197	11/2"-16 UN	22,2	76,2	11,3
10	CC10	C101C - C1010C	403	152,4	240	50,8	85,8	273	2 <sup>1</sup> / <sub>4</sub> "-14 UNS	22,2	88,9	20,9
25	CC25	C251C - C2514C	533	152,4	319	76,2	114,3	313	3 <sup>5</sup> / <sub>16</sub> "-12 UNS	36,5	117,5	41,3

# OPTIONAL ACCESSORIES FOR USE WITH CC5, CC10 & CC25 HYDRAULIC CLAMPS

CC10



- May be used with CC5
- \*\* Must be used with a threaded adapter.



#### **TESTERS**

Hydraulic 200, 300 & 750 l/min (50, 75 and 200 GPM)





# 200, 300 AND 750 L/MIN IN-LINE HYDRAULIC TESTERS


- Accurately measure oil flow, pressure and temperature on in-plant equipment, forklifts, machine tools and more.
- Temperature and flow readings are in Metric and English, accurate to within ±2% of full scale.
- Dual pressure gauges for high and low pressure readings; low pressure gauge is automatically shut off and protected as pressure rises beyond its maximum reading.
- Automatic pressure compensating feature lets you increase flow without affecting pressure setting.
- Reverse flow through tester will not cause damage; replaceable safety disc ruptures if pressure exceeds upper limit.
- Solid state voltage regulator eliminates errors caused by voltage change during testing.
- Troubleshoots systems with capacities to 750 I/min at pressures less than 350 bar. Accurately measure oil flow to ±5%, pressure to within 2% and temperature readings within 1%.

 Pressure gauge is liquid filled to dampen system pulsation.


For more precise low pressure readings, an optional dual pressure gauge kit is available. Consult factory.

No. HT50A – Hydraulic circuit tester with single liquid filled pressure gauge, 0-5000 psi, 0-350 bar. Includes two adapter unions for 3/4" male NPTF fittings. Wt., 16,8 kg


#### Testing a pump



#### Testing a relief valve



#### Testing a directional valve







	Maximum													
	Max		Flo	w	Opera	ting	Temp	erature				A	В	C
Order	Flow		Ran	ges	Pres	sure	Scale	Range	Port	Weig	tht	in.	in.	in.
Number	(Vmin)	Scale	(gpm)	(Vmin)	psi	(bar)	°F	°C	Sizes	lbs.	kg.	(mm)	(mm)	(mm)
									1 <sup>1</sup> /16-12UN					
HT50A	200	_	0-50	0-200	5,000	345	20-240	-6 to 114	Female "0"	30.3	16.8	121/4	$6^{1}/_{4}$	10
									Ring with			(311)	(159)	(255)
									Union Adapt.			,	,	,
									³/₄" Female					
									NPTF					
HT75	300	High	15-75	50-300	5,000	345	100-250	40-120	3/4" NPT	18.2	8.6	133/4	11 <sup>7</sup> /8	5³/ <sub>4</sub>
		Low	3-15	10-60					Swivel			(349,25)	(301,62)	(146,05)
-		High	25-200	100-750					11/2"*					
HT200	750				5,000	345	100-250	40-120	SAE	28.2	13.6	15 <sup>7</sup> /8	131/4	6 <sup>3</sup> / <sub>4</sub>
		Low	5-40	20-150					Split Flange			(403,47)	(336,55)	(171,45)



For a complete listing of accessories for the HT series of hydraulic system testers, consult factory. \*Not included, must be ordered separately.

#### USE THE 200, 300 OR 750 L/MIN TESTER TO SIMULATE ACTUAL OPERATING CONDITIONS OF THE SYSTEM UNDER TEST

Testing the pump: Operator runs engine at a specific rpm and adjusts tester's pressure compensating valve to simulate a work load. By comparing meter readings with manufacturer specs, proper operation of pump can be confirmed. If oil flow and pressure do not meet specs, the pump is faulty. Or, if test results and specifications agree, the operator will know that the problem is elsewhere in the system and that other tests must be performed. Regardless of the component being tested, hook-up and testing is accomplished in minutes.

**NOTE:** These hydraulic testers should always be used with the owner's manual/manufacturers' specifications for the system under test.

# SERVICE ACCESSORIES

Hydraulic Tester

# DUAL GAUGE CONVERSION KIT FOR 50 GPM TESTER.

Provides more precise low pressure readings. Remove pressure gauge block and gauge from tester and replace it with this block.

Install high pressure gauge from tester (350 bar) onto this new block.

**No. 307281** – Dual gauge conversion kit. Consists of gauge mounting block, pulsation dampener, thermal overload protector, low pressure gauge and gauge protector. Wt. 0,45 kg.





No. 37045 — Auxiliary power cord. For use with any 12 or 24 volt battery to remotely power tester. Wt. 0,5 Kg. CAUTION: For use on negative ground systems only.

**No. 204990** – Auxiliary power converter. Permits use of 120/230 volt outlet to power tester. Wt. 0,45 kg.





37045

#### **Hoses**

No. 9785 – Hose, 19,1 mm I.D. x 3/4"

NPTF male both ends. 3m length. 155
bar working pressure. (2 req'd on 200
& 300 I/min testers) Wt., 3kg.

The following hose assemblies are all
4-ply spiral wound wire, 3 m long. For
use with 750 I/min testers.

No. 9786 – Hose, 25,4 mm I.D. x 11/4" NPT mail both ends. Recommended max. flow 340 I/min, with a working pressure of 280 bar. Wt., 6,3 kg. No. 9787 – Hose, 31,8 mm I.D. x 11/4" NPT male both ends. Recommended max. flow 530 I/min, with a working pressure of 210 bar. Wt., 6.4kg.

No. 9788 – Hose, 38,1 mm I.D. x 11/2" NPT male both ends. Recommended max flow 750 I/min, with a working pressure of 150 bar. Wt., 11,4 kg.

#### 203264





#### **Hose reducer bushings**

**No. 203264** – Consists of two hose reducer bushings, 11/4" NPT female x 11/2 NPT male end. Needed to adapt No. 9786 25,4 mm I.D. hose and No. 9787 31,8 mm I.D. hose to tester. Wt., 1 kg.



## **SERVICE TOOLS**

Accessories



#### **PHOTO TACHOMETER**

- Infrared light source, micro-processor controlled crystal display.
- Strong magnetic base is included. Machine speed: It is critical for proper machining operations. Speeds too fast or too slow can shorten tool life and cause expensive, unnecessary machine downtime. This digital photo tach can take readings from revolving shafts on drill presses, grinders, lathes and other machines. It can also be used to check engine operation on in-plant vehicles like forklifts. The 3344A is

accurate to within  $\pm$  1 rpm. The 10mm high liquid crystal display is easily visible even in high ambient light areas.

No. 3344A - Digital Photo Tachometer. With memory, photo probe assembly, magnetic base, 2,75 m of reflective tape and plastic case. Wt., 2 kg.

No. 39811 - Replacement magnetic base assembly. Wt. 0,1kg.

No. 45329 - Replacement photo probe assembly. Wt., 0.2 kg.

No. 204666 - Replacement retro-reflective indicator tape, 2,75 m long x 12,7mm wide. Wt., 0.1 kg.

#### **SPECIFICATIONS**

Readout: Liquid crystal display: 4 (10mm high) digits, low battery indicator, memory mode indicator, high and low RPM memory mode indicator.

Range: 200 to 9999 rpm. Accuracy: ± .25%,  $\pm 1$  rpm. Update time: 3/4 second. Power switch: Membrane switch (automatic shut-off after one minute of no signal input). Power source: 9 volt alkaline battery. Light source: Infrared with 4,6m plug-in cable. Light holder assembly: 13,6 kg rated magnet; 50,8 mm dia. x 6,4 mm high (102 mm high overall with post). **Size:** 86 w, 152 h x 38 mm d.

**Carrying case:** 343 w, 254 h x 102 mm d.

#### **HTS50 HEAVY-DUTY PIPE SEALANT** WITH TEFLON®

- Seals new or damaged threads; resists water, chemicals and oils.
- · Replaces conventional tape methods; forms a clog-free seal. Effective at 700 bar.

When "plumbing" a hydraulic system, there's now a better answer than tapes which can tear or shred, possibly plugging filters, valves or gauges. This compound combines the

lubricating qualities of Teflon® with a fast curing anaerobic sealant. Seals all metal fittings, Co.) plugs and threaded joints quickly and easily. Cures to form a permanent seal which is inert to hydrocarbons, most acids, chemicals, solvents and steam. Allows adjustment up to 16 hours after assembly; cannot loosen under vibration. Prevents galling of mating parts upon disassembly. Withstands temperatures from  $-54^{\circ}$  to  $+190^{\circ}$  C.

No. HTS50 - Sealant, 50 ml. tube. Wt., 0.2 kg.

(Teflon® is a registered trademark of duPont

HTS50



#### "O" RING SEAL PICKS

Even the seemingly simple job of removing and installing "O" ring seals can be difficult without the aid of the proper tool. The 7312 all metal "O" ring seal pick does the job with ease. Two special picks in set No. 7103 get right to the trouble areas.

No. 7312 - "O" ring seal pick. Wt., 0.1 kg. No. 7103 - Set of two "O" ring seal picks. Wt., 0.1 kg.



#### UNIVERSAL OUTSIDE THREAD CHASER No. 7402 - Thread chaser, complete

Restore damaged threads on shafts, housings, cages, etc., for re-assembly of matching parts. Eliminates need for thread-cutting equipment. Will not harm threads. V-pads and dies can be replaced. Cap. 32 to 127 mm O.D.

(with 6 dies: threads per inch - 4,  $5, 6, 7, 7^{1}/_{2}, 8, 9, 10, 11, 11^{1}/_{2},$ 12, 14, 16, 18, 20 and 24). Wt., 0,2 kg.

No. 202817 - Metric die set (3 dies: mm per thread: 1,  $1^{1}/_{4}$ ,  $1^{1}/_{2}$ ,  $1^{3}/_{4}$ , 2,  $2^{1}/_{2}$ , 3,  $3^{1}/_{2}$ , and 4). Wt., 0.1 kg.



#### **MAGNETIC PICK-UP TOOL**

Has permanent magnetic head for retrieving parts from otherwise inaccessible places. No. 7395 - Pick-up tool with pocket clip. 152 mm Ig. Wt., 0.1 kg.





# WRENCHES, **PRY BARS**

Spanners & Jimmy Bars

#### **RATCHETING CHAIN WRENCHES**

Special head design allows you to turn wrench in either direction. Ratcheting action makes it possible most any size and shape.

**No. 7400** – Chain wrench, cap. 12,7 to 121 mm O.D. (Capacity= 450 Nm) Wt., 0,9kg

**No. 7401** – Chain wrench, cap. 76 to 171 mm O.D. (Capacity= 900 Nm ) Wt., 2,3 kg.

No. 209199 - Replacement chain with Our rolling head pry bars are an pin for No. 7400 chain wrench (406 mm long).

pin for No. 7401 chain wrench (610 mm long).

#### **ADJUSTABLE HOOK SPANNER** WRENCH

Needed wherever turret adjusting nuts or packing gland nuts are used. Cap.: 38 to 102 mm. Handle overall length: 483 mm.

No. 885 – Adjustable hook spanner wrench. Wt., 1,4 kg.

#### ADJUSTABLE HOOK SPANNER **WRENCHES**

Replace many fixed-size wrenches... cover range of capacities needed to service industrial tractors and other equipment. Drop-forged jaws adjust to eleven positions for a capacity of 121 to 324 mm O.D. Handle overall length: 610 mm; diameter: 25,4 mm.

No. 7307 - Spanner wrench with one 9,5 mm thick jaw. Wt., 3,3 kg.

No. 7308 - Spanner wrench with two interchangeable jaws: one 9,5 mm thick, one 19 mm thick. Wt., 5 kg

#### **HEAVY-DUTY ADJUSTABLE SPANNER**

Extra heavy construction. Has one 19 mm thick, eleven-position hook-jaw for a capacity of 131 to 324 mm O.D. Drop-forged. Handle length: 654 mm; handle dia.: 33.3 mm

No. 7309 - Heavy duty adjustable hook spanner wrench. Wt., 5 kg.

#### ADJUSTABLE GLAND NUT WRENCH

Designed to handle 51 to 152 mm dia. hydraulic cylinder gland nuts on many construction vehicles. Fits 6.4 and 7.9 to re-grip without removal. For parts of mm dia. pin holes; features a 3/4" sq. drive.

> No. 1266 - Adjustable gland nut wrench. Wt., 1,4 kg.

No. 204928 - Replacement pin for No. 1266

#### **PRY BARS**

extremely popular and useful tool. Head may be used for almost any pry-No. 209200 - Replacement chain with ing job since a great deal of leverage can be obtained. Long tapered body may be used as a lining-up drift.

> **No. 7162** – Pry bar; 9,5 mm round, 152 mm long. Wt., 0,1 kg.

No. 7163 - Prv bar: 11.1 mm round. 305 mm long. Wt., 0,3 kg.

No. 7164 - Pry bar; 14,3 mm round, 406 mm long. Wt., 0,5 kg.

No. 7165 - Pry bar; 19 mm round, 457 mm long. Wt., 1 kg.

#### **JIMMY BARS**

Ideal for general lifting or prying. Heat treated chrome alloy steel to resist bending or breaking.

No. 7166 - Jimmy bar; 15,9 mm round, 457 mm long. Wt., 0,6 kg.

**No. 7167** – Jimmy bar; 19 mm round, 610mm long. Wt., 1,1 kg.

No. 7168 - Jimmy bar: 22.2 mm round, 762 mm long. Wt., 1 kg.

#### "MAJOR PERSUADER" JIMMY BARS

Two big jimmy bars for big jobs. Forged from chrome alloy steel.

**No. 7420** – Jimmy bar; 22,2 mm round, 1.168 mm long. Wt., 3,4 kg.

No. 7421 - Jimmy bar; 25,4 mm round, 1.372 mm long. Wt., 1,9 kg.



7168

# PULLERS

Page Page Page ...129-132 ...146-150 ...137 **PULLER BASICS HYDRAULIC ADAPTERS PULLER SETS** Page Page ...138, 139 ...151 ...133 **MECHANICAL BLANKETS JAW PULLERS** Page Page Page ...152, 153 ...134 ...140 UNIVERSAL **MECHANICAL** 2/3 JAW **PUSH PULLERS PULLERS PULLERS GRIP-O-MATIC** Page Page ...141 ...154, 155 ...135 **PULLER ACCESORIES ATTACHMENTS GRIP-O-MATIC INSTALLER** Page

> ...142-145 JAW PULLERS

**PUSH PULLERS** 



**PULLER SETS** 

#### **CONSIDERATIONS:**

Determine the type of puller or puller combination. Which puller type is best suited for gripping the part?

Is a combination of puller types required?

Determine the reach needed for your particular pulling problem. The puller you select must have a reach equal or greater than the corresponding sizes of the part to be pulled.


Determine the spread need. The spread is determined by the width of the part

being pulled. The puller's spread should be greater than the width of the part to be pulled.

Estimate the force needed to solve your pulling problem. A puller with the proper reach and spread will usually have enough capacity to remove the corresponding part. When in doubt, always use a puller with a larger capacity than what may be needed. Rusted parts or parts with a large area of resistance may need more pulling force.

## **PULLER SELECTION**

Basics
3 Basic Puller Scenarios





In order to perform a proper pull, be certain that you firmly grip the gear, bearing, wheel, pulley, etc., and apply force to the shaft. Use a 3-jaw puller, instead of a 2-jaw, whenever possible for better gripping power and a more uniform displacement of pulling force.

# PULLING A GEAR, BEARING, WHEEL, PULLEY, ETC., FROM A SHAFT

#### **RECOMMENDED TOOLS:**





Either manual or hydraulic. For extra force and convenience, use a hydraulic puller. Both are available in 2 or 3 jaw configurations and are used to grip the outer circumference of a part or can be used with a pulling attachment, such as a bearing/pulley attachment. (Page 133, 140, 142-143, 152-153)



#### **Push-Pullers**

can thread directly into a threaded part for easy and secure removal. Push-Pullers can be used in conjunction with bearing/pulley attachments which grip the part from behind. A wide assortment of male and female threaded adapters are available as well as metric adapters. (Page 134, 144-145)



#### Bearing/ pulley attachments

provide a "knife-like" edge to get behind parts for added versatility and secure removal of parts. Great for parts that don't offer adequate grip with jaw-type pullers. (Page 135)



#### **Adapters**

Whether you need an adapter compatible with any number of threaded hole sizes, protection of part to be pulled or for assisting the installation of a component; Power Team offers a variety of adapters to assist in the removal or installation of parts. (Page 137)




## **PULLER SELECTION**

Basics
3 Basic Puller Scenarios

PULLING INTERNAL BEARING RACES, RETAINER, SEALS, ETC.

# Z



By extending the narrow jaws of an internal pulling attachment through the center of the part to be pulled, a straight pull is insured, and damage to the housing is avoided. While parts within a "blind hole" in a housing do present a problem, Power Team has the internal pulling attachment or a combination of an internal pulling attachment and puller to handle the situation.

#### **RECOMMENDED TOOLS:**



Internal pulling attachments

have narrow jaws which extend through the center of the part to be pulled. They provide a straight pull and avoid damaging housings. Internal attachments feature adjustable jaws to fit various diameter parts. (Page 135)



Slide hammer with internal attachment


is ideal for removing parts from blind holes, especially where there is no housing to brace puller legs against. (Page 138-139)



Push-puller with internal attachment.

Push-puller is available in both manual and hydraulic versions. (Page 134-135, 144-145)

3



A shaft with a threaded end can be removed without damage by using one of our slide hammer, manual Push-puller or hydraulic Push-pullers, in conjunction with the proper threaded adapter. Removal is easy! If the shaft to be removed has external threads, simply choose one of our female threaded adapters of proper size/thread. If the shaft has internal threads, simply choose the correct size male threaded adapter.

# PULLING A PRESS-FITTED SHAFT FROM A HOUSING

**Note:** Manual pullers require that the shaft being pulled is no more than twice the diameter of the puller's forcing screw. To determine the recommended tonnage for hydraulic pullers, multiply the diameter of the shaft to be pulled by ten. Example: For a 1" (25 mm) shaft, we recommend 10 tons of pulling force.

#### **RECOMMENDED TOOLS:**





**Slide hammer puller** matched with a set of threaded adapters is a perfect tool for light duty pulling needs. (Page 138-139)




**Push-pullers** matched with a set of threaded adapters make for an extra versatile pulling tool. (Page 134, 137, 144-145)

# **PULLER SELECTION**

Basics
Choosing the Right Puller

#### WHY POWER TEAM ROLLED PULLER THREADS ARE SUPERIOR:



#### Pitch diameter of thread

**ROLLED THREADS** start with a material O.D. equal to the pitch diameter of the thread. The rolling process moves material from below the pitch diameter and creates a smoother and stronger thread.

#### **Centerline of screw**

**CUT THREADS** start with a material O.D. equal to the thread O.D.. Cutting can cause tears on the thread surface which can make it rough and can cause minute cracks at root of thread which can open up during heat treat and lessen the capacity of the screw.





Puller with a bearing pulling attachment was used to take a bearing off a utilities well pump motor.

	Features	Benefits
	<ul> <li>Grip-O-Matic® feature on jaw type pullers</li> <li>2-way, 3-way and 2/3-way combination pullers 1 to 37 ton mechanical pullers 5 to 50 ton hydraulic pullers 2¹/s" (54 mm) to 27⁵/s" (702 mm) reach 3¹/₄" (83 mm) to 44" (1,118 mm) of spread</li> </ul>	<ul> <li>The harder the pulling force, the tighter the jaws grip</li> <li>A wide variety of pullers; select a specific puller for a specific application or select one or more pullers for general applications</li> </ul>
7	<ul> <li>Forged alloy steel jaws</li> </ul>	<ul> <li>Strongest possible part; the grain of the material follows the contour of the part.</li> </ul>
	Machined puller jaw toes	<ul> <li>Larger and stronger pulling toe than most competitors</li> </ul>
	<ul> <li>Alloy steel heads (forged or flame cut)</li> </ul>	<ul> <li>Heat treated and designed for maximum strength</li> </ul>
	• Rolled "V" threads	<ul> <li>Stronger and smoother than cut threads</li> </ul>
	Special coating on threads	<ul> <li>Resists corrosion, traps lubrication better than black oxide</li> </ul>
	<ul> <li>Heat treated alloy steel cross bolts</li> </ul>	<ul> <li>Designed for max. shear strength</li> </ul>
	<ul> <li>Standard hydraulic cylinders on Grip-O-Matic® series</li> </ul>	<ul> <li>Cylinder can be removed from puller and used in other hydraulic applications</li> </ul>

**NOTE:** The puller application photos shown in this catalog are shown without protective blankets for clarity of photos. Power Team strongly recommends you always make your pull with a protective device in place. For protective blankets, refer page 151.



#### **PULLER**

#### Safety Tips

# A SAFETY FIRST!

#### **Operator safety comes first!**

Tons of force are being exerted with your Pulling System. You must respect this force, and observe safety precautions at all times

#### **A** CAUTION

It is impossible to predict the exact force required for every pulling job: setup requirements and the size, shape and condition of the parts being pulled vary a great deal. In addition, the Power Team Pulling System is so versatile, it is possible that components in a pulling setup may have different tonnage ratings.

The lowest "capacity" component, then, determines the capacity of the setup. For example: When an accessory with a 1 ton capacity is used with a 10 ton capacity puller, the setup can be used only at a force of one ton.

These tools should be used only by trained personnel familiar with them.

Always wear eye protection during a job since work parts, or the pulling tool itself, may break and parts may fly. It is recommended to cover the work with a Power Team Protective Blanket or use a shield while force is being applied. If you are at all unsure which tool or attachment to select, contact the Power Team factory.


#### A few easy tips to remember:

- **1. Wear safety glasses at all times!** You have only one pair of eyes, so protect them from possible flying parts.
- 2. Keep your pulling tools in shape! Clean and lubricate the puller's forcing screw frequently, from threads to tip, to assure long service life and proper operation.
- **3. Cover work with a protective blanket!** With high forces being exerted on the part being pulled, breakage may sometimes result. By covering the work with a protective blanket, the mechanic reduces the danger of flying parts.
- **4. Apply force gradually!** The component should give a little at a time. Do not try speed removal by using an impact wrench on the puller screw.
- **5. Use the right size puller!** If you have applied maximum force and the part has not moved, go to a larger capacity puller. Resist sledging.
- **6. Align puller legs and jaws!** Be sure the setup is rigid and that the puller is square with the work.
- **7. Mount puller so grip is tight!** Tighten the adjusting strap-bolts when using a jaw type puller. Always use a 3-jaw puller whenever possible. A 3-jaw puller gives a more secure grip, more even pulling power. Apply force gradually.
  - Never use an extension on a wrench. Never use an impact wrench.
  - Never strike the end of the forcing screw. Always cove work with a protective blanket.
- 8. Do not couple puller legs! The tonnage capacity of a Push-Puller®is reduced when longer than standard legs are used, or when legs are in compression. The chance of breaking, bending or misaligning legs increases. Keep reach to a minimum. Use shortest legs possible to reach workpiece. Thread legs into work piece, pulling attachment or adapters evenly. Uneven legs will cause greater pull or push on one side, creating a bending action which could cause damage to work piece or cause a leg to break. The sliding plates must always be on the opposite side of the cross block from the forcing screw nut or hydraulic cylinder. Always cover work with a protective blanket.

#### **Bearing pulling attachments:**

These attachments may not withstand the full tonnage of the pullers with which they are used. The shape and condition of the part being pulled affects the tonnage at which the puller blocks and/or studs may bend or break. Always select the largest attachment which will fit the part to be pulled.









# PULLERS DESIGNED TO PULL GEARS, BEARINGS AND COUNTLESS OTHER PRESS FITTED PARTS.

# Shaft protector

Pulling attachment Styles



Step plate

Styles of puller cross heads

2-jaw 3-jaw 2/3-jaw head head combination



Fed. Spec.: GGG-P-00781-D


 Grip-O-Matic® feature on all pullers. The harder the pull,

the tighter the grip for removing gears, bearings and countless other press fitted parts.

- 2-way, 3-way and 2/3 way combination pullers make it easy to select a specific puller for a specific application.
- Forged from high quality steel, heat treated and subjected to rigorous tests which exceed rated puller capacity.
- Alloy steel heads are forged for maximum strength.
- Forcing screw threads are rolled, not cut. This process creates a smoother and stronger thread.
- Heat treated alloy steel cross bolts for maximum shear strength.
- Machined puller jaw toes produce larger and stronger pulling toes.

#### **JAW PULLERS**

Mechanical
1 to 25 Ton
2 & 3 Jaw Pullers



**Choosing the right size puller:** Compare the "reach" and "spread" of the pulling job with that of the pullers listed. The puller selected must have dimensions greater than those of the job.

		M	ax.			law	
	Order No.	Reach (mm)	Spread (mm)	Screw Size (in.)	Thickness (mm)	Width (mm)	Capacity, Style and Weight
1020 1021	1020	54	82,6	5/16-24 x 98,4 mm	3,5	6,4	1-Ton, 2-Jaw;
1020	1021	54	82,6	<sup>5</sup> / <sub>16</sub> –24 x 98,4 mm	3,5	6,4	0,14 kg 1-Ton, 3-Jaw; 0,23 kg
1022	1022	85,7	101,6	³/₅–24 x 124 mm	Upper 4,8	Upper 6,4	2-ton, 2-Jaw; 0,4 kg
	1023	85,7	121	³/s–24 x 124 mm	Lower 3,2 Upper 4,8 Lower 3,2	Lower 12,7 Upper 6,4 Lower 12,7	(Reversible Jaws) 2-ton, 2/3-Jaw; 0,6 kg (Reversible Jaws)
1024	1024	83	152	<sup>9</sup> / <sub>16</sub> –20 x 176 mm	Upper7,9	Upper 9,5	5-Ton, 2-Jaw; 0,8 kg
Delet Delet	1000				Lower 6,4	Lower 19,1	(Reversible Jaws)
	1026	83	178	9/18-20 x 176 mm	Upper 7,9	Upper 9,5	5-Ton, 2/3-Jaw; 1,3 kg
V 1 7 V 16 2	1025	140	152	9/16 <b>–</b> 20 x 176 mm	Lower 6,4 Upper7,9	Lower 19,1 Upper 9,5	(Reversible Jaws) 5-Ton, Long 2-Jaw;
1025	1023	140	132	716 <del>-</del> 20 X 176 IIIII	Lower 6,4	Lower 19,1	(Reversible Jaws) 0,9 kg
1010 / 17 1011 / 181	1027	140	178	<sup>9</sup> /₁₅–20 x 178 mm	Upper 7,9	Upper 9,5	5-Ton, Long 2/3-Jaw;
(1) (1)	1027	140	110	/10 20 X 170 Hilli	Lower 6,4	Lower 19,1	(Rev. Jaws) 1,5 kg
1035	1035	127	229	11/16-18 x 229 mm	Upper7,9	Upper 25,4	7-Ton, 2-Jaw;
1035					Lower 8,7	Lower 25,4	(Reversible Jaws) 2 kg
	1037	127	267	<sup>11</sup> / <sub>16</sub> –18 x 229 mm	Upper 7,9	Upper 25,4	7-Ton, 2/3-Jaw;
( ) ( )					Lower 8,7	Lower 25,4	(Rev. Jaws) 2,8 kg
1036 1038	1036	222	241	<sup>11</sup> / <sub>16</sub> –18 x 229 mm	8,7	25,4	7-Ton, Long 2-Jaw; 2,3 kg
(1) (1)	1038	222	279	<sup>11</sup> / <sub>16</sub> <b>–18</b> x 229 mm	8,7	25,4	7-Ton, Long 2/3-Jaw; 3,3 kg
- 0 - 0	1039	279	318	13/16-16 x 305 mm	14,3	25,4	13-Ton, 2-Jaw;
							4,8 kg
	1040	387	279	<sup>13</sup> / <sub>16</sub> –16 x 305 mm	14,3	25,4	13-Ton, Long 2-Jaw; 5,9 kg
	1041	279	356	13/16-16 x 305 mm	14,3	25,4	13-Ton, 2/3-Jaw;
							6,7 kg
1039/1040 1041/1042	1042	387	432	<sup>13</sup> / <sub>16</sub> –16 x 305 mm	14,3	25,4	13-Ton, Long 2/3-Jaw;
							8,3 kg

<sup>•</sup> For puller piece part identification, consult factory.

<sup>•</sup> Available standard 17.5 ton & 25 ton mechanical jaw pullers, consult factory.

#### **PUSH-PULLERS®**

Mechanical 10, 17 <sup>1</sup>/<sub>2</sub>, & 30 Ton Cap. FOR REMOVING AND INSTALLING GEARS, BEARINGS, PULLEYS AND OTHER PRESS-FITTED PARTS.

No. 927 - 10-Ton Capacity can be used with No. 1123 bearing pulling attachment or No. 679 pulley pulling attachment. May also be used with Nos. 1150, 1151, 1152, or 1153 internal pulling attachments.

No. 938 - 171/2-Ton Capacity can be used with Nos. 1124 and 1130 bearing pulling attachment or Nos. 679 and Bearing Pulling 680 pulley pulling attachment. May also be used with Nos. 1150, 1151, 1153, or 1166 internal pulling attachments.

No. 939 - 30-Ton Capacity can be used with Nos. 1126 and 1127 bearing pulling attachment or No. 680 pulley pulling attachment (two 8012 adapters are required to connect 680 to puller). Can be used with No. 1165 internal pulling attachments.



Attachment

#### **ASSEMBLING THE TOOL TO APPLY PUSHING OR PULLING FORCE:**


- 1. Determine if you want the tool's forcing screw to push or pull.
- 2. To exert pushing force, the forcing nut is installed beneath the cross block, as shown on left.
- 3. To cause the forcing screw to pull, the forcing nut is placed on top of the cross block.

Spread -

4. The slididng plates must always be placed on the opposite side of the cross block from the forcing nut.

#### Selection and capacity rating -

Each Push-Puller's specified tonnage "capacity" is determined using its standard legs in tension. Using longer legs, or a setup in which the legs are in compression, will reduce the "capacity". Always select the largest "capacity" puller and the shortest legs that will fit the job.



92	<b>27</b> M	Max.				
	Reach	Spread	Screw	Size	Notes / Weight	
927	210 mm	54 - 184 mm	³/4 <b>"-1</b> 6 x 305 mm			s threaded $5/8$ "–18. No. 1100 legs uded. Wt., 3,2 kg.
	Order No.	Leg Length & Wt.		Order No.	Leg Length & \	Wt.
	1103	121 mm, 🚜 0,45 kg 🖷		1102	298 mm, 1 kg	W 100
	1100*	171 mm, 🚛		1101	400 mm,	U
Д 🐧 Д		0,7 kg 👊			1,5 kg	01   1

Extra Legs (pair) for No. 927 Push-Puller (Reach equals leg length plus 50,8 mm with leg end caps.)


	938	1	Max.				
		Reach	Spread	Screw	Size	Notes / Weight	
938		282 mm	79–298 mm	1"-14 x 336 mm	Leg ends thre included. Wt.,		o. 1106 legs and No. 24827 leg ends
9 8	2	Order No.	Leg Length & V	Vt.	Order No.	Leg Length & V	Vt.
	T	1107	114 mm		1105	572 mm	300
			1,1 kg			4,1 kg	
		1106*	241 mm		1108	762 mm	
1 .	Į.		2 kg			5,2 kg	
——Spread	<u> </u>	1104	419 mm				
Opreda			3kg				

Extra Legs (pair) for No. 938 Push-Puller (Reach equals leg length plus 50,8 mm with leg end caps.)



	939		Max.				
		Reach	Spread	Screw	Size I	Notes / Weight	
939		267 mm	178–413 mm	1¹/2"-12 x 438 mm	Leg ends thre		o. 1109 legs and No. 28390 leg
9 5		Order No.	Leg Length & W	t.	Order No.	Leg Length & V	Wt.
ATT	T	1109*	203 mm		1111	711 mm	
Reach			3,6 kg			10 kg	0
		1110	457 mm	cui (			
V ii   Spread	9		6,8 kg				
Spread	_	Extra Legs	(pair) for No. 939	Push-Puller (Reach equa	ıls leg length plu	s 66,7 mm with	leg end caps.)

**CAUTION** – These attachments may not withstand the full tonnage of the pullers they are used with. The shape and condition of the part being pulled affects the tonnage at which the jaws may slip off. Always select the largest attachment which will fit behind the part being pulled (See page 132).



PULLING ATTACHMENTS

Jaw Spreads Bearing & Pulley

Fed. Spec.	: GGG-P-00781-D
------------	-----------------

	Jaw					
Order No.	Spread (mm)	Reach (mm)	A (in. — thd.)	B (in. – thd.)	Wt. (kg)	Application
1153	38,1–127	54	1–14	<sup>5</sup> /8–18	1,9	Use with Nos. 927 and 938 Push-Pullers,
1150	38,1–152	102	1–14	<sup>5</sup> /8–18	2	
1151 1152	38,1–178 38,1–152	133 102	1–14	5/8 <b>–18</b> 5/8 <b>–18</b>	2 1,6	Use with Nos. 927 and 938 Push-Pullers, 1155 and 1156
	33,1 132	102		7 0 10	1,0	slide hammer pullers, or 24832 and 24833 puller screw.
1154	38,1–152	102	1–8	<sup>5</sup> / <sub>8</sub> –18	2	Use with No. PPH17.
1165	76,7–229	149	11/2-12	1–14	6,1	Use with No. 939 Push-Puller.
1166	76,2–229	149	11/4-7	1–14	6,1	Use with No. PPH30.
	Puller Screws					
24832	349 mm long	<sup>5</sup> /8–18	0,5			Use with Nos. 1150, 1151, 1152, and 1153.
24833	140 mm long	<sup>5</sup> / <sub>8</sub> –18	0,2			Use with Nos. 1150, 1152, and 1153.

• 24832 & 24833 acts as a regular forcing screw when threaded directly into block of pulling attachment.



Spread |

- "Knife-like" edges fit behind bearings and other hard-to-grip parts for easy removal, even where clearance is limited.
- Usable with both Grip-O-Matic® jaw type pullers and Push-Pullers®.
- All puller blocks are made from forged alloy steel.



Attachment clamps down into V-groove to distribute load. Use with Grip-O-Matic® pullers or Push-Pullers.



Cross section

- $\mathbf{X}$  = Thread of tapped hole in adapter.
- $\mathbf{Y} = \mathbf{D}$ istance between adjusting screws.



										<u> </u>
	Max.									"Knife-like" Flat back edges surface
Order	Spread	X	Y	A	В	C	D	E	Wt.	
No.	(mm)	(in.)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(kg)	Application - (Use with Puller Nos.)
1121	6,4-22,2	5/16-18	43	11,1	3,2	12,7	34,9	50,8	0,3	1020, 1022, and 1023.
1122	3,2-51	³/s <b>–1</b> 6	62	11,1	4,0	15,9	50,8	69,9	0,6	1024, 1025, 1026, 1027, 7392 and 7393.
1123	9,5-117	<sup>5</sup> /8–18	111	22,2	9,5	25,4	88,9	114,3	2.3	1035, 1036, 1037, 1038, and 927.
1124	12,7-133	5/s <b>-18</b>	152	34,9	11,1	31,8	127	158,8	5,4	1039, 1040, 1041, 1042, PH172, PPH17, and 938.
1126	16-203	1-14	181	34,9	17,5	34,9	146,1	190,5	9	1047, 1043, and 939.
1127	19-340	1-14	260	44,5	17,5	44,5	158,8	215,9	18,8	1047, 1073, and 939.
1128	127-327	13/4-12	330	44,5	19,1	57,2	327	406	45,4	PH553C, and PPH50. (When using 1128 with PPH50, two
										8024 adapters are required to connect PPH50 to the puller tees.)
1130	12,7-219	5/s <b>-1</b> 8	152	34,9	11,1	31,8	127	158,8	5,4	1039, 1040, 1041, 1042, PH172, PPH17, and 938.
			V-belt	pulley p	ulling at	tachme	ents			
679	45-149	⁵/₅–18	152						2	1035, 1036, 1037, 1038, and 927.
680	42,3-254	5/s <b>-1</b> 8	257						10,1	1039, 1040, 1041, 1042, 1047, PH172, PPH30* and 938.
										(When using 680 with PPH30, two 8012 adapters are required.)



# **PULLER SETS**

Manual 10 & 17 ½ Ton

**10 ton manual puller set –** This puller set is just what you need for removing gears, bearings, etc. Includes pullers, attachments, and many accessories.





17½ ton manual puller set – The pullers and accessories in this set can be used for hundreds of applications including quick and easy maintenance involving removal and replacement of press-fit parts.

Manual Puller Set No. Order No.	Set Contents	Pullers	Set Contents	Accessories
IPS10M	927	10 ton capacity Push-Puller® with 171 mm legs	8075	Step plate adapter set
10 ton capacity	1023	2 ton combination 2/3-jaw puller	8044	Female threaded adapter set
Wt., 24 kg.	1026	5 ton combination 2/3-jaw puller	8035	Female threaded adapter: ½"–20 x %"–18
	1027	5 ton combination 2/3-jaw puller	1151	Bearing cup pulling attachment
	1037	7 ton combination 2/3-jaw puller	1121	Bearing pulling attachment
	1178	Slide hammer set	1122	Bearing pulling attachment
			1123	Bearing pulling attachment
			1101	400 mm long puller legs for 927 (pr.)
IPS17M	938	17½ ton capacity Push-Puller® with 241 mm legs	8075	Step plate adapter set
17 <sup>1</sup> / <sub>2</sub> ton capacity	1027	5 ton combo 2/3-jaw puller, with long jaws	1105	572 mm legs for 938
Wt., 52,7 kg.	1037	7 ton combination 2/3-jaw puller	1130	Bearing pulling attachment
	1041	13 ton combination 2/3 jaw puller	1151	Bearing cup pulling attachment
	1045	17½ ton 3-jaw puller	8038	Female adapter: %"–18 F. x ¾"–16 F. (2)



## **PULLER ADAPTERS**

Specialty Metric

# Female threaded adapters - Use these adapters on the ends of Push-Puller<sup>®</sup> forcing screws, legs, or slide hammers in the removal and installation of shafts, axles, and housings.

**Set No. 8044 –** consists of a set of 6 adapters (Nos. 8037-8042)

	Order No.	Female End "A"	Female End "B"	Order	Female No.	Female End "A"
	8035*	1/2"-20	<sup>5</sup> /8" <b>-18</b>	8040	<sup>5</sup> /8" <b>-1</b> 8	1"-14
	8036*	1"-14	1"-14	8041	<sup>5</sup> /8" <b>-1</b> 8	11/8"-12
	8037	<sup>5</sup> /8" <b>-18</b>	5/8"-18	8042	<sup>5</sup> /8"–18	11/4"-12
₹	8038	<sup>5</sup> /8"–18	<sup>3</sup> / <sub>4</sub> "–16	8043*	<sup>5</sup> /8" <b>-1</b> 8	11/2"-12
	8039	5/8"-18	<sup>7</sup> /s14			

Note: All adapters available separately.

\*Not included in set No. 8044. Order separately.

• Male-female threaded adapters – These adapters are used on ends of Push-Puller® legs, with forcing screws or slide hammers to assist in pulling shafts, bearing caps, pinions, and many other parts.

	Order No.	Female End	Male End	Length (mm)		Order No.	Fema <b>l</b> e End	Male End	Length (mm)
	8000	<sup>5</sup> /8"–18	¹/4" <b>-</b> 20	57,2		8015	<sup>5</sup> /8 <b>"-18</b>	3/4"-10	57,2
<u>a</u> <u> </u> a	8001	<sup>5</sup> /8"–18	5/16"-18	57,2	ı	8016	1"-14	3/4"-10	63,5
	8002	<sup>5</sup> /8"–18	7/16"-14	57,2	ı	8017	5/8"-18	<sup>7</sup> /8"–14	57,2
	8003	<sup>5</sup> /8"–18	<sup>7</sup> / <sub>16</sub> "–20	57,2		8018	5/8"-18	<sup>7</sup> /8 <b>"-</b> 9	57,2
	8004	<sup>5</sup> / <sub>8</sub> "–18	<sup>3</sup> / <sub>8</sub> "–24	57,2		8019	<sup>5</sup> / <sub>8</sub> "–18	1"-14	57,2
	8005	<sup>5</sup> /8"–18	³/8 <b>"-1</b> 6	57,2		8020	1"–8	5/8"-18	76,2
	8006	<sup>5</sup> /8" <b>-18</b>	<sup>1</sup> / <sub>2</sub> "–20	57,2		8021	1"–8	1"-14	76,2
	8007	<sup>5</sup> / <sub>8</sub> "–18	1/2"-13	57,2		8022	<sup>5</sup> /8 <b>"-18</b>	1/8" pipe	57,2
	8008	<sup>5</sup> /8"–18	9/16"-18	57,2		8023	11/4"-12	1"-14	114,3
	8009	<sup>5</sup> /8"–18	9/16"-12	57,2		8024	11/4"-12	13/4"-12	114,3
Fed. Spec.:	8010	<sup>5</sup> /8"–18	<sup>5</sup> /8" <b>-11</b>	57,2		8025	11/4"-7	<sup>5</sup> /8"–18	101,6
GGG-P-00781-D	8011	1"-14	5/16"-11	63,5		<b>8027</b>	11/4"-7	1"-14	101,6
	8012	1"-14	<sup>5</sup> /8" <b>-18</b>	81	T	8028	1 <sup>5</sup> /8"-5 <sup>1</sup> / <sub>2</sub>	1"–8	101,6
	8013	<sup>5</sup> /8"–18	<sup>3</sup> / <sub>4</sub> "–16	57,2		8029	1 <sup>5</sup> /8"-5 <sup>1</sup> / <sub>2</sub>	1"-14	101,6
	8014	1"–14	3/4"-16	63,5		Note: N	los. 8000–802	9 – each sold	individua <b>ll</b> y.

• Step plate adapter sets – Power Team step plate adapters are necessary for pulling and installing bearings, gears, or other parts on hollow shafts or housings. Puller screw forces against step plate adapter, as shown at right. May be used with Power Team jaw-type pullers, Push-Pullers® and shop presses.

**Set No. 8075** – set of 11 adapters (Nos. 8057-8067). **Set No. 8076** – set of 6 adapters (Nos. 8068-8073).

		Set No. 807	75	;	Set No. 8075	;	Set No. 8076				
	Order No.	Dia."A" (mm)	Dia""B" (mm)	Order No.	Dia."A" (mm)	Dia""B" (mm)	Order No.	Dia."A" (mm)	Dia."B" (mm)		
<b>□</b>	8057	25,4	19,1	8063	47,5	38,1	8068	66,5	53,8		
A ->	8058	28,4	22,1	8064	50,8	41,1	8069	69,9	57,2		
	8059	31,8	25,4	8065	53,8	44,5	8070	72,9	60,3		
B →	8060	34,8	28,4	8066	60,2	47,5	8071	76,2	63,5		
	8061	41,1	31,8	8067	63,5	50,8	8072	82,6	69,9		
©	8062	44,5	34,8				8073	88,9	76,2		

• **Shaft protector set --** Power Team shaft protectors are designed to protect shaft centers from distortion when extreme pressures are applied with jaw-type pullers or Push-Pullers®. Shaft protectors are inserted between the end of the puller screw and the shaft.

**Set No. 8056** - Set of 6 shaft protectors (Nos. 8050 thru 8055).






# SLIDE HAMMER PULLERS



**Blind hole puller set** — Removal of bearings, bushings, sleeves and other friction-fitted parts from blind holes can now be accomplished with ease. Set provides selection of expanding collets 8 to 44,5 mm I.D. Collet is placed through bore of part to be removed, then expanded with actuator pin so that lips of collet secure a positive grip for pulling. Pulling force is exerted by means of a forcing screw and bridge assembly or with a slide hammer.

**No. 981** - Blind-hole puller set with slide hammer, forcing screw, bridge, actuator pins, collets, and storage box. Wt., 9,5 kg.



Order No.	Desc	ription	Order No.	cription		
24835	Forcin	g Screw	28253	Actuator Pir	n (5 mm dia.)	
24836	Forcing	Screw Nut	28256	Actuator Pin	(12,7 mm dia.)	
22185	Hamme	er 1,1 kg.	41331	Br	idge	
208627	Shank & Tee	Bar Assembly	28323GY8	al Box		
28250	Actuator Pin	(3,2 mm dia.)	10419	Meta	Metal Box	
Order No.	Inch Range	MM Range	Order No.	Inc Range	MM Range	
33856*	5/16" to 3/8"	8 to 9.5	33861**	3/4" to 7/8"	19.1 to 22.2	
33857*	3/8" to 7/16"	9.5 to 11.1	33862**	<sup>7</sup> / <sub>8</sub> " to 1"	22.2 to 25.4	
33858**	7/16" to 1/2"	11.1 to 12.7	33863***	1" to 11/4"	25.4 to 31.7	
33859**	1/2" to 5/8"	12.7 to 15.9	33864**	1 <sup>1</sup> / <sub>4</sub> " to 1 <sup>1</sup> / <sub>2</sub> "	31.7 to 38.1	
33860**	5/8" to 3/4"	15.9 to 19.1	33865***	11/2" to 13/4	38.1 to 44.4	

\*Use with 3 mm actuator pin. \*\*Use with 4,8 mm actuator pin. \*\*\*Use with 12,7 mm actuator pin


**Slide hammer puller set** – This very handy set is ideal for those close-quarter, inside pulling jobs. Very practical for pulling motor, generator, and magneto bearings. Also good for removing small-bore bushings, bearings, and oil seals.

No. SS2 - Slide hammer puller set. Wt., 2,6 kg.

1		Inside :	Spread
	Jaw Set	Min. (mm)	Max. (mm)
	001	()	(111111)
-	1172	12,7	50,8
	1174	12,7	34,9

**Slide hammer puller set** – This useful set contains a reversible-jaw slide hammer puller with a 1,1 kg sliding hammer plus an assortment of special jaws (3 of each size) and adapters. In this set, you get all the versatility you demand of a slide hammer puller.

No. 1178 - Slide hammer puller set with 1,1 kg. sliding hammer. Wt., 6,3 kg.



		2-Jaw Sp	read	3-Jaw Spread					
	Ins	side	Out	side	ln:	side	Out	side	
Jaw	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	
	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	(mm)	
44195	38,1	114,3	19,1	127	38,1	120,7	25,4	114	
32054	19,1	60.3	_	_	25,4	69.9	_	_	
44148	69,9	139.7	19,1	191	82,6	158,8	25,4	159	
34698	31,8	88,9	25,4	114	38,1	108	38,1	114	

#### Sliding hammers only -

**No. 22185 –** 1,1 kg sliding hammer.

**No. 34331 -** 2,3 kg sliding hammer.







**Bearing cup remover –** The 7136 is perfect for pulling internal bearing cups, seals, bushings, etc. Jaw spread – 23,8 to 82,6 mm, reach to 88,9 mm. Use with any slide hammer having  $^{5}/_{8}$ "-18 thread (Power Team 1155, 1156 or 927 Push-Puller®).

7136

No. 7136 - Universal bearing cup remover. Wt., 0,7 kg.

**Pilot bearing pullers** -These very versatile pullers are built especially for inside pulling jobs, and particularly for removing flywheel pilot bearings on machines and construction vehicles. Also very practical for pulling motor, generator and magneto bearings.

**Special slide hammer puller –** Ideal for pulling jobs in very close quarters, as in removal of small-bore bushings,

removal of small-bore bushings, bearings, oil seals, etc. Internal pulling attachment has jaw spread of 12,7 to 35 to 35 to 35 to 36 to 37 to 37 to 37 to 37 to 38,1



No. 1174 - Puller head, less slide hammer.

**Basic slide hammer units** – Compatible with internal pulling attachment (see page 198). Compatible with threaded adapters (see page 204-205). 610 mm length, <sup>5</sup>/<sub>8</sub>"–18 threaded end.


No. 1155 - Basic slide hammer unit with 2,3 kg hammer. Wt., 3,3 kg.

No. 1156 - Basic slide hammer unit with 1,1 kg hammer. Wt., 2,2 kg.

**Reversible-jaw slide hammer pullers** – Ideal for pulling gears, bearings, outer races, grease retainers, oil seals, etc. Two or three jaws may be used and positioned for "inside" or "outside" pulling jobs. Both have  $^{5}/_{8}$ " – 18 threaded end so attachments and adapters may be used.

**No. 1176** – Slide hammer puller with 1,1 kg hammer, 27241 two-way head and 34698 jaws. Wt., 3,3 kg

No. 1177 - Same as 1176 but with 2,2 kg hammer. Wt., 4,8 kg









		2 Jaw	/ Spread		3 Jaw Spread						
Order No.	In Min. (mm)	side Max. (mm)	Out: Min. (mm)	side Max. (mm)	Ins Min. (mm)	ide Max. (mm)	Outs Min. (mm)	side Max. (mm)	Prod. Wt. (kg)	Overall Length (mm)	
1176	31,8	88,9	25,4	114	38,1	108	38,1	114	3,6	686	1176
1177	31,8	88,9	25,4	114	38,1	108	38,1	114	4,8	686	1177

**Slide hammer pullers with cup pulling attachments –** These combine a basic slide hammer with No. 1152 internal pulling attachment for removing oil seals, outer races, and bearing cups from blind holes.

No. 1157 - Slide hammer puller consisting of 1156 slide hammer and 1152 internal pulling attachment.

**No. 1158 –** Same as 1157 but with 1155 slide hammer.

Order No.	Reach Max. (mm)	Spread Min. (mm)	Spread Max. (mm)	Prod. Wt. (kg)	Overall Length (mm)	
1157	102	38,1	152	4,5	711	1158
1158	102	38,1	152	5,6	711	



# HYDRA GRIP-O-MATIC®

Use with 2 & 3

Jaw Pullers

6 to 30 Ton











# A SELF CONTAINED PULLING SYSTEM IN A COMPACT PACKAGE.

- You get the world's most copied puller design; the harder the pulling force, the tighter the jaws grip for secure holding force.
- Power Team pullers are tested for top performance and reliability at maximum capacity and jaw spread.
- Removing a wide variety of gears, bearings, bushings, pulleys and other press-fitted parts becomes a routine task.
- Easily metered release valve control knob.
- Spring loaded live centering cone.
- Bladder type oil reservoir.
- Rapid adjustment.
- Use with 2 or 3 jaws.
- Supplied with a sturdy storage/carrying case.
- Features Power Team's exclusive Marathon Limited Lifetime Warranty.





These pullers are ideal for pulling a wide variety of press-fitted parts including bushings, bearings, wheels, gears and pulleys. Applications can be found in a wide variety of industries as well. Grip-O-Matic® pullers have been rigorously tested for top performance and reliability. PH82K is a complete pulling system which includes a hydraulic power module, 2-way puller head, jaws, legs and bearing splitter attachment; all contained in a convenient carrying case.





PH303C







Cyl. Cap. (tons)	Order No.	Rea Studs (mm)	ach Jaws (mm)	Min. Reach (mm)	Max. Studs (mm)	Spread Jaws (mm)	Stroke (mm)	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (in.)	Wt. (kg)
6	PH63C	_	152	_	_	200	80	11	6,4	22	83	22	_	4,9
8	PH83C	_	190	_	_	249	80	11	9,5	25,4	83	22	_	6,6
15	PH113C	_	229	_	_	280	80	14,3	9,5	29	83	29	_	8,0
30	* PH303C	_	375	_	_	540	110	27	36.5	38	170	54	_	32.3
8	PH82K	266,7	207	125	300	245	80	52	25,4	16	83	22 5/	/8-18 UNF	9,5
11	** HST11S	_	150	_	_	102-410	80	_	_	_	65	29	_	14,5

- \* PH303C includes protective blanket & storage case
- \*\* Max bar size 60mm

#### **PULLER**

Accessories

**Hydra Grip-O-Matic® puller accessory kits** – K82 accessory kit for the Hydra-Grip-O-Matic® puller No. PH83C. Includes 2-way puller head, 2 jaws, 2 threaded legs and sturdy carrying/storage case.

No. K82 — Accessory kit for PH83C Grip-O-Matic® hydraulic puller. K83 2/3 way head accessories kit for a Hydra Grip-O-Matic® puller No. PH83C. Includes 2/3 way puller head, 3 jaws, 3 threaded legs and sturdy carrying/storage case.

No. K83 - Accessory kit for PH83C Grip-O-Matic® hydraulic puller.



**Puller Accessory converts PH113C into a Hydraulic Straightening Tool –** Portable...Good for straightening mechanical shafts, round bars, etc. Simply remove pump and cylinder from puller head and insert them into the straightening tool accessory. This product is widely used in steel mills, wire roll companies, wire extruding companies, textile industry, and any straightening situation where portability and power are required. Contoured heat-treated shaft adapter included.

No. HST11 - Spread: 89 to 410 mm, Reach: 150 mm. Wt., 9,5 kg.




Long jaw set for PH83C and PH113C Grip-O-Matic® pullers — This long jaw set is the perfect addition to the PH83C or PH113C Grip-O-Matic® hydraulic pullers. The extra long jaws give you the added capability of pulling a wider variety of parts. Jaw capacity is 8 tons when used with the PH83C puller; 15 tons when used with the PH113C puller.

No. 1188 — Spread: 280 to 317 mm, Reach: 317mm.



#### **PULLERS**

Hydraulic 5, 10, 17½, 30 & 50 Ton



- Remove gears, bearings, and other press-fitted parts with speed and ease.
- Broad capacity range of 5, 10,  $17^{1}/_{2}$ , 30 and 50 tons.
- 5 and 10 ton sets include: single-acting, spring return hydraulic cylinder with hose, coupler and dust cap; single-speed hydraulic hand pump; puller.
- 17½, 30 and 50 tons sets include: Power-Twin® single acting, spring return hydraulic cylinder with hose, coupler and dust cap; single-speed hydraulic hand pump; puller, adjusting screw and crank.
- Hydraulic cylinder of all models is readily removable from puller for use with pump in other hydraulic applications. You get maximum maintenance versatility for your investment.

#### 5 ton capacity, 2/3 jaw puller -

**No. PH53C** – Combination 2-jaw/3-jaw puller set. Includes 1057 5 ton puller, RPS55 hydraulic set (C55C cylinder, P12 700 bar hand pump, fittings, coupler, and 1,8 m hose), and 309874 pushing adapter. I Wt., 9,1 kg.

**No. PH53CR** – Combination 2-jaw/3-jaw puller set. Includes 1057 5 ton puller, C55C cylinder, and 309874 pushing adapter. Wt., 5,5 kg


No. 1057 - 5 ton cap. 2-jaw/3-jaw puller only. Wt., 3,5 kg.

#### Available components -

**No. 309874** – 15,9 mm diameter pushing adapter. (Included with PH53C and PH53CR hydraulic puller sets.) Wt., 0,3 kg.

No. 309875 - 22,2 mm diameter pushing adapter. Wt., 0,3 kg.

**No. 47997** – 2-way/3-way puller head. (Can be used to convert No. 1038 7 ton manual puller into a 5 ton hydraulic puller.) Wt., 1,1 kg.



Fed. Spec.: GGG-P-00781-D

#### 10 ton capacity, 2/3 jaw puller -

**No. PH103C** – Combination 2-jaw/3-jaw puller; 10 ton capacity. Set includes 1060 10 ton puller, RPS1010 cylinder and pump set, 202179 threaded adapter, and 34602 pushing adapter. Wt., 23,6 kg.

**No. PH103CR** – Combination 2-jaw/3-jaw puller, 10 ton capacity. Set includes 1060 10 ton puller, 202179 threaded adapter, 34602 pushing adapter, and C1010C cylinder only. (Pump and hose not included.) Wt., 14,5 kg.

**No. 1060 –** Combination 2-jaw/3-jaw puller only; 10 ton capacity. (Cylinder and pump set, hose, coupler, and adapter No. 202179 not included.) Wt., 7,7 kg.

**NOTE:** This puller may be used with any 10 ton single-acting cylinder having a  $2^{1}/4$ "-14 straight collar thread.







#### 17½ ton capacity, 2-jaw puller -

**No. PH172 –** 2-jaw puller with RT172 center-hole Power-Twin® cylinder, cylinder half coupler, P55 pump, 1,8 m hose, hose half coupler, 1"– 8 x 508 mm long adjusting screw, and adjusting crank. Wt., 27,7 kg.

No. 1064 - Puller only. (Cylinder, pump, hose, coupler, screw, and crank not included). Wt.,10 kg.

#### 17½ ton capacity, 3-jaw puller -

**No. PH173 –** 3-jaw puller with RT172 center-hole Power-Twin® cylinder, cylinder half coupler, P55 pump, 1,8 m hose, hose half coupler, 1"– 8 x 508 mm long adjusting screw, and adjusting crank. Wt., 34 kg.

No. PH173R - 3-jaw puller with screw and crank, and RT172 center-hole twin cylinder. Wt.,25,4 kg .

No. 1066 - Puller only. (Cylinder, pump, hose, coupler, screw, and crank not included). Wt., 16,3 kg.

#### 30 ton capacity, 3-jaw puller -

**No. PH303 –** 3-jaw puller with RT302 center-hole Power-Twin® cylinder, cylinder half coupler, P55 pump, 1,8 m hose, hose half coupler, 1<sup>1</sup>/<sub>4</sub>"– 7 x 610 mm lg. adjusting screw, and adjusting crank. Wt., 67,7 kg.

No. PH303R - 3-jaw puller with screw and crank, and RT302 center-hole twin cylinder. Wt., 59 kg.

No. 1074 - Puller only. (Cylinder, pump, hose, coupler, screw, and crank not included). Wt., 40,9 kg.

#### 50 ton capacity, 3-jaw puller -

**No. PH503 –** 3-jaw puller with RT503 center-hole Power-Twin® cylinder, cylinder half coupler, P55 pump, 1,8 m hose, hose half coupler, 1<sup>5</sup>/<sub>8</sub>" – 51/2 x 772 mm long adjusting screw, and adjusting crank. Wt., 130 kg.

No. 1080 - 3-jaw puller only. (Cylinder, pump, hose, coupler, screw, and crank not included). Wt., 86,7 kg.

#### **PULLER ONLY**

Order No.	Cap. (Tons)	Jaws	Jaw Reach (mm)	Jaw Spread (mm)	Jaw Thickness (mm)	Jaw Width (mm)	Wt. (kg)
1057	5	2/3	222	292	8,7	25	3,5
1060	10	2/3	381	432	14,3	25	7,7
1064	171/2	2	292	406	20,6	32,5	10
1066	$17^{1}/_{2}$	3	292	508	20,6	32,5	16,3
1074	30	3	494	864	28,6	41,3	40,9
1080	50	3	702	1.118	35,7	47,6	86,7

**ACAUTION:** Always use a 3-jaw puller where clearance permits in order to provide a more stable setup and a more even pulling force.



## PUSH-PULLERS®

Hydraulic 17<sup>1</sup>/<sub>2</sub>, 30 & 50 Ton

# THE POWER TO MAKE IMPOSSIBLE JOBS BECOME ROUTINE.


- Can apply a hydraulic pushing or pulling force, depending on how thepuller is set up.
- Each unit includes perfectly matched hydraulic components that can be detached from the Push-Puller® for other tasks requiring dependable Power Team power; assuring maximum return on your investment.
- Optional leg kits adapt your Push-Puller® to extra long or extra short reach.
- A wide variety of threaded adapters, bearing pulling attachments and internal pulling attachments can be used in combination with our Push-Pullers®.





#### **ASSEMBLING THE TOOL TO APPLY PUSHING OR PULLING FORCE:**

- 1. Determine if you want the tool's forcing screw to push or pull.
- To exert pushing force, the forcing nut is installed beneath the cross block, as shown on left.
- 3. To cause the forcing screw to pull, the forcing nut is placed on top of the cross block.
- The sliding plates must always be placed on the opposite side of the cross block from the forcing nut.



NOTE: L = leg length: 114; 241; 419; 572 and 762 mm subtract 124 mm from leg length to determine reach when using leg end caps.

**Selection and capacity rating** – Each Push-Puller's specified tonnage "capacity" is determined using its standard legs in tension. Using longer legs, or a setup in which the legs are in compression, will reduce the "capacity". Always select the largest "capacity" puller and the shortest legs that will fit the job.

**Power Twin® cylinder –** This unique center-hole cylinder powers each Push-Puller®. Puller screw runs right between the twin spring cylinder. A basic head allows you to change from a tapped hole to a plain hole by merely changing the head insert.

#### 171/2 ton capacity Push-Puller® -

**No. PPH17** – Push-Puller® with RT172 center-hole Power Twin® cylinder, cylinder half coupler, P55 pump, 9767 1,8 m. hose, 9798 hose half coupler, 419\* mm legs, 24827 leg ends, 1"-8 x 508 mm lg. adjusting screw and adjusting crank. Wt., 26,8 kg.

**No. PPH17R** – Same as above, but without P55pump, 9767 1,8 m. hose and 9798 hose half coupler. Wt., 18,2 kg.

**No. 1062** – Puller only. (Cylinder, pump, hose, coupler, screw and crank not included.) Wt., 9,1 kg.



Bearing pulling attachments: Nos. 1124 and 1130.

Pulley pulling attachment: **No. 679**. Internal pulling attachment: **No. 1154**.

Legs: **Nos. 1104, 1105, 1106, 1107 and 1108 -** Pair of legs for  $17^{1}/_{2}$ -ton "capacity" Push-Puller<sup>®</sup>.





**Leg Ends –** Upper leg ends are threaded  $^3/_4$ "-16. Lower leg ends are threaded  $^5/_8$ "-18 x 25 mm lg.

\* No. 1104 included in PPH17, PPH17R & 1062.



#### 30 ton capacity Push-Puller® -

No. PPH30 – Push-Puller® with RT302 center-hole Power Twin® cylinder, cylinder half coupler, P55 pump, 9767 1,8 m. hose, 9798 hose half coupler, 457\* mm legs, 28390 leg ends, 1¹/₄"-7 x 610 mm lg. adjusting screw and adjusting crank. Wt., 46,3 kg.

**No. PPH30R –** Same as above, but without P55 pump, 9767 1,8 m hose and 9798 hose half coupler. Wt., 37,2 kg.

**No. 1070 –** Puller only. (Cylinder, pump, hose, coupler, screw and crank not included.) Wt., 19,1 kg.

#### **USE WITH:**

Bearing pulling attachments. **No. 680** (Use two 8012 adapters to connect to puller.)
Pulley pulling attachment: **No. 679**.
Internal pulling attachment: **No. 1166**.
Legs: **Nos. 1109, 1110 and 1111 -** Pair of legs for 30 ton "capacity" Push-Puller®.

#### 50 ton capacity Push-Puller® -

**No. PPH50** – Push-Puller® with RT503 centerhole Power Twin® cylinder, cylinder half coupler, P55 pump, 9767 1,8 m hose, 9798 hose half coupler, 610\* mm legs, 15/s"-51/2 x 722 mm lg. adjusting screw and adjusting crank. Wt., 91,3 kg.


**No. PPH50R** – Same as above, but without P55 pump, 9767 1,8 m hose and 9798 hose half coupler. Wt., 82,2 kg.


**No. 1076** – Puller only. (Cylinder, pump, hose, coupler, screw and crank not included.) Wt., 48,1 kg.

#### **USE WITH:**


Bearing pulling attachments: Nos. 1128 and 1129.


Legs: **Nos. 1112 and 1113 -** Pair of legs for 50 ton "capacity" Push-Puller<sup>®</sup>.





\* No. 1110 included in PPH30, PPH30R & 1070.





\* No. 1112 included in PPH50, PPH50R & 1076.





### **PULLER SETS**

Hydraulic 17<sup>1</sup>/<sub>2</sub>, 30 & 50 Ton



Wooden storage box No. **3084350R9** is included with the sets listed on this page. 1.016L x 406W x 406D mm

1.016L x 406W x 406D mm Metal storage boxes also available (See page 151).




**No. IPS17 –** 17<sup>1</sup>/<sub>2</sub> ton capacity puller set. Includes hydraulics, pullers, wooden storage box and accessories listed below. Wt., 86,7 kg.

**No. IPS17B** – Puller set with MB5 metal box. Wt., 96,7 kg.



17½ ton hydraulic puller set - This set includes a 3-jaw puller and a Push-Puller. Ideal for heavy duty applications; put this set to work wherever large gears, bearings, wheels, pulleys, etc. are found.

**No. IPS17H –** 17<sup>1</sup>/<sub>2</sub> ton capacity hydraulic puller set. Includes hydraulics, pullers, wooden storage box and accessories listed below. Wt., 62,2 kg.



	CONTENTS OF	SET NO.	IPS17
Contents	Hydraulics	Contents	Accessories
P55	Single-stage hyd. hand	1154	Bearing cup pulling attach
	Pump assembly	1122	Bearing pulling attachment
RT172	17 <sup>1</sup> / <sub>2</sub> ton cylinder	1123	Bearing pulling attachment
	with threaded insert	1130	Bearing pulling attachment
9798	Hose half coupler		Threaded Adapters
9767	Hydraulic hose – 1,8 m	679	V-belt pulley pulling attachment
9670	Tee adapter	8005	<sup>5</sup> / <sub>8</sub> " – 18 F. x <sup>3</sup> / <sub>8</sub> " – 16 M. (2)
9059	Pressure gauge	8006	$^{5}/_{8}$ " – 18 F. x $^{1}/_{2}$ " – 20 M. (2)
	Pullers	8007	$^{5}/_{8}$ " – 18 F. x $^{1}/_{2}$ " – 13 M. (2)
1062	17 <sup>1</sup> / <sub>2</sub> ton cap. Push-Puller®	8010	<sup>5</sup> / <sub>8</sub> " − 18 F. x <sup>5</sup> / <sub>8</sub> " − 11 M. (2)
	with 419 mm legs		<sup>5</sup> / <sub>8</sub> " – 18 F. x <sup>3</sup> / <sub>4</sub> " – 16 M. (2)
24814	Speed crank		$^{5}/_{8}$ " – 18 F. x $^{3}/_{4}$ " – 10 M. (2)
32118	Adjusting screw		$^{5}/_{8}$ " – 18 F. x $^{7}/_{8}$ " – 14 M. (2)
201923	Pushing adapter		$\frac{5}{8}$ " - 18 F. x $\frac{7}{8}$ " - 9 M. (2)
1105	572 mm legs (pr)	!	<sup>5</sup> / <sub>8</sub> " – 18 F. x 1" – 14 M. (2)
1066	17 <sup>1</sup> / <sub>2</sub> ton 3-jaw hyd. puller	!	1" – 8 F. x <sup>5</sup> / <sub>8</sub> " – 18 M. (1)
1027	Combination 2/3-jaw puller	8021	1" – 8 F. x 1" – 14 M. (1)
41224	17 <sup>1</sup> / <sub>2</sub> ton 2-jaw puller head	8038	<sup>5</sup> / <sub>8</sub> " –18 F. x <sup>3</sup> / <sub>4</sub> "–16 F. (2)
24832	Puller screw	8044	Female threaded adapter set
1037	Combination 2/3-jaw puller	<del> </del>	Set of 6 shaft protectors (8050-8055)
1041	Combination 2/3-jaw puller	8075	Set of 11 adaptors (8057-8067)
28228	Cylinder cap		

	CONTENTS OF S	SET NO. IPS	17H
Contents	Hydraulics	Contents	Accessories
P55	Single-stage hydraulic	1154	Bearing cup pulling attach.
	hand pump assembly	1130	Bearing pulling attachment
RT172	17 <sup>1</sup> / <sub>2</sub> ton cylinder with	1105	572 mm legs (pr)
	threaded insert	24814	Speed crank
9798	Hose half coupler	28228	Screw cap
9767	Hydraulic hose – 1,8 m	32118	Adjusting screw
9670	Tee adapter	201454	Pushing adapter
9059	Pressure gauge	41224	2-jaw head for 1066
	Pullers		Threaded Adapters
1062	171/2 ton cap. Push-Puller	8020	1" $- 8 \text{ F. } \text{ x} \frac{5}{8}$ " $- 18 \text{ M. } (1)$
	with 419 mm legs	8038	<sup>5</sup> / <sub>8</sub> " - 8 F. x <sup>3</sup> / <sub>4</sub> " - 16 F. (1)
1066	17 <sup>1</sup> / <sub>2</sub> ton 3-jaw hyd. puller		





**30 ton capacity puller set** – Just what you need for those big jobs. Not only do you get a 30 ton hydraulic Push-Puller®, you also get a 2-jaw and 3-jaw hydraulic puller. Plus, many popular accessories and the hardware to tackle the big jobs right away.

**No. IPS30H** – 30 ton capacity hydraulic maintenance puller set. Includes hydraulics, pullers, wooden storage box and accessories listed below. Wt., 150 kg.

	CONTENTS OF S	SET NO. IP	S30H
Contents	Hydraulics	Contents	Pullers
P55	Single-stage hydraulic hand	1074	30 ton, 3-jaw hyd. puller
	pump assembly	41226	2-way head for 1074
RT302	30 ton cylinder with	1070	30 ton cap. hydraulic Push-
	threaded insert		Puller® with 457 mm legs
9798	Hose half coupler	1111	711 mm legs for 1070
9767	Hydraulic hose – 1,8 m	27198	Speed crank
9670	Tee adapter	28229	Screw cap
9059	Pressure gauge	34510	Pushing adapter
	Accessories	34758	Adjusting screw
8036	Female threaded adapters 1" – 14F. x 1" – 14F. (2)		
1166	Bearing cup pulling attach.		
1127	Bearing pulling attachment		



**Note:** Wooden storage box No. **3084380R9** is provided with the sets listed on this page. 1180L x 615H x 579D mm. Metal storage boxes also available (See page 151).

#### **50 ton capacity puller set -** For those really big jobs,

this 50 ton puller set is what you need. Just think of the jobs you can do with a 50 ton hydraulic Push-Puller®, a 2-jaw and a 3-jaw puller, both with a 50 ton capacity. Of course, you also get many versatile accessories and attachments.

**No. IPS50H** – 50 ton capacity hydraulic maintenance puller set. Includes hydraulics, pullers, wooden storage box and accessories listed below. Wt., 261 kg.

CONTENTS OF SET NO. IPS50H								
No.	Hydraulics	No.	Pullers					
P55	Single-stage hydraulic hand pump assembly		50 ton, 3-jaw hyd. puller 2-way head for 1080					
RT503	50 ton cylinder with threaded insert	1076	50 ton cap. hydraulic Push- Puller® with 610 mm legs					
9798	Hose half coupler	1113	864 mm legs for 1076					
9767	Hydraulic hose – 1,8 m	29595	Speed crank					
9670	Tee adapter	28230	Screw cap					
9059	Pressure gauge	34755	Pushing adapter					
	Threaded Adapters	32698	Adjusting screw					
8024	$1^{1}/_{4}$ " - 12F. x $1^{3}/_{4}$ " - 12M.		Accessories					
(2)		1128	Bearing pulling attachment					
8028	1 <sup>5</sup> / <sub>8</sub> " - 5 <sup>1</sup> / <sub>2</sub> F. x 1" - 8M.							
8029	1 <sup>5</sup> / <sub>8</sub> " - 5 <sup>1</sup> / <sub>2</sub> F. x 1" - 14M.							



▲ CAUTION: All the items shown may not withstand the full tonnage specified. Example: When an accessory with a 1 ton capacity is used with a 7 ton puller, the setup can be used only at a force of 1 ton.



### **PULLER SETS**

Hydraulic 17<sup>1</sup>/<sub>2</sub> & 30 Ton 17<sup>1</sup>/<sub>2</sub> & 50 Ton

IPS3017

17 $\frac{1}{2}$  and 30 ton capacity puller sets — These heavy-duty maintenance sets will more than pay for themselves, especially in saving you costly damage to parts. This set lets you tackle hundreds of applications where pushing and pulling are required.

**No. IPS3017** – 17<sup>1</sup>/<sub>2</sub> and 30 ton capacity manual and hydraulic puller set. Includes hydraulics, pullers, and accessories listed below. Wt., 244 kg.

No. IPS3017B - Puller set with MB8 metal box. Wt., 256 kg.




**Note:** Wooden storage box No. **3084360R9** is provided with this set. **1.016** L x 432 H x 610D mm. Metal storage boxes also available (See page 151).



2-jaw puller reaches through spokes of gear to grip hub. Hand pump supplies hydraulic power.




Flexible coupler is removed from electric motor shaft with 2-jaw puller.



Typical setup for removing sprocket drive pinion shaft. Puller screw is attached to shaft by threaded adapter. Shaft is now ready to be pulled out hydraulically.

▲ CAUTION: All the items shown may not withstand the full tonnage specified. Example: When an accessory with a 1 ton capacity is used with a 7 ton puller, the setup can be used only at a force of 1 ton.



	CONTENTS OF S	ET NO. JE	P\$3017
No.	Hydraulics	No.	Accessories
P55	Single-stage hyd. hand	24832	Special puller forcing screw
	pump assembly	8075	Step plate adapter set
RT172	17 <sup>1</sup> / <sub>2</sub> ton center-hole twin	8076	Step plate adapter set
	cylinder w/ threaded insert	8056	Shaft protector set
RT302	30 ton center-hole twin	679	Pulley pulling attachment
	cylinder w/ threaded insert	680	Pulley pulling attachment
9798	Hose half coupler	1154	Bearing cup pulling attach.
9767	Hydraulic hose – 1,8 m	1166	Bearing cup pulling attach.
9670	Tee adapter	1122	Bearing pulling attachment
9059	Pressure gauge	1123	Bearing pulling attachment
	Pullers Pullers	1126	Bearing pulling attachment
1062	$17^{1}/_{2}$ ton cap. hydraulic	1130	Bearing pulling attachment
	Push-Puller® w/419 mm legs		Threaded Adapters
1070	30 ton cap. hydraulic	8005	$\frac{5}{8}$ " - 18 F. x $\frac{3}{8}$ " - 16 M. (2)
	Push-Puller® w/457 mm legs	8006	$^{5}/_{8}$ " $-$ 18 F. x $^{1}/_{2}$ " $-$ 20 M. (2)
1066	17 <sup>1</sup> / <sub>2</sub> ton 3-jaw hyd. puller	8007	$\frac{5}{8}$ " - 18 F. x $\frac{1}{2}$ " - 13 M. (2)
1074	30 ton 3-jaw hyd. puller	8010	$\frac{5}{8}$ " - 18 F. x $\frac{5}{8}$ " - 11 M. (2)
41224	17 <sup>1</sup> / <sub>2</sub> ton 2-jaw puller head	8012	1" – 14 F. x <sup>5</sup> / <sub>8</sub> " – 18 M. (2)
41226	30 ton 2-jaw puller head	8013	$\frac{5}{8}$ " - 18 F. x $\frac{3}{4}$ " - 16 M. (2)
1027	Combination 2/3-jaw puller	8015	$\frac{5}{8}$ " - 18 F. x $\frac{3}{4}$ " - 10 M. (2)
1037	Combination 2/3-jaw puller	8017	$\frac{5}{8}$ " – 18 F. x $\frac{7}{8}$ " – 14 M. (2)
1041	Combination 2/3-jaw puller	8018	<sup>5</sup> / <sub>8</sub> " – 18 F. x <sup>7</sup> / <sub>8</sub> " – 9 M. (2)
43892	Long jaws (3) for 1037	8019	<sup>5</sup> / <sub>8</sub> " – 18 F. x 1" – 14 M. (2)
30902	Long jaws (3) for 1041	8020	1" – 8 F. x <sup>5</sup> / <sub>8</sub> " – 18 M. (1)
1105	572 mm legs for 1062	8021	1" – 8 F. x 1" – 14 M. (1)
1111	711 mm legs for 1070	8025	$1^{1}/_{4}$ " - 7 F. x $^{5}/_{8}$ " - 18 M. (2)
24814	Speed crank	8027	1 <sup>1</sup> / <sub>4</sub> " – 7 F. x 1" – 14 M. (2)
27198	Speed crank	8036	1" – 14 F. x 1" – 14 F. (2)
28229		8038	<sup>5</sup> / <sub>8</sub> " – 18 F. x <sup>3</sup> / <sub>4</sub> " – 16 F. (2)
28228		8044	Female threaded adapter set
	Adjusting screw		
	Adjusting screw		
34510	Pushing adapter		
201923	Pushing adapter		





17½ and 50 ton capacity puller sets — If your looking for a maintenance puller set that will handle a wide variety of applications, this is the one for you. The mechanical and hydraulic pullers and attachments are designed to handle most removing and installing jobs with a minimal amount of effort.

**No. IPS5017** –  $17^{1}/_{2}$  and 50 ton capacity manual and hydraulic puller set. Includes hydraulics, pullers, wooden storage box and accessories listed below. Wt., 405 kg.

No. IPS5017B - Puller set with MB16 metal box. Wt., 415 kg.

IPS501

	CONTENTS OF S	ET NO. IF	PS5017					
No.	Hydraulics	No.	Accessories					
P55	Single-stage hyd. hand	8075	Step plate adapter set					
	pump assembly	8076	Step plate adapter set					
RT172	17 <sup>1</sup> / <sub>2</sub> ton center-hole twin	8056	Shaft protector set					
	cylinder w/ threaded insert	1154	Bearing cup pulling attach.					
RT503	50 ton center-hole twin	1166	Bearing cup pulling attach.					
	cylinder w/ threaded insert	1122	Bearing pulling attachment					
9798	Hose half coupler	1123	Bearing pulling attachment					
9767	Hydraulic hose – 1,8 m	1126	Bearing pulling attachment					
9670	Tee adapter	1127	Bearing pulling attachment					
9059	Pressure gauge	1130	Bearing pulling attachment					
	Pullers	34479	Reducing adapter for 1166					
1062	17 <sup>1</sup> / <sub>2</sub> ton cap. hydraulic	10215	Hex nut; 3/4" - 16 (2)					
	Push-Puller® w/419 mm legs	24829	Short bolt					
1076	50 ton cap. hydraulic		Threaded Adapters					
	Push-Puller® w/610 mm legs	8005	$\frac{5}{8}$ " - 18 F. x $\frac{3}{8}$ " - 16 M. (2)					
1066	17 <sup>1</sup> / <sub>2</sub> ton 3-jaw hyd. puller	8006	$^{5}/_{8}$ " – 18 F. x $^{1}/_{2}$ " – 20 M. (2					
1080	50 ton 3-jaw hyd. puller	8007	$^{5}/_{8}$ " $-$ 18 F. x $^{1}/_{2}$ " $-$ 13 M. (2)					
41224	17 <sup>1</sup> / <sub>2</sub> ton 2-jaw puller head	8010	5/8" – 18 F. x $5/8$ " – 11 M. (2)					
50449	50 ton 2-jaw puller head	8013	$\frac{5}{8}$ " - 18 F. x $\frac{3}{4}$ " - 16 M. (2)					
1027	Combination 2/3-jaw puller	8015	<sup>5</sup> / <sub>8</sub> " - 18 F. x <sup>3</sup> / <sub>4</sub> " - 10 M. (2)					
1037	Combination 2/3-jaw puller	8019	<sup>5</sup> / <sub>8</sub> " – 18 F. x 1" – 14 M. (2)					
1041	Combination 2/3-jaw puller	8020	1" $- 8 \text{ F. } \text{ x}  ^{5}/_{8}$ " $- 18 \text{ M. } (1)$					
43892	Long jaws (3) for 1037	8021	1" – 8 F. x 1" – 14 M. (1)					
30902	Long jaws (3) for 1041	8023	1 <sup>1</sup> / <sub>4</sub> " - 12 F. x 1" - 14 M. (2)					
1105	572 mm legs for 1062	8028	$1^{5}/8" - 5^{1}/2$ F. x $1" - 8$ M. (1)					
1113	864 mm legs for 1076	8029	15/8" - 51/2 F. x 1" - 14 M. (1)					
24814	Speed crank	8038	<sup>5</sup> / <sub>8</sub> " – 18 F. x <sup>3</sup> / <sub>4</sub> " – 16 F. (1)					
29595	Speed crank	8044	Female threaded adapter set					

**28228** Screw cap

28230 Cylinder cap

**32118** Adjusting screw

32698 Adjusting screw34755 Pushing adapter


201923 Pushing adapter

**7392** Gear and pulley puller

**24833** Forcing screw for 7392



**Note:** Wooden storage box No. **3084360R9** is provided with this set. **1143** L x 572 H x 762D mm. Metal storage boxes also available (See page **151**).



Combination of 50 ton capacity Push-Puller and cup pulling attachment simplifies the removal of a final drive axle seal.



Hydraulically powered Push-Puller removes drive wheel. Pulling attachment is used to provide gripping surface.



3-jaw puller provides grip while hydraulic hand pump provides power to push shaft from housing. Shaft protector is used on end of puller screw.

▲ CAUTION: All the items shown may not withstand the full tonnage specified. Example: When an accessory with a 1 ton capacity is used with a 7 ton puller, the setup can be used only at a force of 1 ton.




## **PULLER SETS**

Hydraulic 17<sup>1</sup>/<sub>2</sub>, 30 & 50 Ton

17½, 30 & 50 ton capacity puller set — Here's the ultimate in industrial puller sets! You'll find a puller for just about every job. Included in this "master set" are  $17^{1}/_{2}$ , 30 and 50 ton hydraulics, along with an extensive assortment of pullers, attachments and adapters.

**No. IPS5317** –  $17^{1}/_{2}$ , 30 and 50 ton capacity manual and hydraulic puller set. Includes hydraulics, pullers, wooden storage box and accessories listed below. Wt., 572 kg.





Note: Wooden storage box
No. 3084400R9 is provided with this set.
1168L x 571H x 571D mm.
Metal storage boxes also available (See page 151).

▲ CAUTION: All the items shown may not withstand the full tonnage specified. Example: When an accessory with a 1 ton capacity is used with a 7 ton puller, the setup can be used only at a force of 1 ton.

	CONTENTS OF SET NO. IPS5317							
Contents	s Hydraulics	Contents	Accessories					
P55	Single-stage hyd. hand	28230	Screw cap					
. 00	pump assembly	32118	Adjusting screw					
P460	Two-stage hyd. hand pump	32698	Adjusting screw					
	w/ 3-way control valve	34758	Adjusting screw					
RT172	17 <sup>1</sup> / <sub>2</sub> ton center-hole twin	34510	Pushing adapter					
	cylinder w/ threaded insert	34755	Pushing adapter					
RT302	30 ton center-hole twin	201923	Pushing adapter					
	cylinder w/ threaded insert	8075	Step plate adapter set					
RT503	50 ton center-hole twin	8076	Step plate adapter set					
	cylinder w/ threaded insert	8056	Shaft protector set					
9798	Hose half coupler (2)	679	Pulley pulling attachment					
9767	Hydraulic hose – 1,8 m (2)	680	Pulley pulling attachment					
9670	Tee adapter	1154	Bearing cup pulling attach.					
9059	Pressure gauge	1166	Bearing cup pulling attach.					
	Pullers	1122	Bearing pulling attachment					
1062	17 <sup>1</sup> / <sub>2</sub> ton cap. hydraulic	1123	Bearing pulling attachment					
	Push-Puller® w/419 mm legs	1126	Bearing pulling attachment					
1070	30 ton cap. hydraulic	1127	Bearing pulling attachment					
	Push-Puller® w/457 mm legs	1128	Bearing pulling attachment					
1076	50 ton cap. hydraulic	1130	Bearing pulling attachment					
	Push-Puller® w/610 mm legs	34479	Reducing adapter					
1066	$17^{1}/_{2}$ ton 3-jaw hyd. puller	,	Threaded Adapters					
1074	30 ton 3-jaw hyd. puller	8005	$\frac{5}{8}$ " – 18 F. x $\frac{3}{8}$ " – 16 M. (2)					
1080	50 ton 3-jaw hyd. puller	8006	<sup>5</sup> / <sub>8</sub> " – 18 F. x <sup>1</sup> / <sub>2</sub> " – 20 M. (2)					
41224	17 <sup>1</sup> / <sub>2</sub> ton 2-jaw puller head	8007	<sup>5</sup> / <sub>8</sub> " – 18 F. x <sup>1</sup> / <sub>2</sub> " – 13 M. (2)					
41224 41226	17 <sup>1</sup> / <sub>2</sub> ton 2-jaw puller head 30 ton 2-jaw puller head	8010	<sup>5</sup> / <sub>8</sub> " – 18 F. x <sup>1</sup> / <sub>2</sub> " – 13 M. (2) <sup>5</sup> / <sub>8</sub> " – 18 F. x <sup>5</sup> / <sub>8</sub> " – 11 M. (2)					
41224 41226 50449	17 <sup>1</sup> / <sub>2</sub> ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head	8010 8012	<sup>5</sup> / <sub>8</sub> " – 18 F. x <sup>1</sup> / <sub>2</sub> " – 13 M. (2) <sup>5</sup> / <sub>8</sub> " – 18 F. x <sup>5</sup> / <sub>8</sub> " – 11 M. (2) 1" – 14 F. x <sup>5</sup> / <sub>8</sub> " – 18 M. (2)					
41224 41226 50449 1027	17 <sup>1</sup> / <sub>2</sub> ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller	8010 8012 8013						
41224 41226 50449 1027 1037	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller	8010 8012 8013 8015	$ \begin{tabular}{lllllllllllllllllllllllllllllllllll$					
41224 41226 50449 1027 1037 1041	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller	8010 8012 8013 8015 8017						
41224 41226 50449 1027 1037 1041 43892	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037	8010 8012 8013 8015 8017 8018						
41224 41226 50449 1027 1037 1041 43892 30902	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037	8010 8012 8013 8015 8017 8018 8019						
41224 41226 50449 1027 1037 1041 43892 30902 32136	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037 Long jaws (3) for 1041 Long jaws (3) for 1154	8010 8012 8013 8015 8017 8018 8019 8020	$ \begin{tabular}{lllllllllllllllllllllllllllllllllll$					
41224 41226 50449 1027 1037 1041 43892 30902 32136 1105	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037 Long jaws (3) for 1041 Long jaws (3) for 1154 572 mm legs for 1062	8010 8012 8013 8015 8017 8018 8019 8020 8021	$\begin{array}{l} {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm z''} - 13 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 11 \; {\rm M.} \; (2) \\ 1" - 14 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 18 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 10 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 9 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ 1" - 8 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 18 \; {\rm M.} \; (1) \\ 1" - 8 \; {\rm F.} \; {\rm X} \; 1" - 14 \; {\rm M.} \; (1) \\ \end{array}$					
41224 41226 50449 1027 1037 1041 43892 30902 32136 1105 1106	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037 Long jaws (3) for 1041 Long jaws (3) for 1154 572 mm legs for 1062 241 mm legs for 1062	8010 8012 8013 8015 8017 8018 8019 8020 8021 8023	$\begin{array}{l} {}^{5}/\!\!\mathrm{s}^{"} - 18\mathrm{F.}\mathrm{X}{}^{1}/\!\!\mathrm{s}^{"} - 13\mathrm{M.}(2) \\ {}^{5}/\!\!\mathrm{s}^{"} - 18\mathrm{F.}\mathrm{X}{}^{5}/\!\!\mathrm{s}^{"} - 11\mathrm{M.}(2) \\ {}^{1}\mathrm{l}^{"} - 14\mathrm{F.}\mathrm{X}{}^{5}/\!\!\mathrm{s}^{"} - 18\mathrm{M.}(2) \\ {}^{5}/\!\!\mathrm{s}^{"} - 18\mathrm{F.}\mathrm{X}{}^{3}/\!\!\mathrm{s}^{"} - 16\mathrm{M.}(2) \\ {}^{5}/\!\!\mathrm{s}^{"} - 18\mathrm{F.}\mathrm{X}{}^{3}/\!\!\mathrm{s}^{"} - 10\mathrm{M.}(2) \\ {}^{5}/\!\!\mathrm{s}^{"} - 18\mathrm{F.}\mathrm{X}{}^{3}/\!\!\mathrm{s}^{"} - 14\mathrm{M.}(2) \\ {}^{5}/\!\!\mathrm{s}^{"} - 18\mathrm{F.}\mathrm{X}{}^{7}/\!\!\mathrm{s}^{"} - 9\mathrm{M.}(2) \\ {}^{5}/\!\!\mathrm{s}^{"} - 18\mathrm{F.}\mathrm{X}{}^{7}/\!\!\mathrm{s}^{"} - 9\mathrm{M.}(2) \\ {}^{5}/\!\!\mathrm{s}^{"} - 18\mathrm{F.}\mathrm{X}1^{"} - 14\mathrm{M.}(2) \\ {}^{1}/\!\!\mathrm{l}^{"} - 8\mathrm{F.}\mathrm{X}5^{"}/\!\!\mathrm{s}^{"} - 18\mathrm{M.}(1) \\ {}^{1}/\!\!\mathrm{l}^{"} - 12\mathrm{F.}\mathrm{X}1^{"} - 14\mathrm{M.}(1) \\ {}^{1}/\!\!\mathrm{l}^{4}/\!\!\mathrm{l}^{"} - 12\mathrm{F.}\mathrm{X}1^{"} - 14\mathrm{M.}(2) \\ \end{array}$					
41224 41226 50449 1027 1037 1041 43892 30902 32136 1105 1106 1107	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037 Long jaws (3) for 1041 Long jaws (3) for 1154 572 mm legs for 1062 241 mm legs for 1062	8010 8012 8013 8015 8017 8018 8019 8020 8021 8023 8024	$\begin{array}{l} {}^{5}/8" - 18 \; F. \; X \; 1/2" - 13 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; X \; 5/8" - 11 \; M. \; (2) \\ {}^{1}" - 14 \; F. \; X \; 5/8" - 18 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; X \; 3/4" - 16 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; X \; 3/4" - 10 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; X \; 3/4" - 14 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; X \; 7/8" - 9 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; X \; 7/8" - 9 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; X \; 1" - 14 \; M. \; (2) \\ {}^{1}" - 8 \; F. \; X \; 5/8" - 18 \; M. \; (1) \\ {}^{1}'4" - 12 \; F. \; X \; 1" - 14 \; M. \; (2) \\ {}^{1}/4" - 12 \; F. \; X \; 1^{3}/4" - 12 \; M. \; (2) \\ {}^{1}/4" - 12 \; F. \; X \; 1^{3}/4" - 12 \; M. \; (2) \\ \end{array}$					
41224 41226 50449 1027 1037 1041 43892 30902 32136 1105 1106 1107 1109	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037 Long jaws (3) for 1041 Long jaws (3) for 1154 572 mm legs for 1062 241 mm legs for 1062 114 mm legs for 1062 203 mm legs for 1070	8010 8012 8013 8015 8017 8018 8019 8020 8021 8023 8024 8025	$\begin{array}{l} {}^{5}/\!\!s" - 18F.x{}^{1}/\!\!s" - 13M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{5}/\!\!s" - 11M.(2) \\ {}^{1}'' - 14F.x{}^{5}/\!\!s" - 18M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{3}/\!\!s" - 16M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{3}/\!\!s" - 10M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{3}/\!\!s" - 14M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{7}/\!\!s" - 9M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{7}/\!\!s" - 9M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{7}/\!\!s" - 14M.(2) \\ {}^{1}'' - 8F.x{}^{5}/\!\!s" - 18M.(1) \\ {}^{1}'' - 8F.x{}^{1}/\!\!s" - 14M.(1) \\ {}^{1}/\!\!4" - 12F.x{}^{1}/\!\!s" - 14M.(2) \\ {}^{1}/\!\!4" - 12F.x{}^{1}/\!\!s" - 12M.(2) \\ {}^{1}/\!\!4" - 7F.x{}^{5}/\!\!s" - 18M.(2) \\ \end{array}$					
41224 41226 50449 1027 1037 1041 43892 30902 32136 1105 1106 1107 1109	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037 Long jaws (3) for 1041 Long jaws (3) for 1154 572 mm legs for 1062 241 mm legs for 1062 114 mm legs for 1062 203 mm legs for 1070 711 mm legs for 1070	8010 8012 8013 8015 8017 8018 8019 8020 8021 8023 8024 8025 8027	$\begin{array}{l} {}^{5}/8" - 18 \; F. \; x \; 1/2" - 13 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; x \; 5/8" - 11 \; M. \; (2) \\ {}^{1}" - 14 \; F. \; x \; 5/8" - 18 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; x \; 3/4" - 16 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; x \; 3/4" - 10 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; x \; 3/4" - 14 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; x \; 7/8" - 9 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; x \; 7/8" - 9 \; M. \; (2) \\ {}^{5}/8" - 18 \; F. \; x \; 1" - 14 \; M. \; (2) \\ {}^{1}" - 8 \; F. \; x \; 5/8" - 18 \; M. \; (1) \\ {}^{1}" - 8 \; F. \; x \; 1" - 14 \; M. \; (1) \\ {}^{1}/4" - 12 \; F. \; x \; 1" - 14 \; M. \; (2) \\ {}^{1}/4" - 12 \; F. \; x \; 1^{3}/4" - 12 \; M. \; (2) \\ {}^{1}/4" - 7 \; F. \; x \; 5/8" - 18 \; M. \; (2) \\ {}^{1}/4" - 7 \; F. \; x \; 1" - 14 \; M. \; (2) \\ \end{array}$					
41224 41226 50449 1027 1037 1041 43892 30902 32136 1105 1106 1107 1109	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037 Long jaws (3) for 1041 Long jaws (3) for 1154 572 mm legs for 1062 241 mm legs for 1062 114 mm legs for 1062 203 mm legs for 1070 711 mm legs for 1070 864 mm legs for 1070	8010 8012 8013 8015 8017 8018 8019 8020 8021 8023 8024 8025 8027 8028	$\begin{array}{l} {}^{5}/\!\!s" - 18F.x{}^{1}/\!\!z" - 13M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{5}/\!\!s" - 11M.(2) \\ {}^{1}'' - 14F.x{}^{5}/\!\!s" - 18M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{3}/\!\!a" - 16M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{3}/\!\!a" - 10M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{3}/\!\!a" - 10M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{7}/\!\!s" - 14M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{7}/\!\!s" - 9M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{7}/\!\!s" - 9M.(2) \\ {}^{5}/\!\!s" - 18F.x{}^{7}/\!\!s" - 14M.(2) \\ {}^{1}'' - 8F.x{}^{5}/\!\!s" - 18M.(1) \\ {}^{1}'' - 8F.x{}^{1}/\!\!s - 14M.(1) \\ {}^{1}/\!\!4" - 12F.x{}^{1}/\!\!4" - 12M.(2) \\ {}^{1}/\!\!4" - 12F.x{}^{1}/\!\!s" - 18M.(2) \\ {}^{1}/\!\!4" - 7F.x{}^{5}/\!\!s" - 18M.(2) \\ {}^{1}/\!\!4" - 7F.x{}^{5}/\!\!s" - 18M.(2) \\ {}^{1}/\!\!4" - 7F.x{}^{5}/\!\!s" - 18M.(1) \\ \end{array}$					
41224 41226 50449 1027 1037 1041 43892 30902 32136 1105 1106 1107 1119 1111	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037 Long jaws (3) for 1041 Long jaws (3) for 1041 572 mm legs for 1062 241 mm legs for 1062 2114 mm legs for 1062 203 mm legs for 1070 711 mm legs for 1070 864 mm legs for 1070 Accessories	8010 8012 8013 8015 8017 8018 8019 8020 8021 8023 8024 8025 8027 8028 8029	$\begin{array}{l} {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 13 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 11 \; {\rm M.} \; (2) \\ {}^{1}'' - 14 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 18 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 10 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 9 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 9 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}'' - 8 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 12 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 7 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 18 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 7 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s'} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} -$					
41224 41226 50449 1027 1037 1041 43892 30902 32136 1105 1106 1107 1111 1113	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037 Long jaws (3) for 1041 Long jaws (3) for 1154 572 mm legs for 1062 241 mm legs for 1062 114 mm legs for 1062 203 mm legs for 1070 711 mm legs for 1070 864 mm legs for 1070 Accessories Special puller forcing screw	8010 8012 8013 8015 8017 8018 8019 8020 8021 8023 8024 8025 8027 8028 8029 8036	$\begin{array}{l} {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 13 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 11 \; {\rm M.} \; (2) \\ {}^{1}'' - 14 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 18 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 10 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 9 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 9 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}'' - 8 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 12 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 7 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 18 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 7 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 5 \; {}^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'' - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm s''} - 14 \; {\rm F.} \; {\rm X} \; 1'$					
41224 41226 50449 1027 1037 1041 43892 30902 32136 1105 1106 1107 1111 1113	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037 Long jaws (3) for 1041 Long jaws (3) for 1154 572 mm legs for 1062 241 mm legs for 1062 2114 mm legs for 1062 203 mm legs for 1070 711 mm legs for 1070 864 mm legs for 1070 Accessories Special puller forcing screw Speed crank	8010 8012 8013 8015 8017 8018 8019 8020 8021 8023 8024 8025 8027 8028 8029 8036 8038	$\begin{array}{l} {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm z''} - 13 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 11 \; {\rm M.} \; (2) \\ {}^{1}'' - 14 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 18 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 10 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 9 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{1}'' - 8 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 18 \; {\rm M.} \; (1) \\ {}^{1}'' - 8 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 12 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 12 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 7 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 7 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 5^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5^{1}/{\rm s'} \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5^{1}/{\rm s'} \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5^{1}/{\rm s'} \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm H.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{$					
41224 41226 50449 1027 1037 1041 43892 30902 32136 1105 1106 1107 1111 1113 24832 24814 27198	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037 Long jaws (3) for 1041 Long jaws (3) for 1054 572 mm legs for 1062 241 mm legs for 1062 2114 mm legs for 1062 203 mm legs for 1070 711 mm legs for 1070 864 mm legs for 1070 Accessories Special puller forcing screw Speed crank	8010 8012 8013 8015 8017 8018 8019 8020 8021 8023 8024 8025 8027 8028 8029 8036	$\begin{array}{l} {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 13 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 11 \; {\rm M.} \; (2) \\ {}^{1}'' - 14 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 18 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm a''} - 16 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm a''} - 10 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 9 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm M.} \; (1) \\ {}^{1}'' - 8 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm a''} - 12 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm a''} - 12 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm a''} - 7 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm a''} - 7 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5 \; {\rm 1'}/{\rm c} \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm H.} \; (1) \\ {}^{1}/{\rm c''} - 14 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm H.} \; (1) \\ {}^{1}/{\rm c''} - 14 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm H.} \; (1) \\ {}^{1}/{\rm c''} - 14 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm H.} \; (1) \\ {}^{1}/{\rm c''} - 14 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm H.} \; (1) \\ {}^{1}/{\rm c''} - 14 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm H.} \; (1) \\ {}^{1}/{\rm c''} - 14 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm H.} \; (1) \\ {}^{1}/{\rm c''} - 14 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm H.} \; (1) \\ {}^{1}/{\rm c''} - 14 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm H.} \; (1) \\ {}^{1}/{\rm c''} - 14 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm H.} \; (1) \\ {}^{1}/{\rm c''} - 14 \; {\rm F.} \; {\rm X} \; {\rm 1''} - 14 \; {\rm F.} \; (2) \\ {}^{1}/{\rm c''} - 12 \; {\rm A''} \; {\rm 1''} - 14 \; {\rm A''} \; {\rm 1''} - 14 \; {\rm A''} \; {\rm 1''} - 14 \; {\rm A''} \; {\rm 1''} - 14 \; {\rm A''} \; {\rm 1''} - 14 \; {\rm A''} \; {\rm 1''} - 14 \; {\rm A''} \; {\rm 1''} - 14 \; {\rm A''} \; {\rm 1''} - 14 \; {\rm A''} \; {\rm 1''} - 14 \; {\rm A''} \; {\rm 1''} - $					
41224 41226 50449 1027 1037 1041 43892 30902 32136 1105 1106 1107 1111 1113 24832 24814 27198 29595	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037 Long jaws (3) for 1041 Long jaws (3) for 1054 572 mm legs for 1062 241 mm legs for 1062 2114 mm legs for 1062 203 mm legs for 1070 711 mm legs for 1070 864 mm legs for 1070 Accessories Special puller forcing screw Speed crank Speed crank	8010 8012 8013 8015 8017 8018 8019 8020 8021 8023 8024 8025 8027 8028 8029 8036 8038	$\begin{array}{l} {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm z''} - 13 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 11 \; {\rm M.} \; (2) \\ {}^{1}'' - 14 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 18 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 10 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 9 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{1}'' - 8 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 18 \; {\rm M.} \; (1) \\ {}^{1}'' - 8 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 12 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 12 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 7 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 7 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 5^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5^{1}/{\rm s'} \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5^{1}/{\rm s'} \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5^{1}/{\rm s'} \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm H.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{$					
41224 41226 50449 1027 1037 1041 43892 30902 32136 1105 1106 1107 1111 1113 24832 24814 27198 29595 28228	17¹/₂ ton 2-jaw puller head 30 ton 2-jaw puller head 50 ton 2-jaw puller head Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Combination 2/3-jaw puller Long jaws (3) for 1037 Long jaws (3) for 1041 Long jaws (3) for 1054 572 mm legs for 1062 241 mm legs for 1062 2114 mm legs for 1062 203 mm legs for 1070 711 mm legs for 1070 864 mm legs for 1070 Accessories Special puller forcing screw Speed crank	8010 8012 8013 8015 8017 8018 8019 8020 8021 8023 8024 8025 8027 8028 8029 8036 8038	$\begin{array}{l} {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm z''} - 13 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 11 \; {\rm M.} \; (2) \\ {}^{1}'' - 14 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 18 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 10 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{7}/{\rm s''} - 9 \; {\rm M.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{1}'' - 8 \; {\rm F.} \; {\rm X} \; {}^{5}/{\rm s''} - 18 \; {\rm M.} \; (1) \\ {}^{1}'' - 8 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 12 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 12 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 7 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 7 \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (2) \\ {}^{1}/{\rm s''} - 5^{1}/{\rm s} \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5^{1}/{\rm s'} \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5^{1}/{\rm s'} \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm M.} \; (1) \\ {}^{1}/{\rm s''} - 5^{1}/{\rm s'} \; {\rm F.} \; {\rm X} \; {}^{1}/{\rm s''} - 14 \; {\rm H.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{\rm s''} - 16 \; {\rm F.} \; (2) \\ {}^{5}/{\rm s''} - 18 \; {\rm F.} \; {\rm X} \; {}^{3}/{$					



#### PROTECT YOURSELF AND YOUR EQUIPMENT.

**Power Team protective blanket** – Our blankets are designed to contain broken or lying parts from the most extreme forces, thus resulting in a much safer work environment.


**Testing results** – In our lab, this style of blanket held the parts of a necked-down grade 8 bolt, which shattered in a 100 ton center-hole hydraulic cylinder. The blanket sustained no visible damage when shot with a force and impact that shattered safety glasses!

- Effectively contain broken or flying parts from the most extreme pulling, pressing, pushing or stressing forces.
- Ideal for use with pullers and forcing presses.
- Made of see-through, high-tensile, tear resistant material.
- Unlike rigid, fixed guards, these blankets can be wrapped and strapped around a job.
- The clear protective blankets allow you to visually monitor the job from start to finish.
- Protective blankets come in a carrying/storage pounch to reduce aging caused by prolonged exposure to light.




Order No.	Size (mm)	Number of Straps	Wt. (kg)
PB1230C	305 x 762	2	1,3
PB2036C	508 x 914	2	1,9
PB2860C	711 x 1.524	3	4,2
PB3372C	838 x 1.829	3	5,3
PB44120C	1.118 x 3.048	4	10,9
PB51156C	1.295 x 3.962	4	15,5

Note: Custom sizes are available on a special order basis. Please consult factory.





- Rugged, 16 gauge (1,6 mm) steel construction with fully arc welded seams for extra strength and weather protection.
- Full length piano hinges, mating cover to body, protect against weather and theft.
- Single or double latch security tabs for padlocks.
- Mechanical cover supports, two 57 mm high skids.
- Fold-down 19 mm pipe handles on each end of chest.
- Pre-drilled for optional casters, which enhance mobility.
- Durable baked enamel finish.





And Security Chests







## UNIVERSAL PULLERS

55 Ton Enforcer 55



#### **ENFORCER 55**

- Hydraulic lift system for easy, precise position of puller.
- Unique dual pump arrangement: Low pressure pump positions, holds and opens jaws
  The high pressure pump advances and retracts the pushing cylinder without releasing
  clamped jaws.
- 3 Hydraulically-actuated jaws. Cylinder moves in or out to provide a safe, secure grip on workpiece.
- Puller can be assembled in 2 or 3 jaw configurations.
- 5 Choice of cylinder with a 159 mm or 337 mm stroke.
- 6 Self-centering: Center cylinder on work; puller jaws will automatically grip work evenly.
- Super Grip-O-Matic® feature means the harder the pull, the tighter the puller jaws grip. No chains or cages required to keep puller jaws from slipping or springing off the part being pulled.
- 8 Guards at pinch points protect operator.
- 9 Cart's swivel casters give ease of mobility.
- 10 Large wheels make movement of cart easy.
- Puller can be mounted on cart 90 degrees to right or left of puller cart centerline, permitting use in tight quarters, such as between machinery.

#### **Pushing Adapters**

Order No.	A (mm)	B (mm)	Qty.**	
251002	69,9	69,9	1	$\begin{array}{c c} & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ & & & \\$
350593†	69,9	152,4	2	
350594	69,9	76,2	1	
350637	69,9	254	1	

\*\* Number of adapters supplied with each Enforcer.

	8 7 10
s jaws. easing	
rip	

#### **Conversion kit**

No. 251468 – Kit converts PH553C series to PH553CL series. Jaws are 305 mm longer. Kit contains three jaws and six straps with guards. Wt., 114 kg.

Note: Four cylinder extensions (not pictured) are included. The included lifting eyes (not pictured) permit use of an overhead crane to raise entire assembly.

	Min.	Reach Min.	Max.	Reach Max.	Overall	CyL		Prod.		Puller Jaw Ti Dimensions	
Order No.	Spread (mm)	Spread (mm)	Spread (mm)	Spread (mm)	Length* (mm)	Stroke (mm)	Power Source Requirements	Wt. (lbs.)	A (mm)	B (mm)	C (mm)
PH553C	101,6	559	1.219	356	2.286	159	115 V, 60Hz, 25 Amp Cap.	339	22	32	48
PH553C13	101,6	381	1.219	178	2.286	337	115 V, 60Hz, 25 Amp Cap.	352			
PH553CL13*	63,5	651	1.149	559	2.591	337	115 V, 60Hz, 25 Amp Cap.	379	1 ( )	\ <u>~</u>  c	
PH553C-230	101,6	559	1.219	356	2.286	159	230 V, 50/60 Hz, 15 Amp Cap.	339	\ \	1	<b>1</b> ✓
PH553C13-230	101,6	381	1.219	178	2.286	337	230 V, 50/60 Hz, 15 Amp Cap.	352			
PH553CL-230*	63,5	829	1.149	737	2.591	159	230 V, 50/60 Hz, 15 Amp Cap.	366			В
PH553CL13-230*	63,5	651	1.149	559	2.591	337	230 V, 50/60 Hz, 15 Amp Cap.	379		→ A	<b>←</b> Å
Protective blankets a	available	, see pa	ge 151.								

<sup>\*</sup> Long Jaws

**Note:** Cart and Puller (cart width is 813 mm)
See other pulling attachments on page 135



<sup>†</sup> Only 1 for units with 337 mm stroke.

## UNIVERSAL PULLERS

100 Ton
Enforcer 100





An ideal puller for steel mills, mines, oil fields, utility projects, paper mills, construction sites, railroads, airline shops, shipyards or anywhere else where large equipment and machinery pose tough maintenance challenges.


#### "Enforcer 100" universal puller -

No. PH1002-220 – 100 ton, 2-jaw universal hydraulic puller. Includes: 2-jaw Grip-O-Matic® puller, PE552S-50-220 2-speed electric/hydraulic power unit, C10010C 100 ton hydraulic cylinder with 260 mm stroke and six adapters. Wt., 404 kg.

**No. PH1002J –** Same as PH1002-220, but without hydraulic power unit. Wt., 375 kg.


**No. PE552S-50-220 –** Pump only. 0,84 KW, 220 volt, 50Hz/60Hz, single phase, draws 15 amps at full load. Also available in 115 volt, 60Hz, order No. **PE552S** 

Note: For 115 volt, 60Hz applications, Order No. PH1002



#### **ENFORCER 100**


- Adjustable jaws mean they always pull on a flat surface. Retaining chain holds jaws in place during positioning.
- Grip-O-Matic® feature means jaws grip progressively tighter as morepulling force is applied.
- 3 100 ton hydraulic cylinder is single-acting, spring return type with a maximum working pressure of 700 bar.
- 4 Lifting bracket allows puller to be lifted if the workpiece center is more than 914 mm off the floor.
- Adjusting screw allows operator to move vertical position of the puller.
- Spring loaded feature means Enforcer 100 will align itself on uneven pulls.
- 7 Hydraulic pump is a 2-stage, high pressure unit controlled by remotehand switch with 7,6 m cord.
- 8 Tow bar provides puller with plenty of mobility.
- 9 Pushing adapters have a diameter of 105 and 63,5 mm.



#### Ram extensions

Order No.	Adapter Type	Amount included w/puller	J (mm)	K (mm)	L (mm)	M (mm)	N (mm)
44745	Push	1	105	_	343	63,5	_
44766	Ext.	4	105	_	_	_	203
30304	5 Push	1	105	79,4	_	_	_

	Min.	Reach Min.	Max.	Reach Max.				Cylinder	Vertical		Max.		
Order No.	Spread A (mm)	Spread B (mm)	Spread C (mm)	Spread D (mm)	E	er Jaw ' F (mm)	Tip G (mm)	Height H (mm)	Stroke Adjust. (mm)	Overall Length (mm)	Thickness Workpiece (mm)	Wheel Dia. (mm)	Power Source Requirements
PH1002-220 PH1002J	381 381	1.067 1.067	1.219 1.219	864 864	25,4 25,4	,	127 127	260 260	305-914 305-914	2.388 2.388	305 305	260 260	220 V, 50 Hz, 13 Amp C



Cap.

## ROLLER BEARING PULLER / INSTALLER

(Railroad Edition)
100 Ton Pulling Capacity


- Quickly remove or install tapered roller bearings.
- Designed with cooperation of major bearing manufacturers.
- It's a fast, simple, one-man operation with 100-ton of pulling force provided.
- Completely portable for easy, convenient positioning and out-of-the-way storage.
- The standard in most wheel shops.

#### **Universal railroad axle journal roller bearing puller/installer –** For years,

the standard in most wheel shops. Power Team now has four models to choose for greater flexibility. With both sling and jack models available and two pumps to choose from, you can tailor the unit to match your needs. With the proper equipment and know-how, removal and installation of axle journal roller bearings takes an absolute minimum of time and effort.

Each unit will service a full line of bearings with rotating end caps, from class B thru GG. No other method can match Power Team's simplicity. Removal is very easy. Simply remove the end caps, slip the pulling shoe between the bearings and the wheel, actuate the pump, and in seconds, 100 tons of pulling force removes the bearing. Installation is just as easy! Each unit is CSA certified (LR19814) and comes complete with a heavy-duty 100-ton hydraulic cylinder, 10,000 P.S.I. (700 bar) pump with remote control solenoid valve, hydraulic pressure gauge (No. 11543), a pulling shoe and installing tube.

Order No.	Model Type	Cylinder Type	Valve Type	Pı H.P	ımp Informa Phase	ation Voltage
PR2100J <sup>†</sup>	Jack	Double Acting	Solenoid	2**	1	115 or 230*/60Hz
PR3100J <sup>†</sup>	Jack	Double Acting	Solenoid	3	3	230 or 460*/60Hz
PR2100S <sup>†</sup>	Sling	Double Acting	Solenoid	2**	1	115 or 230*/60Hz
PR3100S <sup>†</sup>	Sling	Double Acting	Solenoid	3	3	230 or 460*/60Hz



<sup>\*\*</sup> The 1,49 kW., 115 volt requires 30 amp service.

For 220V/50Hz/Single-phase: Order PR2100J -50-220

For 380V/50Hz/3-phase: Order PR3100J -50-380 (Suitable for 415V/50Hz/3 phase)

460V/60Hz/3-phase suitable for 440V/50Hz/3-phase.




Our roller bearing pullers are ideal for replacing tough, worn-out bearings on RR freight cars.



The photo above shows the Universal Puller in position on the roller bearing assembly, which is ready for removal.

**Tooling order information -** IMPORTANT...This tooling chart applies only to standard AAR configurations for freight care applications. In order to provide adapters needed to service housing-type locomotive and passenger car bearings, as well as metric bearings, Power Team must be provided with the following information: bearing manufacturer's name and general arrangement drawing number, size of bearing to be serviced, railroad name and location and part numbers of adapters already in your possession if you currently own a Puller/Installer.



<sup>\*\*</sup> Screws are supplied with the guide tube and should be ordered as replacements only.








		Class and size(mm) of bearing assembly to be serviced										
Tool Description	Class B 108 x 203 (No.)	Class C 127 x 229 (No.)	Class D 140 x 254 (No.)	Class E 152 x 279 (No.)	Class EE 140 Axle. (No.)	Class EE 152 Axle. (No.)	Class F 165 x 305 (No.)	Class G 178 x 305 (No.)	Class G 165 Axle. (No.)	Class GG 165 Axle. (No.)		
Pulling Shoe	No. 4208	45 is includ	ded as part	of basic ma	achine – Do	Not Order		420846	420846	420846		
Pulling Shoe Insert Adapter	30522	30512	30521	30520	30520	30519	30519	_	_	_		
Guide Tube & Cap Screw Assembly	253313	253314	253317	253318	253316	253327	253320	253321	253319	253323		
Cap Screw**	253156	253349	253308	253155	253307	253308	253310	253326	253309	253309		
Guide TubeNo. Adapter	23934	21248	21248	21247	21247	21247	21247	21247	21247	21247		
Installing Tube	No. 4208	45 is includ	ded as part	of basic ma	achine – Do	Not Order		30417	30417	30417		
Installing Tube Adapter Ring	21242	21258	21256-1	21255-1	21255-1	21257-1	21257-1	30586	30585	30585		

**Note:** Adapters listed above are for servicing the following roller bearing assemblies: Brenco "Crown-Taper", New Departure-Hyatt "Hy-Roll Taper", SKF "Expediter" and Timken "AP".

<sup>\*\*</sup> Screws are supplied with the guide tube and should be ordered as replacements only.



		Ca	pacity		Speed								
Order No.	Stroke (mm)	Pull (Tons)	Inst. (Tons)	Advance (mm/min.)	Pull (mm/min.)	Inst. (mm/min.)	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	Weight (kg)
PR2100J	394	100	68	900	81	113	813	383	1.059	912	1.981	1.493	528
PR3100J	394	100	68	900	81	113	813	383	1.059	912	1.981	1.493	520
PR2100S	394	100	68	900	81	113	619	279	_	1.283	1.632	985	455
PR3100S	394	100	68	900	81	113	619	279	_	1.283	1.632	985	458




## PLC SYNCHRONOUS LIFT

## POWER TEAM® PLC Synchronous Lift and Lowering System

- For precise controlled hydraulic movement and weighing of Oil Rig Platforms, Heavy Structures, Vessels & Machineries etc.
- It uses feedback from multiple sensors to control lifting, lowering and positioning of any large, heavy or complex structure regardless of weight distribution.
- Synchronous lifting reduces the risk of bending, twisting or tilting due to uneven weight distribution or load-shifts between the lift points.
- Programmable, failsafe monitoring & safety alarms of system include operating parameters, such as displacement accuracy, lifting velocity, valve response errors.

(Optional: Data logging, load tilting, remote/online system troubleshooting)



#### **Features**

- Computerized PLC System c/w Touch Screen Panel
- Control from 4 to 60 Jacking Points
- 10 to 1000 Ton on each Jacking Point
- Precision Accuracy at +/- 1mm full scale
- Pressure / Load Display on Control Panel
- Displacement Display on Control Panel
- Linkage to Data Logger and Printer
- Standard Hydraulic Components
- System incorporates emergency alarms with auto-stop features

#### **Option**

- Basic System with Analogue Gauge
- Heat Exchanger for continuous operation
- Available up to 80 jacking points on request








**Control Panel** 



### **Stage Lifting and Lowering System**







	Order No.	Maximum Cylinder Capacity	Cylinder Oil Capacity	Cylinder Effective Area						D	imension	s in mm.					
L	order No.	Push (Ton)	Push (cu. cm.)	Push (sq. cm.)	Stroke (mm)	А	В	C	D	E	F	G	Н	ı	J	К	L
	PSL-506	50	1,132	71,2	150	460	127	75	157	Ø24	150	300	10	5	620	150	300
	PSL-1006	93	2.242	133,1	150	500	175	75	205	Ø24	200	300	10	5	720	150	300
	PSL-1506	139	3,334	197,9	150	532	210	130	240	Ø24	200	400	10	5	820	200	400
	PSL-2006	187	4.485	266,3	150	560	241	130	271	Ø24	200	400	10	5	820	200	400
	PSL-3006	272	5.920	387,8	150	670	273	195	313	Ø24	230	510	10	5	990	230	500

Note: Specifications subject to change

### **Stage Lifting System**

- Height of Lifting depends on Support and not Cylinder Stroke
- From 4 to 48 Jacking Points
- 50 to 300 Ton on each Jacking Point
- Option for Synchronized PLC Control System
- Option of Higher Capacity
- Option for Analogue Gauge or Digital Display

# CONSTRUCTION PROJECTS

## POWER TEAM Hydraulic System Solution Provider in specialized construction projects:-

- Synchronous Lifting, Lowering & Weighing Systems for precise controlled hydraulic movement & weighing of Oil Rig Platforms, Heavy Structures & Machineries etc.
- High Tonnage, Heavy Lifting & Supporting of Bridges, Buildings, Structures, Ship Segments, Heavy Equipment & Machineries etc.
- Stage Lifting Systems of Oil Storage Tanks, Generators, Turbine Covers etc. to elevated height.
- Integrated Hydraulic Systems for Bridge Construction Equipment: Formwork Travelers, Launching Gantries, Movable Scaffolding Systems etc.
- Foundation Testing, Pipe Jacking, Tunneling, Bridge Maintenance, Oil Rig Construction, Power Plant Construction, Port / Harbor Construction etc.

#### Typical Hydraulic Applications in Industrial, Building & Heavy / Civil Construction:

- Lifting / Lowering
- Erecting
- Pulling
- Supporting
- Weighing
- Hoisting
- Underpinning
- Testing

- Rraking
- Transportation
- Tensioning
- Load Testing

#### **Bridge Construction**

Bridge projects that become bigger and more demanding require POWER TEAM products and systems. Difficult lifting and holding applications above and below ground require POWER TEAM pumps and cylinders. New spanning projects and maintenance of current spanning structures are served by POWER TEAM portable high performance, high-pressure hydraulic tools & systems.










#### **Structure Jacking and Positioning**

POWER TEAM products have lifted large and small structures as well as precious historical buildings. A broad range of reliable lifting, pulling or positioning solutions powered by POWER TEAM pumps matches the products to the job requirement.

For precision synchronous lift & lowering of delicate structures, we offer computerized PLC system to control from 4 to 80 jacking points of up to 1,000 Ton capacity hydraulic cylinder each.





Weighing System of Oil Rig

#### **Post Tensioning & Stressing**

POWER TEAM Center Hole cylinders provide an array of options for strand cable tensioning, anchor bolts, forcing screws and pulling systems. They are long lasting, easy to use, corrosion resistant and are designed to withstand static loads.

POWER TEAM compact, light weight PE55 VANGUARD, Electric Hydraulic Pumps for long, trouble free life in most demanding work environments and excellent choice for rugged applications. For operating single- or double-acting cylinders or stressing jacks.

## CONSTRUCTION APPLICATIONS







### **Bridge Bearing Repair & Maintenance**

For decades, POWER TEAM has provided reliable lifting and holding systems for replacing bridge bearings. POWER TEAM products are designed to fit within your needs for compact solutions and critical maintenance.







#### **Building & Civil Construction**

POWER TEAM broad range of high tonnage hydraulic cylinders coupled with high performance high-pressure pumps has provided vast applications in lifting, testing, jacking, positioning solutions etc. Designed to work in some of the most difficult and harsh environments. Proven performance that meets your critical productivity timeline backed by reliable and proven reputation.








### **Construction Equipment Repair & Maintenance**

POWER TEAM offers a broad range of hydraulic and mechanical tools to keep your heavy equipment and machineries reliably operating. Tools include hydraulic pumps, cylinders, jacks, pullers, torque wrenches, nut splitters, floor cranes, shop presses, in-line flow testers etc.

## **ACCESSORIES**

### Seal Kits



Electric				
Powered Pump	Model	Repair	Viton	EPR
Order No.		Kit*	Seal Kit	Seal Kit
PE102-220	В	300651		300653
PE102A-220	В	300651		300653
PE104-220	В	300651		300653
PE172-50-220	А	300430		300648
PE172A-50-220	А	300430		300648
PE172M-50-220	Α	300430		300648
PE174-50-220	Α	300430		300648
PE174M-50-220	Α	300430		300648
PE182-50-220	С	300914		
PE183-2-50-220	С	300914		
PE183-50-220	С	300914		
PE183A-50-220	С	300914		
PE184-2-50-220	С	300914		
PE184-50-220	С	300914		

Air				
Powered Pump	Model	Repair	Viton	EPR
Order No.		Kit*	Seal Kit	Seal Kit
PA172	В	300430		300648
PA174	В	300430		300648
PA6	F	300805		
PA6-2	F	300848		
PA64	F	300883		
PA6A	F	300840		
PA6AM	F	300840		
PA6D	F	300844		
PA6D2	F	300850		
PA6DM	F	300844		
PA6DM-1	F	300844		
PA6DM-2	F	300850		
PA6M	F	300805		
PA6M-1	F	300831		
PA6M-2	F	300848		
PA6R	F	301030		
PA6RM	F	301030		
PA9	В	300949		
РА9Н	В	300949		



Couplers Order No.	Repair Kit*	Viton Seal Kit	EPR Seal Kit		
9795	209100	9796-V	9796-E		
9796	300826 & 209100	9796-V	9796-E		

Model	Repair Kit*
	300373
	300376
А	300404
В	300116
В	300147
А	300879
А	300608
А	300514
А	300620
	A B B A A

/alves Order No.	Model	Repair Kit*
9500		300451
9504		300451
9506		300451
9508		300451
9509		300451
511		300451
512	С	300835
519	С	300835
520		300451
552	В	300332
555	С	300835
556		300489
569		300605
570		300605
575	Α	300683
581	В	27345
582	В	300129
628	D	300571
632		300594
642		300592
644		300593

Torque Wrench	Seal Kit for	Seal
Order No.		Kit*
TWSD1	COMPLETE (Body & Multi-Swivel)	BSDAS010006
TWSD1	BODY only	BSDAS010007
TWSD3	COMPLETE (Body & Multi-Swivel)	BSDAS030006
TWSD3	BODY only	BSDAS030007
TWSD6	COMPLETE (Body & Multi-Swivel)	BSDAS060006
TWSD6	BODY only	BSDAS060007
TWSD11	COMPLETE (Body & Multi-Swivel)	BSDAS110006
TWSD11	BODY only	BSDAS110007
TWSD25	COMPLETE (Body & Multi-Swivel)	BSDAS250006
TWSD25	BODY only	BSDAS250007
TWLC2	COMPLETE (Body & Multi-Swivel)	DFTAS020004
TWLC2	BODY only	DFTAS020005
TWLC4	COMPLETE (Body & Multi-Swivel)	DFTAS040004
TWLC4	BODY only	DFTAS040005
TWLC8	COMPLETE (Body & Multi-Swivel)	DFTAS080004
TWLC8	BODY only	DFTAS080005
TWLC15	COMPLETE (Body & Multi-Swivel)	DFTAS150004
TWLC15	BODY only	DFTAS150005
TWLC30	COMPLETE (Body & Multi-Swivel)	DFTAS300004
TWLC30	BODY only	DFTAS300005
MULTI-SWIVEL (S1)	TWSD1/3 and TWLC2/4	DFTAS010004
MULTI-SWIVEL (S2)	TWSD6/11/25 and TWLC8/15/30	DFTAS020009

<sup>\*</sup> These seals come standard on all above products. Refer Parts List for correct model no. & more details.

## **ACCESSORIES**

Seal Kits



Cylinder	Seal	Viton
Order	Kit*	Seal
No.	AIL.	Kit
NO.		NIC
C51C	300404	300210
C53C		300210
C55C		300210
C57C	300404	300210
C59C		300210
C101C		300211
C102C		300211
C104C		300211
C106C		300211
C108C		300211
C1010C		300211
C1012C		300211
C1014C		300211
C1016C		300211
C151C	300453	300471
C152C	300453	300471
C154C	300453	300471
C156C	300453	300471
C158C	300453	300471
C1510C		300471
C1512C		300471
C1514C		300471
C1516C		300471
C251C		300213
C252C		300213
C254C	300147	
C254C		300213
		300213
C258C		
C2510C		300213
C2512C		300213
C2514C		300213
C552C		300215
C554C		300215
C556C	300114	300215
C5510C		300215
C5513C		300215
C756C	300647	300846
C7513C	300647	300846
C1002C	300112	300216
C1006C	300112	300216
C10010C	300112	300216
C55CBT		300210
C106CBT		300211
C1010CB1		
C256CBT		
C2514CBT		
R552C	300147	
R556C	300674	
R5510C	300674	
R1002C	300675	
R1006C	300675	—

43		
Cylinder	Seal	Viton
Order	Kit*	Seal
No.		Kit
R10010C	300675	_
R1502C	300676	
R1506C	300676	
R15010C	300676	
R2002C	300677	
R2006C	300677	_
R20010C	300677	
R2802C	300678	
R2806C	300678	
R28010C	300678	
R3552C	300679	
R3556C	300679	
R35510C	300679	
R4302C	300680	_
R4306C	300680	
R43010C	300680	
R5652C	300681	
R5656C	300681	_
R56510C	300681	_
R1002D	301042	_
R1006D	301042	_
R10010D	301042	_
R1502D	301043	
R1506D	301043	
R15010D		_
R2002D	301044	_
R2006D	301044	
R20010D		_
R2802D	301045	
R2806D	301045	
R28010D		
R3552D	301045	
R3556D	301046	
R35510D		
R4302D	301040	
R4306D	301047	
R43010D		
R5652D	301047	
R5656D	301048	
R56510D		
R552L		
	300674	
R556L	300674	
R5510L	300674	
R1002L	300675	_
R1006L	300675	
R10010L	300675	
R1502L	300676	
R1506L	300676	
R15010L	300676	

Cylinder	Seal	Viton
Order	Kit*	Seal
No.		Kit
R20010L	300677	
R2802L	300678	
R2806L	300678	_
R28010L	300678	_
R3552L	300679	_
R3556L	300679	_
R35510L	300679	_
R4302L	300680	_
R4306L	300680	_
R43010L	300680	_
R5652L	300681	_
R5656L	300681	_
R56510L	300681	_
RA202	300631	_
RA204	300631	_
RA206	300631	_
RA302	300632	_
RA304	300632	_
RA306	300632	_
RA552	300391	_
RA554	300391	_
RA556	300391	_
RA5510	300391	_
RA1002	300444	_
RA1006	300444	_
RA556L	300395	_
RA1006L	300396	
RD106	300017	_
RD1010	300017	
RD256	300118	
RD2514	300118	
RD556	300005	
RD5513	300005	
RD5518	300005	
RD8013	300410	
RD1006	300006	
RD10013	300006	
RD10020		
RD1506	300007	
RD15013		
RD15018	300007	
RD2006	300008	
RD20013	300008	
RD3006	300466	
RD30013		
RD4006	300467	
RD40013	300467	
RD5006	300468	
RD50013	300468	
RH102	300071	300221

Cylinder	Seal	Viton
Order	Kit*	Seal
No.		Kit
RH120	300657	_
RH121	300576	_
RH121T	300576	_
RH123	300576	_
RH202	300615	_
RH203	300069	300222
RH206	300615	_
RH302	300037	300223
RH306	300037	300223
RH503	300059	300225
RH603	300477	300476
RH606	300477	300476
RH1003	300485	300585
RH303	300077	300224
RH306D	300822	300224
RH3010	300625	
RH605	300269	300226
RH6010	300626	_
RH1001	300927	
RH1006	300295	300227
RH10010	300629	
RH1505	300154	300228
RH1508	300583	_
RH2008	300582	_
RHA306	300867	300868
RHA604D	300269	300226
RLS50	300454	_
RLS100	300455	
RLS200	300456	
RLS300	300457	_
RLS500S	300458	_
RLS750S	300459	_
RLS10005	300460	_
RLS15005	300461	
RP25	300628	
RP25 RP55	300628 300627	
		_ 
RP55	300627	
RP55 RSS101	300627 300010	_ _ _ _ _
RP55 RSS101 RSS202	300627 300010 300011	— — — — —
RP55 RSS101 RSS202 RSS302	300627 300010 300011 300297	
RP55 RSS101 RSS202 RSS302 RSS502	300627 300010 300011 300297 300292	
RP55 RSS101 RSS202 RSS302 RSS502 RSS1002	300627 300010 300011 300297 300292 300293	
RP55 RSS101 RSS202 RSS302 RSS502 RSS1002 RSS2503	300627 300010 300011 300297 300292 300293	
RP55 RSS101 RSS202 RSS302 RSS502 RSS1002 RSS2503 RSS1002	300627 300010 300011 300297 300292 300293 — 300578	
RP55 RSS101 RSS202 RSS302 RSS502 RSS1002 RSS2503 RSS1002I RT172	300627 300010 300011 300297 300292 300293 — 300578 300358	

R2002L

R2006L

300677

300677

RH108

300071 300221

<sup>\*</sup> These seals come standard on all above cylinders. Refer Parts List for correct model no. & more details.

## **MEASUREMENTS**/ **SPECIFICATIONS**

Manufacturing Standards



### INTERNATIONAL **QUALITY STANDARD**

Power Team's commitment to quality is evident in everything we do, from raw material receipt to how we support our customers years after they purchase our products. Power Team is registered to ISO 9001: 2000 international quality standard. ISO 9001: 2000 requires compliance with standards for management, administration, product development, manufacturing and continual improvement. Our Registration verifies that Power Team has adopted and maintains documentation for processes ranging from suppliers to customers, inspection, handling, and training, ISO 9001 also requires periodic internal and external audits to ensure all aspects of work affecting quality control are monitored. This always has been, and will continue to be, our philosophy. That's our guarantee to you.

#### **ASME B30.1**

Power Team hydraulic cylinders fully comply with the criteria set forth in the American Society of Mechanical Engineers standard ASME B30.1:

1. Our cylinders are designed to have a minimum of a 2-to-1 safety factor on typical material yield strength; Each cylinder is tested at 125 percent of rated pressure at full travel and is inspected to assure functionality and freedom from leaks.

#### **ASME B40.1**

Power Team heavy-duty pressure gauges are designed in accordance with the recommendations set forth in the American Society of Mechanical Engineers standard ASME B40.1, Grade B.

## C € CE MARK

Power Team is committed to designing, manufacturing, and marketing products that meet or exceed the needs of the customers we serve. Power Team supplies a Letter of Incorporation or a Declaration of Conformity and CE Marking for products that conform with European community directives.

#### **IJ100**

Power Team hoses meet the criteria set forth in the Material Handling Institute's specification #IJ100 for hydraulic hose. Under the procedures outlined in this standard, hydraulic hose shall:

- 1. Have an average minimum life of 30,000 cycles at full rated capacity.
- 2. Have a minimum burst pressure of at least twice the rated operating pressure.



Where specified, Power Team electric power pump assemblies meet the design, assembly, and test requirements of the Canadian Standards Association.

Note: If CSA certification is required, it must be requested at the time the pump is ordered.

#### NEMA

Where specified, Power Team electric power pump assemblies meet the design, assembly, and test requirements of NEMA 12, a National Electrical Manufacturers' Association standard relating to electrical components used to resist moisture and dust.

#### **POWER TEAM PRODUCT DESIGN CRITERIA**

All Power Team brand hydraulic components are designed and/or tested to be safe for use at maximum operating pressures of 700 bar (10,000 psi) unless otherwise specifically noted.

#### **OUALITY ASSURANCE**

All of our hydraulic cylinders are subjected to quality checks during production. All steel bar is certified and has material traceability to the mill. Before leaving the factory, all cylinders are pressure tested to 875 bar (12,500 psi), except the RT series which are tested to 700 bar (10,000 psi) to insure on-the-job reliability. We have made every effort to include the latest specifications for our products in this catalog. Please call the Power Team factory for the most current product specifications. The Power Team Lifetime Marathon Warranty is described in more detail on page 163 of this catalog.



MARATHON™ WARRANTY

# POWER TEAM®

All Power Team products and parts, with the exception noted below, are warranted against defects in materials and workmanship for the life of the product or part. (The life of the product or part is defined as that point in time when it no longer functions due to normal wear.) This warranty does not cover any product or part that has been worn out, abused, heated, ground or otherwise altered, used for a purpose other than that for which it was intended or used in a manner inconsistent with any instructions regarding its use. Chains, batteries, electric motors, gas engines, knives and cutter blades which are sold with Power Team products are not covered by this warranty. All electric motors and gas engines are separately warranted by their manufacturer under the conditions stated in their separate warranty.

Power Team's electronic products are warranted against defects in material and workmanship for one year.

To qualify for warranty consideration, return the Power Team product, freight prepaid, to a Power Team authorized repair center or to the Power Team factory. If any product or part manufactured by Power Team is found to be defective by Power Team, in its sole judgement, Power Team will, at its option, either repair or replace such defective product or part and return it via best ground transportation, freight prepaid. THIS REMEDY SHALL BE THE EXCLUSIVE REMEDY AVAILABLE FOR ANY DEFECTS IN THE PRODUCTS OR PARTS MANUFACTURED AND SOLD BY POWER TEAM OR FOR DAMAGES RESULTING FROM ANY OTHER CAUSE WHATSOEVER, INCLUDING WITHOUT LIMITATION, POWER TEAM'S NEGLIGENCE. POWER TEAM SHALL NOT, IN ANY EVENT, BE LIABLE TO ANY BUYER FOR CONSEQUENTIAL OR INCIDENTAL DAMAGES OF ANY KIND, WHETHER FOR DEFECTIVE OR NON-CONFORMING GOODS, NEGLIGENCE, ON THE BASIS OF STRICT LIABILITY OR FOR ANY OTHER REASON.

Power Team's warranty is expressly limited to persons who purchase Power Team's products or parts for the resale or use in the ordinary course of the buyer's business.

THIS WARRANTY IS EXCLUSIVE, AND POWER TEAM MAKES NO OTHER WARRANTY OF ANY KIND WHATSOEVER, EXPRESSED OR IMPLIED, WITH RESPECT TO THE PRODUCTS MANUFACTURED AND SOLD BY IT, WHETHER AS TO MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE, OR ANY OTHER MATTER. No agent, employee or representative of Power Team has any authority to bind Power Team to any affirmation, representation or warranty concerning Power Team products or parts, except as stated herein.

The purpose of this exclusive remedy shall be to provide the buyer with repair or replacement of products or parts manufactured by Power Team found to be defective in materials or workmanship or negligently manufactured. This exclusive remedy shall not be deemed to have failed of its essential purpose so long as Power Team is willing and able to replace said defective products or parts in the prescribed manner.

## Total Customer Satisfaction is Our Driving Force



**INTERNATIONAL** QUALITY **STANDARD** 









106-127



128-155



World Headquarters The Americas **Customer Service Center** 

5885 11th Street Rockford, Illinois 61109 Tel: 1-815-874-5556

Customer Service/ Order Entry Tel: 800.541.1418 Fax: 800.288.7031

**Technical Services** Tel: 800.477.8326 Fax: 800.765.8326 info@powerteam.com

European **Customer Service Center** 

Albert Thijsstraat 12 6471 WX Eygelshoven The Netherlands Tel: 31 (45) 5678877 Fax: 31 (45) 5678878 infoeurope@powerteam.com infoasia@powerteam.com

Asia Pacific **Customer Service Center** 

Singapore 629563 Singapore Tel: (65) 6265 3343 Fax: (65) 6265 6646

7 Gul Circle

**Customer Service Cente** 

No. 1568 Hua Shan Road **Treasury Building** 9th Floor Shanghai 200052, China Tel: 86 (21) 2208.5888 86 (21) 2208.5660

Fax: 86 (21) 2208.5682 infochina@powerteam.com

- Industries Served:ConstructionSteel & Rolling Mills
- Ship Building & Ship Repairing Mining & Quarrying Manufacturing

- Oil & Gas, Petro-chemical
  Heavy Machineries
  Power Plants
  Electrical

- Transportation Maintenance
- Aerospace
  Test & Quality Assurance
- RailroadMarine Offshore

## Industrial Applications:LiftingMetal Fabrication

- Assembly & Manufacturing
  Forming
  Research & Development

- Load & Tension MeasurementsPushing & PullingClamping & Holding

- Pressing, Bending & Spreading
  Straightening
  Quality Control
  Punching

- BoltingHydraulic Power

#### Distributed by:

## > Power Team®

**World Class** Hydraulic **Tools** 



POWERTEAM.COM

SPX HYDRAULIC TECHNOLOGIES spxhydraulictech.com



